

## **2023 Dugout and Water Well Monitoring Program Clean Harbors Class 1 Waste Management Facility Ryley, Alberta**



PRESENTED TO  
**Clean Harbors Canada Inc.**

FEBRUARY 28, 2024  
ISSUED FOR USE  
FILE: 704-SWM.SWOP04810-01

---

This page is intentionally left blank.

## EXECUTIVE SUMMARY

### Foreword

Tetra Tech Canada Inc. (Tetra Tech) was retained by Clean Harbors Canada Inc. (Clean Harbors) to sample all in-use dugouts and water wells located within a 1.6 km radius of the Ryley Class I Hazardous Waste Facility in Ryley, Alberta.

This sampling program is required by Alberta's *Environmental Protection and Enhancement Act* (EPEA). The facility operates under Alberta Environment and Protected Areas (EPA), in accordance with EPEA Approval No. 10348-03-01 (Appendix A). The program includes the surface water testing of all in-use dugouts and water wells, as identified during the October 1996 baseline sampling program and subsequent updates. The permit to operate defines "in-use" as stored water used for human consumption, cooking, washing, and gardening or livestock purposes. An additional two dugouts (9A, 23) were sampled in 2023 that are now within the 1.6 km radius due to the recent northward expansion of Clean Harbors Ryley Industrial Waste Management Facility. In addition, groundwater wells within a 1.6 km radius of the facility were reviewed and assessed for possible sampling as per the most recent Approval.

Twenty-one dugouts were inspected and sampled during the 2023 dugout sampling program, which is the 28<sup>th</sup> annual sampling event, including the baseline event in 1996. The baseline sampling program is detailed in the report titled *Water Sampling and Testing Program*. All annual dugout sampling has taken place in October.

### Discussion and Recommendations

Analytical results of the dugout sampling program conducted in October 2023 indicate that the Ryley Class I Hazardous Waste Facility does not appear to be adversely impacting water quality in dugouts within the 1.6 km radius sampled. No water wells were accessible for sampling.

Some parameters analyzed in 2023 exhibited an upward trend in concentrations in one or more dugouts relative to historical baseline values, but the majority of concentrations were within the historical ranges for those parameters.

Select parameters had historically high values or concentrations for specific parameters during the 2023 sampling and should continue to be monitored and evaluated in future sampling events.

The following conclusions are based on the 2023 dugout and water well monitoring program:

- Analytical results of the dugout and water well monitoring program conducted in October 2023 indicate that the Ryley Class I Hazardous Waste Facility does not appear to be adversely impacting water quality in dugouts within a 1.6 km radius.
- Some parameters analyzed in 2023 exhibited new maximum observed values in one or more dugouts relative to historical baseline values, but the majority of concentrations were within the historical ranges for those parameters.
- Select parameters having historically high values or concentrations during the 2023 monitoring event should continue to be monitored and evaluated in future sampling events.
- No water wells were located within the 1.6 km radius of the site that could be included in the sampling program.
- A similar monitoring program is recommended for October 2024, as part of the ongoing site Approval compliance process.

- Each landowner should be forwarded a copy of the water chemistry analysis report pertaining to the dugout(s) sampled on their property once the 2023 report is finalized and submitted to AEPA.
- Area water wells should be reassessed every five years to confirm if any new wells have been established and should be included in the annual dugout and water well monitoring program.

## TABLE OF CONTENTS

---

<b>1.0 INTRODUCTION</b>	<b>1</b>
<b>2.0 FIELD SAMPLING METHODS</b>	<b>1</b>
2.1 Landowner Summary	1
2.2 Sampling Procedure	2
2.3 Quality Control and Quality Assurance	4
<b>3.0 REVIEW OF WATER WELLS IN SEARCH RADIUS</b>	<b>5</b>
<b>4.0 FINDINGS</b>	<b>7</b>
<b>5.0 DISCUSSION</b>	<b>10</b>
5.1 Dugout Monitoring	10
5.2 Surrounding Area Water Well Review Summary	11
<b>6.0 CONCLUSIONS AND RECOMMENDATIONS</b>	<b>11</b>
<b>7.0 CLOSURE</b>	<b>12</b>

## LIST OF TABLES IN TEXT

---

Table A: Landowner Information	2
Table B: Sample Location Information	2
Table C: Water Wells Eliminated from Search Radius	5
Table D: Field Verification of Water Wells	6
Table E: Dugout and Water Well Monitoring Summary	8

## APPENDIX SECTIONS

---

### TABLES

Table 1.1 to Table 1.23	Chemical Analytical Results
Table 2	Duplicate 1 Chemical Analytical Results
Table 3	Duplicate 2 Chemical Analytical Results
Table 4	Historical and 2023 Precipitation Data - Total Precipitation (mm)

### FIGURES

Figure 1	Dugout Sampling Location Plan
Figure 2	Parameters with 2023 Maximum Value Trend Charts

## APPENDICES

Appendix A	Regulatory Approval - Alberta Environment And Parks EPEA Approval No.10348-03-01
Appendix B	Tetra Tech's Limitations on the Use of This Document
Appendix C	Laboratory Certificate of Analysis
Appendix D	Historical Dugout Chemical Analytical Results
Appendix E	Selected Site Photographs

### **LIMITATIONS OF REPORT**

This report and its contents are intended for the sole use of Clean Harbors Canada Inc. and their agents. Tetra Tech Canada Inc. (Tetra Tech) does not accept any responsibility for the accuracy of any of the data, the analysis, or the recommendations contained or referenced in the report when the report is used or relied upon by any Party other than Clean Harbors Canada Inc. or for any Project other than the proposed development at the subject site. Any such unauthorized use of this report is at the sole risk of the user. Use of this report is subject to the terms and conditions stated in Tetra Tech Canada Inc.'s Services Agreement. Tetra Tech's Limitations on the Use of This Document are provided in Appendix B of this report.

## 1.0 INTRODUCTION

Tetra Tech Canada Inc. (Tetra Tech) was retained by Clean Harbors Canada Inc. (Clean Harbors) to sample all in-use groundwater wells and dugouts located within a 1.6 km radius of the Ryley Class I Hazardous Waste Facility in Ryley, Alberta. The sampling program is required by Alberta's *Environmental Protection and Enhancement Act* (EPEA). The facility operates under Alberta Environment and Protected Areas (EPA), in accordance with EPEA Approval No.10348-03-01 (Appendix A).

The program included the water testing of all in-use groundwater wells and dugouts, as identified during the baseline sampling program completed during the fall of 1996 and any additions or subtractions from subsequent annual sampling events. Based on an updated landowner survey in May 2023, there are no potable groundwater wells within the 1.6 km radius to be sampled as local groundwater quality is poor and most residents rely on EPCOR water supply piped to Ryley. The only exception is the Doyle Booth property which utilizes the on-site dugout as its domestic water supply source (Dugout 1 in Table B).

The definition of "in-use" is water used for human consumption, cooking, washing, gardening or livestock purposes. In 2023, the new Approval for developing lands north of the existing landfill extended the 1.6 km limit about 750 m to the north and required five additional dugouts to be included in the annual sampling program. However, three of the dugouts located on the Westmancoat property to the northwest of the site could not be sampled as Tetra Tech was not able to obtain permission from the landowner after multiple attempts to contact them. An additional two dugouts (9A, 23 on Figure 1) were sampled in 2023 that are within the new 1.6 km radius due to the recent northward expansion of Clean Harbors Ryley Industrial Waste Management Facility and these dugouts are defined as "in-use." Water wells within the 1.6 km radius of the site were reviewed in 2023 to update these potential receptors near the site. This exercise is described in Section 3.0.

Twenty-one (21) dugouts were inspected and sampled during the 2023 dugout and water well monitoring program, which is the 28<sup>th</sup> annual sampling event, including the baseline event in 1996. The baseline sampling program is detailed in the report titled *Water Sampling and Testing Program*<sup>1</sup>. All annual dugout and water well monitoring has taken place in October since 1996.

This report presents the field observations and analytical water quality results of the 2023 sampling program with reference to recently collected data.

## 2.0 FIELD SAMPLING METHODS

### 2.1 Landowner Summary

The contact information for each landowner and their number of dugouts in the sampling program is presented in Table A. All landowners were contacted about two weeks prior to the sampling event, and each will be provided with a copy of the water chemistry of their dugout(s) once this report is finalized and sent to EPA. Landowners and contact information was updated as necessary in April and September 2023. The location of each sampled water source and residence, if found, is indicated on Figure 1.

<sup>1</sup>Tetra Tech. 1996. *Water Sampling and Testing Program*.



**Table A: Landowner Information**

Landowner (October 2023)	Contact Name and (Number of Dugouts)	Mailing Address	Telephone Number
D. Booth	Doyle Booth (1)	Box 185, Ryley, Alberta T0B 4A0	780.999.4577
Ewert Farms Ltd.	Mark Ewert (4)	Box 355, Ryley, Alberta T0B 4A0	780.914.5766
B.L. Lyons (now Clean Harbors Canada Inc.)	Brian Lyons (5) *	Box 222, Ryley, Alberta T0B 4A0	780.984.5026
T. Magneson	Terry Magneson (5)	Box 374, Ryley, Alberta T0B 4A0	780.603.1537
County of Beaver	c/o Margaret Jones (1)	Box 140, Ryley, Alberta T0B 4A0	780.663.3730 (direct 825.385.0061)
W. Winsnes	William Winsnes (1)	Box 335, Ryley, Alberta T0B 4A0 SW8-50-17-W4M	780.699.4009
G. Balash	George and Rose Balash (3)	Box 291, St Paul, Alberta T0A 3A0 gsbfarm@gmail.com	780.646.2001
D. Lyons	Darryl Lyons (1)	Box 330, Ryley, Alberta T0A 3A0	780.405.1110

\* Note: Brian Lyons' property (SW and SE 16) was purchased by Clean Harbors in July 2023. It is agreed that Brian Lyons will continue to receive water chemistry data for dugouts on these lands as long as he continues to farm the lands.

## 2.2 Sampling Procedure

The water samples were collected on October 16 and 17, 2023 by two Tetra Tech personnel. A Health and Safety Plan was completed and reviewed prior to initiating sampling. Twenty-one dugouts were sampled at eight properties, and 23 samples were collected: one from each dugout, plus two duplicate samples. Subsamples were collected from the four corners of each respective dugout at 0.20 m to 0.30 m below surface and about 2 metres from the dugout edge and submitted as an equal-weighted composite sample. Care was taken not to disturb bank or bed sediments in the sampling area.

All samples were obtained using standard procedures that minimized potential for contamination during collection, handling, preservation, and transportation to ensure representative samples were collected and tested. Table B contains a summary of the information gathered during the sampling program, including sample name, legal land description and relative dugout location with locations on Figure 1. The lands containing Dugout 12 (Magneson D.3) is incorporated into the Clean Harbor expansion area and therefore, no longer monitored. All dugouts were photographed with representative photos presented in Appendix E.

**Table B: Sample Location Information**

Sample	Sample Name	Legal Land Description (W4M)	Dugout Location
1	Booth D.1	NW ¼ 10-50-17	Dugout northwest of house
2	Ewert D.1	SW ¼ 15-50-17	Dugout south of centre barn
3	Ewert D.2	SW ¼ 15-50-17	Extreme west dugout
4	Ewert D.3	SW ¼ 15-50-17	Extreme east dugout
5	Ewert D.4	SW ¼ 15-50-17	Southeast corner of southwest quarter of Section 15
6	B. Lyons D.1*	SE ¼ 16-50-17	Northeast dugout on southeast quarter of Section 16
7	B. Lyons D.2*	SE ¼ 16-50-17	Northwest dugout on southeast quarter of Section 16
8	B. Lyons D.3*	SE ¼ 16-50-17	Southwest dugout on southeast quarter of Section 16
9	B. Lyons D.4*	SW ¼ 16-50-17	Southwest dugout on southwest quarter of Section 16
9A	B. Lyons D.5*	SW ¼ 16-50-17	Northwest dugout on southwest quarter Section of 16
10	Magneson D.1	SW ¼ 9-50-17	Dugout with windmill on northeast end of yard

**Table B: Sample Location Information**

Sample	Sample Name	Legal Land Description (W4M)	Dugout Location
11	Magneson D.2	SW ¼ 9-50-17	Southeast corner of northwest quarter of Section 9
13	Magneson D.4	SW ¼ 9-50-17	South end of southwest quarter of Section 9, east of main house
14	Magneson D.5	SW ¼ 9-50-17	East end of southwest quarter of Section 9, west of Clean Harbors
15	Magneson D.6	SW ¼ 9-50-17	South end of southwest quarter of Section 9, north of main house
16	Beaver County D.1	NW ¼ 3-50-17	Dugout south of house, northwest quarter of Section 3
19	Winsnes D.1	SW ¼ 4-50-17	Dugout on southwest corner of southwest quarter of Section 4
20	Balash D.1	NE ¼ 5-50-17	Dugout south of west approach, northeast quarter of Section 5
21	Balash D.2	SE ¼ 8-50-17	Dugout on southeast quarter of Section 8
22	Balash D.3	SE ¼ 8-50-17	Dugout is immediately west of Balash D.2
23	D. Lyons D.1	16-NE16-50-17-W4M	Middle of East half of Northeast Section 16

\* Lands owned by Clean Harbors Canada Inc. since July 2023.

ALS Laboratory Group (ALS) of Edmonton was the laboratory selected to perform the sample analysis and is certified by the Canadian Association of Laboratory Accreditation (CALA) for the parameters tested. ALS prepared sampling sets beforehand with bottles for each dugout to be tested. These sets included the individual sample bottles and preservatives needed to perform the analysis required by the Permit to Operate.

The following analytical parameters were tested for all dugouts and duplicate samples, as required by Approval No. 10348-03-01, Section 4.5:

- Major ions: calcium, magnesium, sodium, potassium, chloride, carbonate, bicarbonate, and sulphate
- Dissolved metals: aluminum, antimony, arsenic, barium, boron, cadmium, chromium, hexavalent chromium (chromium VI), cobalt, copper, lead, manganese, mercury, molybdenum, nickel, selenium, silver, thallium, tin, uranium, and zinc
- pH (field and laboratory)
- Electrical conductivity (EC) (field and laboratory)
- Benzene, toluene, ethylbenzene, xylenes (BTEX)
- Petroleum hydrocarbon (PHC) fractions F1 and F2
- Total dissolved solids (TDS)
- Total suspended solids (TSS)
- Chemical oxygen demand (COD)
- Dissolved organic carbon (DOC)
- Nutrients: ammonia (as N), Total Kjeldahl Nitrogen (TKN), nitrate (as NO<sub>3</sub>-N), nitrite (as NO<sub>2</sub>-N), and total phosphorus
- Phenols

Analytical request forms, including chain-of-custody data, were completed by Tetra Tech when the samples were submitted to the laboratory for analysis.

Hexavalent chromium (Chromium VI) was not analyzed in 2023 due to an oversight on the CoC. A multi-year laboratory quotation was obtained in 2021 for the 2021 through 2023 sampling events and was not updated to reflect the revised Approval in time for the 2023 sampling program. Hexavalent chromium analysis will be included in subsequent years.

In addition to lab testing, field parameter testing of the composite water sample was carried out at each dugout for the following:

- pH
- Electrical conductivity (EC)

Photographs were taken of each monitored dugout, and visual inspections were conducted to identify notable sheen, colour, odour, or other physical characteristics of the water in each dugout.

The analytical reports for each sample collected were forwarded to Tetra Tech once the analysis was completed. The 2023 laboratory Certificate of Analysis, as received from ALS, is presented in Appendix C. Table 1 summarizes the data collected in the last five years, including the 2023 monitoring program for each dugout. Appendix D contains the historical dugout chemical analytical results from 1996 up to 2023 data.

## 2.3 Quality Control and Quality Assurance

To evaluate field sampling reproducibility, duplicate water samples were collected during the 2023 sampling event at an approximate rate of 10% of total samples collected. In October 2023, the duplicates were taken from Dugout 11 (Duplicate 1) and Dugout 1 (Duplicate 2) and submitted as blinds for laboratory analysis for the same suite of parameters as the original samples (Tables 2 and 3).

To analyze the field sampling and laboratory testing reproducibility, the sample-duplicate pair was evaluated using the relative percentage difference (RPD) method, involving calculation of RPD when both sample and duplicate concentrations were greater than, or equal to, five times the laboratory reporting detection limit (RDL), as shown in Equation 1 below.

### Equation 1:

$$\%RPD = (| \text{sample} - \text{duplicate concentrations} | \text{ divided by } \bar{X}) \text{ multiplied by } 100$$

Where  $\bar{X}$  is the average concentration of a sample and its duplicate.

Surface water quality parameters were considered as having passed the quality assurance (QA)/quality control (QC) reproducibility procedure if the RPD was less than or equal to 20%, indicating a close correlation between the sample-duplicate pair. RPD is usually used for objectively flagging data for further review, rather than for taking corrective action.

RPD values were not calculated if one or both of the sample-duplicate concentrations were less than five times the RDL. In these cases, water quality parameters were still considered as having passed the QA/QC reproducibility procedure if the other sample duplicate concentration difference was less than one RDL value.

The RPD calculations are summarized in Table 2 (Duplicate 1) and Table 3 (Duplicate 2). All but four RPD tests satisfied the requirements (Two failing tests from each Duplicate). The QA/QC reproducibility guidelines were not satisfied for the following parameters:

- Duplicate 1: COD (36% RPD)
- Duplicate 2: COD (62% RPD) and TSS (33% RPD)

Small variations due to variability in field sampling or laboratory analytical methods (i.e., residuals from previous analysis, etc.) can result in concentration differences that are two or three times greater than the concentration result, which results in higher RPDs which fail the requirements. However, the concentrations are similar in most cases and often have acceptable variability even though the RPD calculation may indicate otherwise. The Duplicate RPD failures are limited in number (one or two out of 60 tests conducted for each duplicate). Based on this fact, a limited number of failed results is within acceptable variability, and the duplicate analysis indicates the data are stable and considered reliable overall.

### 3.0 REVIEW OF WATER WELLS IN SEARCH RADIUS

Tetra Tech completed an audit to verify and review the information contained within the EPA Water Well Information Database (WWID) and other publicly available information sources to determine the existence and status of groundwater wells within a 1.6 km radius of the Ryley facility, and to determine if it is warranted to field verify the wells and sample them as part of the Dugout and Water Well Sampling Program (beginning in 2023). The required search radius was 1.6 km; however, to account for the distance from the centre of the facility and spatial inaccuracies within the water well database, an expanded 2.0 km radius was used. The search showed records of 50 water well records drilled for various purposes as of September 2023.

The accuracy of the WWID is limited, as described by EPA - *“Data provided through [WWID] are preliminary in nature. This data may not have been reviewed or edited for accuracy and may be subject to significant change when reviewed or corrected. Please exercise caution and carefully consider the provisional nature of the information provided.”* Further, EPA states that most well locations are not shown precisely enough to field verify. Where no GPS coordinates were provided in the driller submission forms (particularly for older wells), the well location is plotted in the centre of the LSD or quarter-section that was provided, and therefore, the WWID does not contain a high level of spatial accuracy.

Based on the available information, it appears that most wells are not suitable for regular sampling or are no longer present or available for use. Of 50 records returned, 44 are considered to not require field verification or are not suitable for sampling. Rationale for elimination is summarized in Table C below and encompasses 44 of the 50 wells. As a result, six (6) wells were included for site reconnaissance during the October 2023 field event.

**Table C: Water Wells Eliminated from Search Radius**

Type of Record or Use	Comments	Number of Wells
Decommissioned	WWID contains a record of well decommissioning.	4
Federal Well Survey	Non-domestic, assumed to be a test well, location unknown.	1
Transfer of land and removal of house	Well assumed to be abandoned/removed when land was sold, and house was removed.	3
Test hole, observation well, or monitoring well	Non-domestic observation well, assumed to be for compliance or other monitoring use based on owner name and/or proposed use.	21
Wells between 90 and 110 years old (pre-1933)	Well assumed to be decommissioned, abandoned, or not possible to locate in the field.	7
Distance Greater than 1.6 km	Wells were determined to be greater than 1.6 km from the edge of the landfill boundary (including the expansion area).	6
Municipal Use	The village of Ryley did not have any record of municipal water wells <sup>2</sup> . All Village water is provided by water line from the City of Edmonton.	2

<sup>2</sup> Email communication from Village of Ryley to Tetra Tech dated September 25, 2023.

Tetra Tech also reviewed the status of the three “observation/investigation” wells (on SE 10-50-17-W4M) located immediately south of the active Claystone Landfill cells and to the east of Highway 854. These “test holes” were part of the 44 excluded wells and were excluded from further review in the September 2023 response to EPA from Clean Harbors Canada Inc. that summarized the area wells to consider in the Annual Dugouts and Water Wells monitoring program. The rationale for exclusion of these three wells is summarized as follows.

“Observation/investigation” wells (test holes) Nos. 1888429, 1888430 and 1888439 are located on lands owned by Claystone immediately south of the existing Claystone Class II Landfill cells and were installed by C. E. Moell as part of the landfill expansion and operation plan at that site. They would be part of the monitoring program at that site if functional, and even if data were available, it would be difficult to interpret due to the close proximity and potential influence of the Claystone Facility (about 200 m to the north). By comparison, the Clean Harbors facility is about 800 m to the southwest of these water wells. In addition, the lands where these wells are located is planned for future cell development and wells will be decommissioned. Our justification for excluding these three wells in the annual Clean Harbor’s Dugout and Water Well monitoring program is they are part of the Claystone operations and monitoring program (if functional), they are much closer to Claystone Landfill operations, and they will soon be decommissioned (if not already decommissioned). Just as Claystone does not monitor wells or dugouts on Clean Harbor’s lands, we do not monitor or sample water wells/dugouts on the Claystone Landfill property.

The remaining six records have the potential to correspond to water wells located on residential property, and therefore, may constitute active water wells. These wells were assumed to be in service until proven otherwise and therefore, field reconnaissance was conducted on October 17, 2023, during the dugout monitoring event. Table D below provides a summary of available information on the remaining six wells and Tetra Tech’s findings during reconnaissance.

**Table D: Field Verification of Water Wells**

GIC ID	Date Completed	Location	Use	Tetra Tech Findings
94701	1986	WH 4-50-17 W4M	Domestic & Industrial	Currently a closed diner nearby which is listed as being for sale. There are two well stickups at the back of the building. A letter was dropped off requesting for more information. No reply received.
94710	Not stated	4-9-50-17 W4M	Domestic & Stock	The landowner (Terry Magnuson) mentioned that there were three water wells surrounding his homestead and his family has decommissioned all three in the last 50 years. Currently, there are no water wells on his property.
94714	Not stated	SW 10-50-17 W4M	Domestic	The only potential residence in the vicinity is vacant/abandoned. GIC 94714 is likely an old record.
94748	Not stated	16-50-17 W4M	Domestic	The landowner stated that he has resided at the property for over 60 years and he doesn’t know of any water wells on the property.
286840	1997	4-10-50-17 W4M	Domestic	The only potential residence in the vicinity is vacant/abandoned. GIC ID 286840 is likely an old record.
94704	1986	4-50-17 W4M	Industrial	The building used to be occupied by “Highway 14 Regional Water Services Commission” and has since moved to a new location with the building currently appearing vacant. A well stickup was noted at an area adjacent to the west of the building. A letter requesting more information was dropped off at the vacant building and at the new office. No reply received.

None of the six outstanding water well records investigated resulted in monitoring or sampling as the well locations could not be confirmed/found or there was no response to either phone calls or letters dropped off at the locations.

## 4.0 FINDINGS

The chemical analysis results from the dugout monitoring program are reviewed for significant changes in parameters and compared to the range of results of previous sampling events, with particular focus on the past five years. The intent is not to compare results to provincial standards for acceptable water quality, but to pre-existing, baseline conditions in 1996 and successive years and identify potential or apparent trends, if any. High variability between years and between sites is possible and expected given only one sampling event per year and high variability in monthly and annual temperature and precipitation data. In addition, parameters at some locations have exceeded provincial water quality objectives since 1996 and are characteristic of natural conditions in the area or are related to pre-existing and ongoing agricultural land use. The objective of this work is to identify elevated levels and/or upward trends in parameters that might be sourced from the landfill through a groundwater, air or surface water pathway. Emphasis has been placed on reviewing sampling points down-gradient (generally east) of the landfill site, although the landfill site is near a local highpoint and groundwater and surface water flow may also be towards the north.

A summary of the 2023 data follows with data in Tables 1, 2 and 3. Table E below provides a summary of the evaluation of the parameters monitored for under the current approval.

Environment Canada's and Alberta Agriculture and Forestry's monthly and annual precipitation data from the Elk Island National Park meteorological station were reviewed and are summarized in Table 4. The total annual precipitation in 2023 was 396.7 mm which was 56.7 mm lower than the mean annual precipitation (or 87% of average) in the region (several different stations as available) since 1996. The months of January, February, March, September, October, November, and December 2023 were particularly low in 2023. The 2014, 2015, 2019, 2021, 2022, and 2023 annual precipitation data was from the Elk Island National Park meteorological station. Note that previous precipitation data (1996 to 2013) were obtained from the Tofield North Station when active. The Alberta Agriculture precipitation website<sup>3</sup> was updated to include more station data, so during 2016-2018, the Holden Alberta Government Drought Monitoring (AGDM) meteorological station data was utilized as it was closer to the subject site than others available. These shifts in the local reporting stations over the years are not expected to have a material impact on annual averages but may affect monthly precipitation data. Overall, there was generally lower than average precipitation in 2023 for a third consecutive year.

The two duplicate samples (Duplicate 1 from Dugout 11 and Duplicate 2 from Dugout 1) were tested for the same parameters as all other dugouts. All data is presented as follows:

The maximum value of each analyzed parameter were reviewed for each dugout location. The 2023 values of most parameters appeared similar to historical values. Parameters with 2023 analytical results greater than the historical values for specific dugouts are summarized in Table E. Data from dugouts 9A and 23 was not assessed as each of these locations commenced monitoring in 2023.

<sup>3</sup> <http://www.agriculture.alberta.ca/acis/alberta-weather-data-viewer.jsp>

**Table E: Dugout and Water Well Monitoring Summary**

Parameter	Locations where the 2023 value is the Maximum Value	Comments
pH (Field)	-	N/A
pH (Lab)	-	N/A
EC (Field)	-	N/A
EC (Lab)	Dugout 10	Lab EC at dugout 10 is the greatest to date, but similar to the 2022 value (2,810 µS/cm).
Chemical Oxygen Demand (COD)	Dugouts 3, 4, 10, and 20	COD results for dugouts 4 and 20 have exceeded historical values since 2022.
Dissolved Organic Carbon (DOC)	-	None
TDS	Dugout 10	TDS at dugout 10 appears to continue to increase year-over-year.
TSS	Dugouts 2, 3, 4, 10, 15, and 20	TSS monitoring commenced in 2021. While upward trends are apparent in several locations, the range of values observed may be within the typical range for the specified locations.
<b>Dissolved Metals</b>		
Aluminum	Dugout 11	No previous indication of elevated Aluminum at dugout 11.
Antimony	-	N/A
Arsenic	Dugout 10	Arsenic concentrations in dugout 10 appear to have increased slightly since 2019.
Barium	-	N/A
Boron	Dugout 9	Elevated but stable boron concentrations have been apparent since 2021.
Cadmium	Dugouts 4 and 11	Dugout 4 cadmium concentration is marginally greater than the laboratory detection limit. Dugout 11 cadmium concentration changed from the lowest observed value to the highest between 2022 and 2023.
Chromium, Total	-	N/A
Chromium, Hexavalent	No data available	No data available
Cobalt	-	N/A
Copper	Dugout 15	No previous trend in copper concentrations at dugout 15.
Lead	Dugouts 3 and 15	Lead concentration at dugout 3 is not appreciably greater than the 2020 value. Lead concentration at dugout 15 is marginally greater than the laboratory detection limit.
Manganese	-	N/A
Mercury	-	N/A
Molybdenum	-	N/A
Nickel	-	N/A
Selenium	-	N/A
Silver	Dugout 11	Silver concentration at dugout 11 is marginally greater than the laboratory detection limit.
Thallium	-	N/A
Tin	Dugouts 3, 4, 10, 11, 13, 14, 19, 21, and 22	Tin concentrations at the specified locations are historically less than the laboratory detection limit.

**Table E: Dugout and Water Well Monitoring Summary**

Parameter	Locations where the 2023 value is the Maximum Value	Comments
Uranium	Dugout 10	Uranium concentration at dugout 10 has increased steadily since 2019.
Zinc	Dugout 15	Zinc concentration at dugout 15 continues to increase since 2022.
<b>Major Ions</b>		
Calcium	Dugout 10	Calcium concentration at dugout 10 continues to increase.
Magnesium	Dugouts 2, 4, 7, 10, 13, and 14	Magnesium concentrations at the indicated dugouts are substantially greater than during historical monitoring.
Potassium	Dugouts 19 and 22	Potassium concentrations at dugouts 19 and 22 do not appear to represent a recent increasing trend.
Sodium	Dugout 10	Sodium concentrations at dugout 10 have slowly increased since 2019.
Carbonate	-	N/A
Bicarbonate	Dugout 10	Bicarbonate concentration at dugout 10 does not appear to represent a recent increasing trend.
Chloride	Dugout 10	Chloride concentrations at dugout 10 have slowly increased since 2019.
Sulfate	Dugout 22	Sulfate concentrations at dugout 22 have increased substantially since 2019.
<b>Nutrients</b>		
Ammonia (as N)	Dugout 10	Ammonia as N concentration at dugout 10 has increased substantially since 2019.
Total Kjeldahl Nitrogen	Dugouts 3 and 10	TKN concentrations in dugouts 3 and 10 do not appear to represent a recent increasing trend.
Nitrate (as NO <sub>3</sub> -N)	Dugout 3	
Nitrite (as NO <sub>2</sub> -N)	Dugouts 3, 10, 11, and 13	
Phosphorus, Total	Dugouts 2, 3, 4, 5, 6, 7, and 10	Phosphorus concentrations in dugouts 2, 3, and 4 continue to increase over their 2022 values and may represent a potential increasing trend in these locations.
<b>BTEX</b>		
Benzene	-	N/A
Toluene	-	N/A
Ethylbenzene	-	N/A
Xylenes, Total	-	N/A
<b>Phenols</b>	-	N/A
<b>PHC Fraction F1</b>	-	N/A
<b>PHC Fraction F2</b>	-	N/A

N/A – Not Applicable. No 2023 locations showed the maximum value for the specified parameter.

Data charts for parameters with locations where the 2023 results were the greatest results on record are presented on Figure 2.



## 5.0 DISCUSSION

### 5.1 Dugout Monitoring

The dugout water levels in 2023 were similar to those observed in 2022. Photos 1 and 2 show typical water levels at dugouts 13 and 19, respectively, and photographs of each dugout were taken at the time of monitoring. Sufficient water was available for sampling at all dugouts in 2023, however landowner authorization to monitor and sample dugouts 24, 25, and 26 had not been received prior to the 2023 monitoring event. These dugout locations were not monitored or sampled in 2023 and they are new due the expanded facility boundary. They will be included in 2024 if possible.

In general, the values of most parameters at most dugouts analyzed in 2023 were similar to historical values, except as described below and in Section 4.0. The following discussion focuses on parameters or parameter groups where observations at select dugouts were at their historical highest values in 2023.

The laboratory EC and total dissolved solids values at dugout 10 reached a new maximum value in 2023. As EC is affected by the total amount of anions and cations in solution, and dugout 10 has new maximum values for almost all the major ions (see below), an unusually high EC could be expected in response. Chemical oxygen demand in four dugouts (dugouts 3, 4, 10, and 20) was at its highest value in 2023, suggesting that the organic constituents of those dugouts may be substantially greater than in previous years. Changes in dugout use by livestock, use of the surrounding farmland, or changes in seasonal presence of decaying organic matter could affect the COD observed in these locations. Dugouts 4 and 20 have recorded elevated COD since 2022 and should be closely observed during future events.

Total suspended solids were recorded at new maximum values for six dugouts in 2023. As TSS analysis was added in 2020, it is likely that the full range of TSS values for some or all of the monitored dugouts have not yet been established. Future monitoring events may confirm if these values are typical or represent a potential increasing trend. Total suspended solids can be affected by livestock activity, bank erosion and wind activity on the dugouts.

Various dissolved metals parameters (aluminum, arsenic, boron, cadmium, copper, lead, silver, tin, uranium, and zinc) were observed at new maximum concentrations in one or more dugouts in 2023. Most of these occurrences appear isolated compared to historical values and not consistent with generally increasing concentrations of the specified parameters at the indicated wells. Tin concentrations have historically been below the laboratory reportable detection limit (RDL) at most dugout locations; however, reportable values were recorded at some locations in 2023 and should be confirmed during future monitoring events.

All major ions except carbonate (calcium, magnesium, sodium, potassium, bicarbonate, chloride, and sulfate) were observed at new maximum concentrations in one or more dugouts in 2023. Calcium, magnesium, sodium, chloride, and sulfate values for the locations noted in Table E may indicated increasing trends of these parameters and should continue to be observed closely during future monitoring events.

Nutrient parameters (ammonia, TKN, nitrate, nitrite, and phosphorus) were all observed at new maximum values at select locations in 2023. Nutrient load in surface water bodies can change with seasonal factors or changes to surrounding land use such as the presence of livestock or application of fertilizers and highly varied results year over year do not necessarily indicate undue influence from nearby landfill operations.

No dugout locations were identified with new maximum BTEX, phenols, or PHC fraction F1 or F2 values in 2023. These parameters are typically indicators of potential contamination sources and are generally not detected above the laboratory RDL.

The assessment of parameters analyzed does not appear to indicate off-site impacts from the Ryley Class I landfill site to these dugouts through groundwater, surface water or air pathways within a 1.6 km radius study area which includes the 21 dugouts sampled in 2023.

## 5.2 Surrounding Area Water Well Review Summary

Tetra Tech completed an audit to verify and review the information contained within the EPA Water Well Information Database (WWID) and other publicly available information sources to determine the status of water wells within a 1.6 km radius of the Ryley facility. Based on the available information, it appears that most wells are not suitable for regular sampling or are no longer present or available for use. Of 50 records returned in the database, 44 are considered to not require field verification (nor are suitable for sampling). Rationale for elimination of the 44 wells included available well record details, age of installation, distance from the Ryley Facility, intended purpose and owner name.

As noted in Section 3.0, none of the six outstanding water well records investigated in the field resulted in monitoring or sampling as the well locations could not be confirmed/found or there was no response to either telephone calls or letters dropped off at the locations.

## 6.0 CONCLUSIONS AND RECOMMENDATIONS

The following conclusions are based on the 2023 dugout and water well monitoring program:

- Analytical results of the dugout and water well monitoring program conducted in October 2023 indicate that the Ryley Class I Hazardous Waste Facility does not appear to be adversely impacting water quality in dugouts within a 1.6 km radius.
- Some parameters analyzed in 2023 exhibited new maximum observed values in one or more dugouts relative to historical baseline values, but the majority of concentrations were within the historical ranges for those parameters.
- Select parameters having historically high values or concentrations during the 2023 monitoring event should continue to be monitored and evaluated in future sampling events.
- No water wells were located within the 1.6 km radius of the site that could be included in the sampling program.
- A similar monitoring program is recommended for October 2024, as part of the ongoing site Approval compliance process.
- Each landowner should be forwarded a copy of the water chemistry analysis report pertaining to the dugout(s) sampled on their property once the 2023 report is finalized and submitted to AEPA.
- Area water wells should be reassessed every five years to confirm if any new wells have been established and should be included in the annual dugout and water well monitoring program.


## 7.0 CLOSURE

We trust this report meets your present requirements. Should you have any questions or comments, please contact the undersigned at your convenience.

Respectfully submitted,  
Tetra Tech Canada Inc.



FILE: 704-SWM.SWOP04810-01  
FILE: 704-SWM.SWOP04810-01  
FILE: 704-SWM.SWOP04810-01



February 28, 2024

---

Prepared by:  
Fahim Nazari, B.Sc., G.I.T.  
Environmental Engineer-in-Training  
Environment & Water Practice  
Direct Line: 780.699.9600  
Fahim.Nazari@tetrattech.com

---

Reviewed by:  
Brent Finnestad, P.Ag.  
Project Manager  
Environment & Water Practice  
Direct Line: 780.718.9317  
Brent.Finnestad@tetrattech.com

---

Reviewed by:  
Brian C. Adeney, P.Eng.  
Principal Consultant  
Environment & Water Practice  
Direct Line: 780.818.6568  
Brian.Adeney@tetrattech.com

/cee

## TABLES

Table 1.1 to Table 1.23	Chemical Analytical Results
Table 2	Duplicate 1 Chemical Analytical Results
Table 3	Duplicate 2 Chemical Analytical Results
Table 4	Historical and 2023 Precipitation Data - Total Precipitation (mm)

**Table 1.1: Chemical Analytical Results**

Sample ID:		Booth D.1				
Site Number:		1				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	84	82	95	96	127
Ammonia-N	mg/L	<0.050	<0.050	0.051	0.117	0.128
Total Kjeldahl Nitrogen	mg/L	2.51	2.75	3.45	3.52	4.36
Dissolved Organic Carbon	mg/L	22.9	19.9	28.9	23.5	29.8
Phenols	mg/L	0.0075	0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	10.6	18.2	41.2	29
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0021	0.0036	0.0049	0.0041	0.0027
Antimony	mg/L	0.00020	0.00016	0.00034	<0.00010	0.00023
Arsenic	mg/L	0.00484	0.00583	0.00809	0.00297	0.00647
Barium	mg/L	0.0614	0.0612	0.0471	0.0992	0.0503
Boron	mg/L	0.047	0.025	0.037	0.023	0.048
Cadmium	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	0.0000052
Chromium	mg/L	<0.00010	<0.00010	<0.00010	<0.00050	<0.00050
Cobalt	mg/L	0.00035	0.00030	0.00051	0.00029	0.00035
Copper	mg/L	0.00053	0.00040	0.00147	0.0002	0.00054
Lead	mg/L	0.000072	0.000055	0.000071	<0.000050	0.000098
Manganese	mg/L	0.00250	0.00783	0.00753	0.08	0.00556
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	0.0000113	<0.0000050
Molybdenum	mg/L	0.000853	0.000611	0.00117	0.000419	0.00106
Nickel	mg/L	0.00353	0.00304	0.00382	0.00277	0.00384
Selenium	mg/L	0.000115	0.000156	0.000096	0.00017	0.000132
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	0.0003
Uranium	mg/L	0.000578	0.000578	0.000824	0.000245	0.000525
Zinc	mg/L	<0.0010	<0.0010	0.0018	<0.0010	<0.0010
<b>Routine Water</b>						
Bicarbonate	mg/L	328	358	424	291	350
Chloride	mg/L	46.3	40.2	55.0	49.2	35
Carbonate	mg/L	<5.0	6.4	7.2	<1.0	5.3
Electrical Conductivity (EC)	uS/cm	714	712	808	651	689
Calcium	mg/L	21.5	20.4	13.9	45.5	22.6
Potassium	mg/L	12.5	13.2	16.4	14.2	10.2
Magnesium	mg/L	10.8	9.69	11.5	16.2	13.2
Sodium	mg/L	128	120	181	74.6	140
Sulfate	mg/L	43.4	26.6	28.0	42.4	51.6
Phosphorus	mg/L	0.211	0.466	0.148	0.525	0.607
pH in H <sub>2</sub> O	pH	8.36	8.42	8.48	8.24	8.46
TDS (Calculated)	mg/L	428	413	522	423	460
Nitrate	mg/L	<0.020	<0.020	<0.020	<0.020	<0.020
Nitrite	mg/L	<0.010	<0.010	<0.010	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	8.4	8.27	9.57	8.23	8.75
Electrical Conductivity (EC)	uS/cm	80	758	507	803	575

**Notes:**

"-" Not required under previous permit

**Table 1.2: Chemical Analytical Results**

Sample ID:		Ewert D.1				
Site Number:		2				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	79	78	99	153	144
Ammonia-N	mg/L	<0.050	<0.050	0.122	0.0625	0.0547
Total Kjeldahl Nitrogen	mg/L	2.70	3.08	2.26	3.8	4.4
Dissolved Organic Carbon	mg/L	22.2	21.1	33.7	45.3	41.3
Phenols	mg/L	0.0101	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	10.6	8.0	35.8	91.4
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0349	0.0059	0.109	0.0179	0.0062
Antimony	mg/L	0.00025	0.00021	0.00052	0.00051	0.00042
Arsenic	mg/L	0.0137	0.00823	0.0103	0.0164	0.0128
Barium	mg/L	0.0449	0.0508	0.0812	0.0401	0.0501
Boron	mg/L	0.040	0.028	0.035	0.041	0.022
Cadmium	mg/L	0.0000070	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Chromium	mg/L	<0.00010	<0.00010	0.00018	<0.00050	0.00054
Cobalt	mg/L	0.00062	0.00046	0.00117	0.00067	0.00049
Copper	mg/L	0.00271	0.00065	0.00389	0.00143	0.00113
Lead	mg/L	0.000076	<0.000050	0.000082	0.000097	0.000078
Manganese	mg/L	0.0138	0.00492	0.00745	0.0287	0.0259
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00198	0.000868	0.00316	0.00196	0.00131
Nickel	mg/L	0.00321	0.00290	0.00698	0.00434	0.0032
Selenium	mg/L	0.000258	0.000172	0.000373	0.000435	0.00035
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Uranium	mg/L	0.00138	0.00101	0.00290	0.00253	0.00192
Zinc	mg/L	0.0011	<0.0010	0.0042	<0.0010	0.0028
<b>Routine Water</b>						
Bicarbonate	mg/L	304	367	551	375	501
Chloride	mg/L	32.9	34.5	56.7	60.1	55.8
Carbonate	mg/L	38.3	16.4	14.3	135	90.4
Electrical Conductivity (EC)	uS/cm	675	732	1110	1340	1,180
Calcium	mg/L	21.5	22.6	22.4	19	24
Potassium	mg/L	16.0	20.3	26.7	23.5	14.2
Magnesium	mg/L	10.2	12.0	14.9	16.1	21
Sodium	mg/L	124	121	255	295	271
Sulfate	mg/L	24.3	28.9	103	118	84.2
Phosphorus	mg/L	0.628	0.745	0.408	0.578	0.980
pH in H <sub>2</sub> O	pH	9.16	8.69	8.59	9.75	9.45
TDS (Calculated)	mg/L	417	436	764	897	824
Nitrate	mg/L	0.047	<0.020	0.021	<0.020	<0.020
Nitrite	mg/L	0.013	<0.010	<0.010	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	EF	8.94	9.35	10.06	8.60
Electrical Conductivity (EC)	uS/cm	829	777	344.6	1388	947

**Notes:**

"-" Not required under previous permit

"EF" Equipment malfunction

**Table 1.3: Chemical Analytical Results**

Sample ID:		Ewert D.2				
Site Number:		3				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	92	119	133	124	226
Ammonia-N	mg/L	0.254	1.13	0.67	0.0393	0.341
Total Kjeldahl Nitrogen	mg/L	3.01	4.86	4.98	4.24	7.96
Dissolved Organic Carbon	mg/L	28.2	31.3	42.5	37.8	36.4
Phenols	mg/L	0.0068	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	13.6	93	53.8	152
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0334	0.0316	0.032	0.009	0.0036
Antimony	mg/L	0.00020	0.00025	0.00064	0.00022	0.00022
Arsenic	mg/L	0.00619	0.00841	0.0153	0.0113	0.00503
Barium	mg/L	0.0364	0.0509	0.0929	0.0252	0.023
Boron	mg/L	0.034	0.011	0.024	0.03	0.033
Cadmium	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	0.0000061
Chromium	mg/L	0.00013	0.00019	0.00013	<0.00050	<0.00050
Cobalt	mg/L	0.00061	0.00125	0.00153	0.00088	0.00077
Copper	mg/L	0.00127	0.00082	0.00197	0.00088	0.00168
Lead	mg/L	0.000164	0.000215	0.000102	0.000089	0.000229
Manganese	mg/L	0.00377	0.264	0.0538	0.0343	0.0429
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.000761	0.000587	0.00204	0.000878	0.00087
Nickel	mg/L	0.00630	0.00565	0.0086	0.00503	0.00485
Selenium	mg/L	0.000366	0.000326	0.000582	0.00038	0.000254
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	0.00015
Uranium	mg/L	0.000775	0.000892	0.00274	0.000777	0.000728
Zinc	mg/L	<0.0010	<0.0010	0.0027	<0.0010	0.0016
<b>Routine Water</b>						
Bicarbonate	mg/L	407	498	662	393	385
Chloride	mg/L	33.3	45.9	62.2	40.2	32.6
Carbonate	mg/L	<5.0	12.6	19.9	23.8	<1.0
Electrical Conductivity (EC)	uS/cm	844	1220	1590	922	804
Calcium	mg/L	25.8	30.1	44.0	28.3	23.4
Potassium	mg/L	19.0	23.5	28.9	19.3	10.8
Magnesium	mg/L	13.4	16.6	23.8	13.6	16.4
Sodium	mg/L	157	222	317	180	155
Sulfate	mg/L	77.3	193	284	80.2	108
Phosphorus	mg/L	0.576	1.19	1.14	1.43	1.69
pH in H <sub>2</sub> O	pH	8.29	8.49	8.61	8.92	8.23
TDS (Calculated)	mg/L	531	789	1110	617	566
Nitrate	mg/L	0.388	0.099	0.034	<0.020	0.392
Nitrite	mg/L	0.029	0.057	<0.010	<0.010	0.084
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	6.49	8.17	8.94	9.19	8.93
Electrical Conductivity (EC)	uS/cm	104.3	1322	986	943	657

**Notes:**

"-" Not required under previous permit

**Table 1.4: Chemical Analytical Results**

Sample ID:		Ewert D.3				
Site Number:		4				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	106	116	115	164	166
Ammonia-N	mg/L	<0.050	<0.050	0.60	0.07	0.168
Total Kjeldahl Nitrogen	mg/L	3.22	3.45	4.27	4.87	4.55
Dissolved Organic Carbon	mg/L	28.3	29.0	38.2	45.9	47.2
Phenols	mg/L	0.0058	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	7.6	8.0	37.8	80
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0107	0.0155	0.0129	0.0111	0.0071
Antimony	mg/L	0.00016	0.00018	0.00025	0.00016	0.00018
Arsenic	mg/L	0.0031	0.00513	0.0077	0.00691	0.00447
Barium	mg/L	0.0418	0.0342	0.0468	0.0208	0.0247
Boron	mg/L	0.039	0.025	0.032	0.039	0.038
Cadmium	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	0.0000071
Chromium	mg/L	0.00017	0.00023	0.00011	<0.00050	<0.00050
Cobalt	mg/L	0.00036	0.00075	0.00080	0.00106	0.00059
Copper	mg/L	0.00163	0.0010	0.00255	0.00091	0.00159
Lead	mg/L	0.000211	0.000278	0.000189	0.000136	0.000081
Manganese	mg/L	0.00879	0.0441	0.114	0.146	0.0634
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.000489	0.000407	0.00143	0.000938	0.00104
Nickel	mg/L	0.00281	0.00314	0.00375	0.00468	0.00332
Selenium	mg/L	0.000188	0.000206	0.000252	0.000277	0.000262
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	0.00011
Uranium	mg/L	0.000262	0.000262	0.000768	0.000332	0.000174
Zinc	mg/L	<0.0010	<0.0010	0.0017	0.0012	0.0033
<b>Routine Water</b>						
Bicarbonate	mg/L	290	338	426	291	308
Chloride	mg/L	56.2	73.5	99.8	68	49
Carbonate	mg/L	<5.0	5.3	<5.0	2.5	3
Electrical Conductivity (EC)	uS/cm	622	750	894	696	575
Calcium	mg/L	22.5	19.5	25.5	20.7	25.5
Potassium	mg/L	14.2	15.7	21.0	18.9	10.1
Magnesium	mg/L	10.7	10.2	11.5	10.9	16.1
Sodium	mg/L	103	126	173	124	101
Sulfate	mg/L	14.3	15.8	13.4	17.2	7.13
Phosphorus	mg/L	0.605	1.08	0.701	1.46	1.6
pH in H <sub>2</sub> O	pH	7.98	8.39	8.40	8.38	8.38
TDS (Calculated)	mg/L	364	432	560	457	419
Nitrate	mg/L	0.027	<0.020	0.103	<0.020	<0.020
Nitrite	mg/L	0.010	<0.010	0.016	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	EF	8.34	8.60	8.53	8.39
Electrical Conductivity (EC)	uS/cm	803	793	275.9	716	500

**Notes:**

"-" Not required under previous permit

"EF" Equipment malfunction



**Table 1.5: Chemical Analytical Results**

Sample ID:		Ewert D.4				
Site Number:		5				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	92	75	124	114	109
Ammonia-N	mg/L	<0.050	0.235	0.51	0.0678	0.143
Total Kjeldahl Nitrogen	mg/L	3.61	3.64	5.41	4.27	3.5
Dissolved Organic Carbon	mg/L	22.7	23.0	35.9	28.3	28.3
Phenols	mg/L	0.0076	0.0012	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	33.8	69	40.2	38.8
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	0.77	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0015	0.0425	0.0782	0.0645	0.0025
Antimony	mg/L	0.00015	0.00035	0.00057	0.00031	0.00024
Arsenic	mg/L	0.00313	0.00692	0.00694	0.00625	0.00595
Barium	mg/L	0.0528	0.0823	0.102	0.0589	0.0338
Boron	mg/L	0.042	0.018	0.034	0.042	0.029
Cadmium	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Chromium	mg/L	<0.00010	0.00013	0.00012	<0.00050	<0.00050
Cobalt	mg/L	0.00043	0.00113	0.00146	0.00093	0.00049
Copper	mg/L	0.00054	0.00123	0.00282	0.00078	0.00055
Lead	mg/L	<0.000050	0.000273	0.000078	0.000093	0.000067
Manganese	mg/L	0.00080	0.0246	0.00707	0.0131	0.0127
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00118	0.00177	0.00312	0.00205	0.00108
Nickel	mg/L	0.00406	0.00732	0.00852	0.00442	0.00348
Selenium	mg/L	0.000217	0.00037	0.000469	0.000305	0.000256
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Uranium	mg/L	0.000602	0.00121	0.00245	0.0013	0.000551
Zinc	mg/L	<0.0010	<0.0010	0.0039	<0.0010	0.0015
<b>Routine Water</b>						
Bicarbonate	mg/L	356	312	494	364	339
Chloride	mg/L	18	12.9	20.5	15.2	10.6
Carbonate	mg/L	6.6	<5.0	9.8	14.9	5.4
Electrical Conductivity (EC)	uS/cm	624	796	878	718	589
Calcium	mg/L	23.9	28.5	29.5	22.2	24.4
Potassium	mg/L	14.5	15.3	19.6	16.7	11.6
Magnesium	mg/L	13.3	13.4	17.1	15.2	14.4
Sodium	mg/L	103	118	168	136	102
Sulfate	mg/L	20.2	136	80.9	42.3	46
Phosphorus	mg/L	0.225	0.591	0.105	0.301	0.988
pH in H <sub>2</sub> O	pH	8.44	8.37	8.50	8.75	8.47
TDS (Calculated)	mg/L	375	482	583	472	388
Nitrate	mg/L	<0.020	<0.020	<0.020	0.032	<0.020
Nitrite	mg/L	<0.010	0.011	<0.010	0.013	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	EF	8.10	9.00	9.23	8.59
Electrical Conductivity (EC)	uS/cm	788	829	551	739	485

**Notes:**

"-" Not required under previous permit

"EF" Equipment malfunction

**Table 1.6: Chemical Analytical Results**

Sample ID:		Lyons D.1				
Site Number:		6				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	18-Oct-2022	17-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	89	98	93	95	84
Ammonia-N	mg/L	0.575	0.191	0.054	0.021	0.241
Total Kjeldahl Nitrogen	mg/L	3.01	3.13	3.19	2.44	3.74
Dissolved Organic Carbon	mg/L	24.7	25.0	29.7	27.1	30.2
Phenols	mg/L	0.0087	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	5.2	23.6	16.6	17.8
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0306	0.0366	0.0034	0.0023	0.0067
Antimony	mg/L	0.00017	0.00017	0.00024	0.00015	0.00011
Arsenic	mg/L	0.00531	0.00537	0.00773	0.00591	0.00516
Barium	mg/L	0.0421	0.0372	0.0330	0.0286	0.0276
Boron	mg/L	0.029	<0.010	0.023	0.056	0.058
Cadmium	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Chromium	mg/L	0.0002	0.00028	<0.00010	<0.00050	<0.00050
Cobalt	mg/L	0.00038	0.00065	0.00078	0.00057	0.00052
Copper	mg/L	0.00063	0.00060	0.00119	0.00044	0.00037
Lead	mg/L	0.000229	0.000149	<0.000050	<0.000050	0.00008
Manganese	mg/L	0.00866	0.223	0.00485	0.0169	0.119
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00076	0.000751	0.00132	0.000992	0.00075
Nickel	mg/L	0.00361	0.00335	0.00336	0.00338	0.00274
Selenium	mg/L	0.000212	0.000251	0.000271	0.000256	0.000184
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Uranium	mg/L	0.000234	0.00025	0.000932	0.000393	0.000116
Zinc	mg/L	0.0016	<0.0010	0.0022	0.0014	<0.0010
<b>Routine Water</b>						
Bicarbonate	mg/L	217	210	325	228	185
Chloride	mg/L	12.9	13.1	18.3	24.2	11.2
Carbonate	mg/L	<5.0	<5.0	<5.0	9.7	<1.0
Electrical Conductivity (EC)	uS/cm	405	439	586	535	419
Calcium	mg/L	18.6	16.9	29.8	23.6	17.2
Potassium	mg/L	17.1	13.6	18.1	17.4	7.54
Magnesium	mg/L	8.46	7.41	10.8	9.12	16.2
Sodium	mg/L	51	59.0	84.7	76.7	53
Sulfate	mg/L	15	36.4	48.8	30.4	36
Phosphorus	mg/L	1.38	1.23	0.589	1.15	1.78
pH in H <sub>2</sub> O	pH	7.91	8.06	8.30	8.72	7.95
TDS (Calculated)	mg/L	232	250	368	331	276
Nitrate	mg/L	0.429	<0.020	<0.020	<0.020	<0.020
Nitrite	mg/L	0.045	<0.010	<0.010	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	EF	7.69	9.13	8.62	8.72
Electrical Conductivity (EC)	uS/cm	496	953	355.1	535	374

**Notes:**  
 "-" Not required under previous permit  
 "EF" Equipment malfunction

**Table 1.7: Chemical Analytical Results**

Sample ID:		Lyons D.2				
Site Number:		7				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	18-Oct-2022	17-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	83	76	182	87	90
Ammonia-N	mg/L	0.414	0.236	0.090	1.330	0.204
Total Kjeldahl Nitrogen	mg/L	2.58	2.67	9.30	3.66	4.45
Dissolved Organic Carbon	mg/L	23.4	20.8	46.8	33.5	29.6
Phenols	mg/L	0.0075	0.0017	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	3.4	43.5	8.6	25.2
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0613	0.0189	0.0176	0.0049	0.0043
Antimony	mg/L	0.00012	0.00014	0.00025	0.00014	0.00012
Arsenic	mg/L	0.00497	0.00461	0.00725	0.00513	0.00422
Barium	mg/L	0.0649	0.0240	0.0357	0.034	0.00746
Boron	mg/L	0.022	<0.010	0.032	0.05	0.046
Cadmium	mg/L	<0.0000050	<0.0000050	0.0000065	<0.0000050	<0.0000050
Chromium	mg/L	0.00018	0.00016	0.00011	<0.00050	<0.00050
Cobalt	mg/L	0.00049	0.00025	0.00081	0.00069	0.00027
Copper	mg/L	0.00083	0.00095	0.00233	0.00046	0.00038
Lead	mg/L	0.000281	0.000087	0.000056	<0.000050	<0.000050
Manganese	mg/L	0.0361	0.0155	0.0101	0.162	0.00983
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00063	0.000745	0.00176	0.000826	0.0005
Nickel	mg/L	0.00341	0.00326	0.00415	0.00279	0.00201
Selenium	mg/L	0.000212	0.000249	0.000257	0.000192	0.000155
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	0.00012	<0.00010	<0.00010
Uranium	mg/L	0.000266	0.000275	0.00114	0.000342	0.000138
Zinc	mg/L	0.0018	<0.0010	0.0046	<0.0010	0.0031
<b>Routine Water</b>						
Bicarbonate	mg/L	232	202	289	270	233
Chloride	mg/L	15.6	13.0	17.9	21.6	15
Carbonate	mg/L	<5.0	<5.0	<5.0	<1.0	<1.0
Electrical Conductivity (EC)	uS/cm	435	409	515	549	455
Calcium	mg/L	17.4	16.9	26.2	22.5	18.5
Potassium	mg/L	18.5	15.5	21.3	19.7	6.99
Magnesium	mg/L	7.74	6.42	9.62	8.64	18
Sodium	mg/L	56.5	54.3	82.2	74.4	61
Sulfate	mg/L	14.5	24.9	32.8	22.6	19.5
Phosphorus	mg/L	1.13	1.09	0.865	1.2	1.68
pH in H <sub>2</sub> O	pH	8.11	8.12	8.25	8.06	7.95
TDS (Calculated)	mg/L	246	230	333	346	291
Nitrate	mg/L	0.396	<0.020	0.047	0.045	0.024
Nitrite	mg/L	0.042	0.013	<0.010	0.02	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	10.73	7.81	9.07	7.93	8.50
Electrical Conductivity (EC)	uS/cm	529	923	173	541	377

**Notes:**

"-" Not required under previous permit

**Table 1.8: Chemical Analytical Results**

Sample ID:		Lyons D.3				
Site Number:		8				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	18-Oct-2022	17-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	105	116	378	125	113
Ammonia-N	mg/L	<0.050	0.286	2.13	0.0994	0.0594
Total Kjeldahl Nitrogen	mg/L	3.66	4.93	18.0	4.0	3.15
Dissolved Organic Carbon	mg/L	30.9	30.8	108	45.7	27.6
Phenols	mg/L	0.0137	<0.0010	<0.003	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	52.8	1040	56.2	176
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0192	0.0175	1.28	0.0064	0.0046
Antimony	mg/L	0.0003	0.00046	0.00131	0.00052	0.00035
Arsenic	mg/L	0.00261	0.00407	0.00556	0.00575	0.0036
Barium	mg/L	0.0461	0.0697	0.185	0.0423	0.0418
Boron	mg/L	0.027	0.014	0.060	0.033	0.059
Cadmium	mg/L	0.0000068	<0.0000050	0.0000423	0.0000081	<0.0000050
Chromium	mg/L	0.00010	0.00011	0.00163	<0.00050	<0.00050
Cobalt	mg/L	0.00161	0.00247	0.00303	0.00136	0.00134
Copper	mg/L	0.00484	0.00425	0.00613	0.0028	0.00306
Lead	mg/L	0.000051	<0.000050	0.00289	<0.000050	0.000051
Manganese	mg/L	0.00279	0.0179	0.166	0.00573	0.0235
Mercury	mg/L	<0.0000050	<0.0000050	0.0000088	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00452	0.00583	0.0316	0.0103	0.00625
Nickel	mg/L	0.0112	0.0125	0.0195	0.0136	0.00808
Selenium	mg/L	0.000684	0.000967	0.00153	0.001	0.000608
Silver	mg/L	<0.000010	<0.000010	0.000018	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	0.000016	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Uranium	mg/L	0.00318	0.00422	0.0213	0.00628	0.00441
Zinc	mg/L	0.0017	<0.0010	0.0108	<0.0010	<0.0010
<b>Routine Water</b>						
Bicarbonate	mg/L	413	426	557	481	373
Chloride	mg/L	22.3	17.5	66.3	26.5	18
Carbonate	mg/L	14.5	15.7	<5.0	15.6	14.9
Electrical Conductivity (EC)	uS/cm	978	816	1470	1240	896
Calcium	mg/L	41.3	31.8	31.8	34.4	34.9
Potassium	mg/L	22.2	20.9	26.6	24.4	17.2
Magnesium	mg/L	24.6	17.1	14.5	23.4	17.7
Sodium	mg/L	149	126	262	216	128
Sulfate	mg/L	138	60.5	306	200	122
Phosphorus	mg/L	0.290	0.447	0.228	0.251	0.536
pH in H <sub>2</sub> O	pH	8.60	8.60	8.31	8.61	8.61
TDS (Calculated)	mg/L	615	500	985	824	567
Nitrate	mg/L	<0.020	0.079	0.096	<0.020	<0.020
Nitrite	mg/L	<0.010	0.020	<0.010	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	7.24	8.54	8.58	8.53	8.08
Electrical Conductivity (EC)	uS/cm	1198	861	845	1238	668

**Notes:**

"-" Not required under previous permit

**Table 1.9: Chemical Analytical Results**

<b>Sample ID:</b>					
<b>Lyons D.4</b>					
<b>Site Number:</b>					
<b>9</b>					
<b>Date Sampled:</b>	<b>29-Oct-2019</b>	<b>8-Oct-2020</b>	<b>21-Oct-2021</b>	<b>18-Oct-2022</b>	<b>17-Oct-2023</b>
Chem. O <sub>2</sub> Demand	137	137	258	236	111
Ammonia-N	0.397	0.888	0.43	0.134	0.105
Total Kjeldahl Nitrogen	4.26	4.02	9.10	6.67	3.9
Dissolved Organic Carbon	42.9	43.2	85.3	79.1	43.6
Phenols	0.0088	0.0013	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	-	61.0	96	40.4	44
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>					
Benzene	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>					
Aluminium	0.0764	0.125	0.221	0.0145	0.0467
Antimony	0.00024	0.00024	0.00117	0.00052	0.00029
Arsenic	0.00314	0.00702	0.00526	0.0122	0.00467
Barium	0.0406	0.0370	0.153	0.052	0.0348
Boron	0.024	0.011	0.053	0.045	0.056
Cadmium	0.0000099	<0.0000050	0.0000115	0.0000157	0.0000064
Chromium	0.00031	0.00035	0.00048	<0.00050	<0.00050
Cobalt	0.00060	0.00092	0.00232	0.00161	0.00101
Copper	0.00123	0.00083	0.00522	0.00299	0.00172
Lead	0.000283	0.000366	0.000096	0.000076	0.000111
Manganese	0.00266	0.0884	0.0828	<0.0050	0.0273
Mercury	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	0.00164	0.000964	0.0136	0.00296	0.00203
Nickel	0.00455	0.00468	0.0139	0.0105	0.00649
Selenium	0.000262	0.000408	0.000441	0.000688	0.000396
Silver	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Uranium	0.000924	0.000664	0.0113	0.00227	0.00124
Zinc	0.0024	<0.0010	0.0022	<0.0010	0.001
<b>Routine Water</b>					
Bicarbonate	442	375	734	633	385
Chloride	22.9	21.0	77.8	20.2	17.2
Carbonate	<5.0	<5.0	20.2	17.2	10.2
Electrical Conductivity (EC)	734	639	1430	1040	660
Calcium	22.2	23.5	36.5	37.8	25.2
Potassium	26.8	28.1	61.4	32.4	12.9
Magnesium	12.7	11.6	21.0	19.4	23.5
Sodium	121	94.5	264	188	93.6
Sulfate	5.32	3.99	81.2	3.8	4.85
Phosphorus	0.614	2.71	0.315	0.885	1.27
pH in H <sub>2</sub> O	8.23	8.39	8.59	8.58	8.49
TDS (Calculated)	431	373	936	715	429
Nitrate	0.336	0.141	2.56	<0.020	0.112
Nitrite	0.030	0.058	0.050	<0.010	<0.010
<b>Field Data</b>					
pH in H <sub>2</sub> O	6.14	8.08	8.60	8.20	8.37
Electrical Conductivity (EC)	897	666	68	1060	513

**Notes:**

"-" Not required under previous permit

**Table 1.9A: Chemical Analytical Results**

Sample ID:		Lyons D.5
Site Number:		9A
Date Sampled:	Units	17-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	100
Ammonia-N	mg/L	0.1
Total Kjeldahl Nitrogen	mg/L	2.57
Dissolved Organic Carbon	mg/L	31.1
Phenols	mg/L	<0.0010
Total Suspended Solids (TSS)	mg/L	28.6
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>		
Benzene	mg/L	<0.00050
Toluene	mg/L	<0.00050
Ethylbenzene	mg/L	<0.00050
Xylenes	mg/L	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10
<b>Dissolved Metals</b>		
Aluminium	mg/L	0.0068
Antimony	mg/L	0.0002
Arsenic	mg/L	0.00296
Barium	mg/L	0.0626
Boron	mg/L	0.029
Cadmium	mg/L	<0.0000050
Chromium	mg/L	<0.00050
Cobalt	mg/L	0.00043
Copper	mg/L	0.00088
Lead	mg/L	0.000177
Manganese	mg/L	0.0036
Mercury	mg/L	<0.0000050
Molybdenum	mg/L	0.00103
Nickel	mg/L	0.005
Selenium	mg/L	0.000225
Silver	mg/L	<0.000010
Thallium	mg/L	<0.000010
Tin	mg/L	0.00017
Uranium	mg/L	0.000756
Zinc	mg/L	0.0012
<b>Routine Water</b>		
Bicarbonate	mg/L	347
Chloride	mg/L	7.94
Carbonate	mg/L	8.5
Electrical Conductivity (EC)	uS/cm	602
Calcium	mg/L	24.3
Potassium	mg/L	11.9
Magnesium	mg/L	14.4
Sodium	mg/L	91.8
Sulfate	mg/L	23.9
Phosphorus, Total	mg/L	0.172
pH in H <sub>2</sub> O	pH	8.47
TDS (Calculated)	mg/L	385
Nitrate	mg/L	0.021
Nitrite	mg/L	<0.010
<b>Field Data</b>		
pH in H <sub>2</sub> O	pH	8.49
Electrical Conductivity (EC)	uS/cm	478

**Notes:**

"-" Not required under previous permit

**Table 1.10: Chemical Analytical Results**

Sample ID:		Magneson D.1				
Site Number:		10				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	339	280	272	245	578
Ammonia-N	mg/L	0.104	0.166	0.26	0.422	6.33
Total Kjeldahl Nitrogen	mg/L	11.0	9.55	8.70	8.71	23.7
Dissolved Organic Carbon	mg/L	102	85.6	84.0	80.6	204
Phenols	mg/L	0.0084	<0.0010	<0.0010	<0.0010	0.0014
Total Suspended Solids (TSS)	mg/L	-	4.4	10.6	22.8	192
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.039	0.187	0.583	0.0607	0.0166
Antimony	mg/L	0.0005	0.00054	0.00072	<0.0020	0.00062
Arsenic	mg/L	0.0175	0.0169	0.0225	0.0222	0.0249
Barium	mg/L	0.0701	0.0728	0.0553	0.0332	0.0254
Boron	mg/L	0.091	0.097	0.125	0.226	0.166
Cadmium	mg/L	0.00005	0.000024	0.000031	<0.00010	0.0000371
Chromium	mg/L	0.00092	0.00097	0.00109	<0.010	<0.00100
Cobalt	mg/L	0.0051	0.00494	0.00628	0.00545	0.00519
Copper	mg/L	0.0255	0.0184	0.0301	0.0318	0.00543
Lead	mg/L	0.00105	0.00131	0.00091	<0.0010	0.000583
Manganese	mg/L	0.587	0.621	0.521	0.359	0.3
Mercury	mg/L	0.0000086	<0.0000050	<0.0000050	<0.0000050	0.0000059
Molybdenum	mg/L	0.00327	0.00339	0.00439	0.00541	0.00278
Nickel	mg/L	0.0243	0.0200	0.0255	0.0244	0.0186
Selenium	mg/L	0.00080	0.00087	0.00105	0.00102	0.00083
Silver	mg/L	<0.000020	<0.000020	<0.000050	<0.00020	<0.000020
Thallium	mg/L	<0.000020	<0.000020	<0.000050	<0.00020	<0.000020
Tin	mg/L	<0.00020	<0.00020	<0.00050	<0.0020	0.00029
Uranium	mg/L	0.00185	0.00221	0.00292	0.0031	0.00436
Zinc	mg/L	0.0076	0.0063	0.0103	<0.020	0.0028
<b>Routine Water</b>						
Bicarbonate	mg/L	609	578	707	650	1,040
Chloride	mg/L	202	217	281	287	323
Carbonate	mg/L	16.1	22.7	24.1	34.6	39.6
Electrical Conductivity (EC)	uS/cm	2150	2230	2690	2810	2,890
Calcium	mg/L	51.7	56.8	74.9	75.5	81.3
Potassium	mg/L	135	116	152	146	49.1
Magnesium	mg/L	31.0	31.9	43.5	42.1	203
Sodium	mg/L	326	347	426	460	553
Sulfate	mg/L	284	363	480	512	388
Phosphorus	mg/L	8.91	7.55	7.01	6.31	12.4
pH in H <sub>2</sub> O	pH	8.52	8.60	8.61	8.78	8.64
TDS (Calculated)	mg/L	1350	1440	1830	1980	2,400
Nitrate	mg/L	1.12	0.85	1.07	<0.10	<0.100
Nitrite	mg/L	<0.020	0.062	0.018	<0.050	0.235
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	9.73	8.63	8.77	8.79	8.19
Electrical Conductivity (EC)	uS/cm	2660	2390	278	2850	2400

**Notes:**

"-" Not required under previous permit

**Table 1.11: Chemical Analytical Results**

Sample ID:		Magneson D.2				
Site Number:		11				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	114	196	Dry	224	192
Ammonia-N	mg/L	0.063	<0.050		0.1	0.902
Total Kjeldahl Nitrogen	mg/L	3.46	7.09		7.23	6.35
Dissolved Organic Carbon	mg/L	33.5	54.6		67.7	50.9
Phenols	mg/L	0.0142	0.0010		<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	345		56.8	86.4
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	Dry	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050		<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050		<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071		<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10		<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10		<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.168	0.0606	Dry	0.0338	0.356
Antimony	mg/L	0.00018	0.00026		0.00039	0.00023
Arsenic	mg/L	0.00332	0.00542		0.00544	0.00833
Barium	mg/L	0.0524	0.0423		0.045	0.0858
Boron	mg/L	0.024	0.031		0.03	0.05
Cadmium	mg/L	0.0000153	0.0000129		0.000007	0.0000334
Chromium	mg/L	0.00034	0.00035		<0.00050	0.00069
Cobalt	mg/L	0.00057	0.00124		0.00222	0.00198
Copper	mg/L	0.00211	0.00224		0.00314	0.00294
Lead	mg/L	0.000582	0.000394		0.000162	0.00204
Manganese	mg/L	0.00213	0.0308		0.00785	0.0885
Mercury	mg/L	0.000005	<0.0000050		<0.0000050	<0.0000050
Molybdenum	mg/L	0.00111	0.00138		0.00643	0.00272
Nickel	mg/L	0.00512	0.00635		0.0116	0.00893
Selenium	mg/L	0.000263	0.000417		0.000663	0.000392
Silver	mg/L	<0.000010	<0.000010		<0.000010	0.000013
Thallium	mg/L	<0.000010	<0.000010		<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010		<0.00010	0.00029
Uranium	mg/L	0.000954	0.00203		0.00497	0.00158
Zinc	mg/L	0.0015	<0.0010	<0.0010	0.0066	
<b>Routine Water</b>						
Bicarbonate	mg/L	296	338	Dry	464	293
Chloride	mg/L	19.2	27.6		28.7	20.9
Carbonate	mg/L	<5.0	<5.0		13.2	2.9
Electrical Conductivity (EC)	uS/cm	516	625		837	500
Calcium	mg/L	20.8	21.0		34.2	22.1
Potassium	mg/L	32.9	33.5		48.4	8.98
Magnesium	mg/L	9.31	9.13		14	28.6
Sodium	mg/L	69.1	91.7		138	75.1
Sulfate	mg/L	5.44	14.5		9.38	4.18
Phosphorus	mg/L	1.21	2.61		0.836	2.72
pH in H <sub>2</sub> O	pH	8.19	8.39		8.62	8.38
TDS (Calculated)	mg/L	303	369		584	383
Nitrate	mg/L	0.253	<0.020		<0.020	0.503
Nitrite	mg/L	<0.010	<0.010		<0.010	0.065
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	10.3	8.42	Dry	8.78	8.67
Electrical Conductivity (EC)	uS/cm	650	662		858	434

**Notes:**

"-" Not required under previous permit



**Table 1.12: Chemical Analytical Results**

Sample ID:		Magneson D.3 (now on Clean Harbors' property)				
Site Number:		12				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	18-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	119	48	12	74	Not monitored
Ammonia-N	mg/L	<0.050	<0.050	<0.050	0.0335	
Total Kjeldahl Nitrogen	mg/L	3.49	2.02	0.57	2.37	
Dissolved Organic Carbon	mg/L	17.9	15.1	8.3	23.3	
Phenols	mg/L	0.0136	<0.0010	<0.0010	<0.0010	
Total Suspended Solids (TSS)	mg/L	-	19.2	7.4	39	
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	Not monitored
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0033	0.0088	0.0125	0.0024	Not monitored
Antimony	mg/L	0.00029	0.00029	0.00028	0.00036	
Arsenic	mg/L	0.00194	0.00169	0.00105	0.00256	
Barium	mg/L	0.0773	0.053	0.0364	0.0954	
Boron	mg/L	0.060	0.062	0.05	0.084	
Cadmium	mg/L	0.0000188	<0.0000050	0.0000153	0.0000201	
Chromium	mg/L	0.00016	<0.00010	0.00029	<0.00050	
Cobalt	mg/L	0.00052	0.00022	<0.00010	0.00028	
Copper	mg/L	0.00242	0.0011	0.00276	0.00121	
Lead	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	
Manganese	mg/L	0.00123	0.00125	0.00067	<0.0050	
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	
Molybdenum	mg/L	0.0254	0.0234	0.0364	0.0434	
Nickel	mg/L	0.0203	0.0146	0.00476	0.0171	
Selenium	mg/L	0.000304	0.000259	0.000246	0.000414	
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	
Uranium	mg/L	0.00247	0.00265	0.00127	0.00322	
Zinc	mg/L	0.0028	<0.0010	0.0044	0.0012	
<b>Routine Water</b>						
Bicarbonate	mg/L	268	282	117	261	Not monitored
Chloride	mg/L	14.7	13.6	49.9	12.9	
Carbonate	mg/L	<5.0	5.0	<5.0	3.4	
Electrical Conductivity (EC)	uS/cm	960	947	772	992	
Calcium	mg/L	49.1	41.3	43.7	35.5	
Potassium	mg/L	13.6	12.2	3.22	14.6	
Magnesium	mg/L	17.4	16.1	13.5	16.8	
Sodium	mg/L	139	144	109	162	
Sulfate	mg/L	252	253	235	252	
Phosphorus	mg/L	0.185	0.081	<0.050	0.122	
pH in H <sub>2</sub> O	pH	8.38	8.40	7.87	8.39	
TDS (Calculated)	mg/L	623	625	478	656	
Nitrate	mg/L	0.029	<0.020	<0.020	<0.020	
Nitrite	mg/L	<0.010	<0.010	<0.010	<0.010	
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	11.68	8.36	8.48	8.28	Not monitored
Electrical Conductivity (EC)	uS/cm	1203	1017	483	1010	

**Notes:**

"-" Not required under previous permit

**Table 1.13: Chemical Analytical Results**

Sample ID:		Magneson D.4				
Site Number:		13				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	1370	1300	3420	1100	1,180
Ammonia-N	mg/L	2.85	2.02	<2.5	1.63	3.38
Total Kjeldahl Nitrogen	mg/L	43.7	42.6	122	42.1	41
Dissolved Organic Carbon	mg/L	415	295	1070	277	326
Phenols	mg/L	0.0116	0.0013	0.0054	0.0018	<0.0020
Total Suspended Solids (TSS)	mg/L	-	24.4	1660	12.6	48.7
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.080	0.0915	0.167	0.273	0.0529
Antimony	mg/L	0.00064	0.00074	0.0021	0.00091	0.0007
Arsenic	mg/L	0.0275	0.0310	0.0841	0.0347	0.0311
Barium	mg/L	0.166	0.195	0.436	0.15	0.132
Boron	mg/L	0.204	0.223	0.46	0.211	0.21
Cadmium	mg/L	0.000079	0.000036	0.000131	0.0000275	0.00007
Chromium	mg/L	0.00285	0.00373	0.0077	0.00337	0.00337
Cobalt	mg/L	0.00794	0.00817	0.0157	0.0113	0.0123
Copper	mg/L	0.0093	0.0103	0.0364	0.00685	0.00846
Lead	mg/L	0.00304	0.00391	0.00584	0.0031	0.00268
Manganese	mg/L	0.748	0.882	1.8	0.771	0.643
Mercury	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	0.0000132
Molybdenum	mg/L	0.00193	0.00371	0.0242	0.00656	0.00388
Nickel	mg/L	0.0350	0.0394	0.0967	0.0435	0.0522
Selenium	mg/L	0.00142	0.00184	0.00626	0.00155	0.00209
Silver	mg/L	<0.000050	<0.000050	0.00012	0.000059	0.00005
Thallium	mg/L	<0.000050	<0.000050	<0.00010	<0.000050	<0.000020
Tin	mg/L	<0.000050	<0.000050	<0.0010	<0.000050	0.0103
Uranium	mg/L	0.00214	0.00303	0.0119	0.00323	0.00263
Zinc	mg/L	0.032	0.0233	0.041	0.0165	0.0221
<b>Routine Water</b>						
Bicarbonate	mg/L	1310	1430	3440	1560	1,240
Chloride	mg/L	603	668	3040	831	461
Carbonate	mg/L	47.6	64.6	522	74.9	24.7
Electrical Conductivity (EC)	uS/cm	4570	4960	16400	5390	3,380
Calcium	mg/L	84.2	82.2	109	101	67.4
Potassium	mg/L	634	602	2420	696	47.6
Magnesium	mg/L	71.6	69.2	262	80	586
Sodium	mg/L	596	655	2840	596	420
Sulfate	mg/L	361	530	2940	715	213
Phosphorus	mg/L	26.9	26.8	34.8	26.2	20.3
pH in H <sub>2</sub> O	pH	8.64	8.68	9.12	8.74	8.51
TDS (Calculated)	mg/L	3040	3380	11000	4190	2,800
Nitrate	mg/L	0.570	0.26	<0.20	0.15	0.102
Nitrite	mg/L	0.083	0.073	<0.10	1.73	1.9
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	9.81	8.59	9.36	8.68	7.96
Electrical Conductivity (EC)	uS/cm	6.83	5430	5513	5580	2890

**Notes:**

"-" Not required under previous permit

**Table 1.14: Chemical Analytical Results**

Sample ID:		Magneson D.5				
Site Number:		14				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	370	380	670	282	202
Ammonia-N	mg/L	0.600	0.210	0.370	0.158	0.198
Total Kjeldahl Nitrogen	mg/L	13.9	14.6	23	9.63	4.93
Dissolved Organic Carbon	mg/L	100	100	171	84.6	68.3
Phenols	mg/L	0.0071	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	73.0	359.0	63.8	74.6
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0182	0.0145	1.21	0.0676	0.0041
Antimony	mg/L	0.00073	0.00059	0.00079	0.00104	0.00058
Arsenic	mg/L	0.0155	0.0168	0.0221	0.0242	0.0232
Barium	mg/L	0.0337	0.0317	0.0979	0.0817	0.0185
Boron	mg/L	0.048	0.059	0.079	0.031	0.071
Cadmium	mg/L	0.000012	<0.000010	0.000026	0.0000161	0.0000084
Chromium	mg/L	0.00055	0.00051	0.00153	<0.0010	<0.00050
Cobalt	mg/L	0.00428	0.00328	0.0032	0.00241	0.00362
Copper	mg/L	0.00527	0.00426	0.004	0.00187	0.00334
Lead	mg/L	0.00037	0.00017	0.00235	0.00014	<0.000050
Manganese	mg/L	0.220	0.218	0.342	0.0226	0.0996
Mercury	mg/L	0.0000063	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00592	0.00596	0.016	0.0238	0.0106
Nickel	mg/L	0.0225	0.0181	0.0228	0.0205	0.018
Selenium	mg/L	0.00088	0.00096	0.00121	0.00074	0.000752
Silver	mg/L	<0.000020	<0.000020	<0.000050	<0.000020	<0.000010
Thallium	mg/L	<0.000020	<0.000020	<0.000050	<0.000020	<0.000010
Tin	mg/L	<0.00020	<0.00020	<0.00050	<0.00020	0.00013
Uranium	mg/L	0.0023	0.00191	0.00347	0.00441	0.00268
Zinc	mg/L	0.004	0.0039	0.0088	<0.0020	<0.0010
<b>Routine Water</b>						
Bicarbonate	mg/L	850	795	1440	769	705
Chloride	mg/L	175	207	476	230	114
Carbonate	mg/L	21.7	40.1	107	80.5	36.5
Electrical Conductivity (EC)	uS/cm	2120	2230	3780	2500	1,560
Calcium	mg/L	50.3	45.7	83.3	51	40.6
Potassium	mg/L	119	122	137	113	18.9
Magnesium	mg/L	35.9	30.6	41.6	29.2	69.6
Sodium	mg/L	353	370	572	461	305
Sulfate	mg/L	162	185	333	319	168
Phosphorus	mg/L	10.1	12.5	2.17	2.05	3.88
pH in H <sub>2</sub> O	pH	8.53	8.78	8.89	9.11	8.84
TDS (Calculated)	mg/L	1340	1390	2460	1760	1,170
Nitrate	mg/L	0.557	0.19	<0.20	<0.10	0.243
Nitrite	mg/L	<0.020	0.065	<0.10	<0.050	0.011
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	11.75	8.81	9.13	9.31	8.53
Electrical Conductivity (EC)	uS/cm	2.78	2300	2551	2520	1238

**Notes:**

"-" Not required under previous permit

**Table 1.15: Chemical Analytical Results**

Sample ID:		Magneson D.6				
Site Number:		15				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	125	88	148	127	89
Ammonia-N	mg/L	<0.050	<0.050	0.28	0.0747	0.0361
Total Kjeldahl Nitrogen	mg/L	4.16	3.27	2.55	4.17	2.95
Dissolved Organic Carbon	mg/L	33.1	26.6	39	39.7	29.7
Phenols	mg/L	0.013	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	11.2	14.2	32	62.4
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0051	0.0136	0.0211	0.0041	0.0035
Antimony	mg/L	0.00086	0.00067	0.00107	0.00088	0.00059
Arsenic	mg/L	0.0134	0.0139	0.0337	0.0209	0.00977
Barium	mg/L	0.0512	0.0370	0.0465	0.0212	0.0237
Boron	mg/L	0.237	0.230	0.302	0.239	0.082
Cadmium	mg/L	0.000012	<0.000010	<0.000025	<0.000010	<0.0000100
Chromium	mg/L	<0.00020	<0.00020	<0.00050	<0.0010	<0.00100
Cobalt	mg/L	0.00075	0.0011	0.00084	0.00069	0.00044
Copper	mg/L	0.00174	0.00085	0.0013	0.0008	0.00207
Lead	mg/L	<0.00010	<0.00010	<0.00025	<0.00010	0.000101
Manganese	mg/L	0.00599	0.172	0.505	0.0308	0.0442
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00179	0.00128	0.00099	0.00151	0.0014
Nickel	mg/L	0.0082	0.0059	0.007	0.00495	0.00514
Selenium	mg/L	0.00029	0.00027	0.00029	0.000297	0.000334
Silver	mg/L	<0.000020	<0.000020	<0.000050	<0.000020	<0.000020
Thallium	mg/L	<0.000020	<0.000020	<0.000050	<0.000020	<0.000020
Tin	mg/L	<0.00020	<0.00020	<0.00050	<0.00020	<0.00020
Uranium	mg/L	0.00507	0.0040	0.0036	0.0044	0.00251
Zinc	mg/L	<0.0020	<0.0020	<0.0050	0.0021	0.0034
<b>Routine Water</b>						
Bicarbonate	mg/L	520	427	577	417	349
Chloride	mg/L	286	294	453	358	189
Carbonate	mg/L	16.6	11.2	12.7	28.1	5.8
Electrical Conductivity (EC)	uS/cm	3120	3050	4140	3760	2,190
Calcium	mg/L	97.9	91.4	83.6	67.4	54.7
Potassium	mg/L	34.1	26.6	40.2	33.1	37.7
Magnesium	mg/L	56.6	57.8	82.8	66.7	20.6
Sodium	mg/L	558	510	823	726	437
Sulfate	mg/L	818	772	1380	1210	686
Phosphorus	mg/L	0.745	0.582	1.25	0.625	0.335
pH in H <sub>2</sub> O	pH	8.52	8.48	8.47	8.84	8.43
TDS (Calculated)	mg/L	2120	1970	2920	2730	1,630
Nitrate	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
Nitrite	mg/L	<0.050	<0.050	<0.050	<0.050	<0.050
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	9.48	8.37	8.55	9.02	8.55
Electrical Conductivity (EC)	uS/cm	3.82	3170	2705	3770	1784

**Notes:**

"-" Not required under previous permit

**Table 1.16: Chemical Analytical Results**

Sample ID:		Beaver D.1				
Site Number:		16				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	93	84	114	185	132
Ammonia-N	mg/L	0.071	0.200	2.200	0.490	0.0495
Total Kjeldahl Nitrogen	mg/L	2.46	3.01	2.38	8.06	3.54
Dissolved Organic Carbon	mg/L	28.1	26.2	36.8	42.7	33.2
Phenols	mg/L	0.0099	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	8.0	12.0	161.0	113
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0036	0.0039	0.0218	0.0046	0.0022
Antimony	mg/L	0.00022	0.00027	0.00057	0.00042	0.00022
Arsenic	mg/L	0.00586	0.00534	0.0131	0.0114	0.00557
Barium	mg/L	0.0489	0.0504	0.0955	0.0243	0.022
Boron	mg/L	0.039	0.020	0.041	0.058	0.05
Cadmium	mg/L	0.0000056	<0.0000050	0.0000066	<0.0000050	<0.0000050
Chromium	mg/L	0.00013	0.00014	0.00016	<0.00050	<0.00050
Cobalt	mg/L	0.00038	0.00050	0.00136	0.00111	0.00072
Copper	mg/L	0.00071	0.00037	0.00154	0.00077	0.00049
Lead	mg/L	<0.000050	<0.000050	0.000059	<0.000050	0.000052
Manganese	mg/L	0.00491	0.134	0.494	0.409	0.229
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00067	0.00047	0.00268	0.00168	0.00113
Nickel	mg/L	0.00493	0.00347	0.00754	0.00695	0.00387
Selenium	mg/L	0.000205	0.000184	0.000491	0.000302	0.000167
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Uranium	mg/L	0.00115	0.000827	0.00362	0.0021	0.00126
Zinc	mg/L	<0.0010	<0.0010	0.0044	0.0011	0.0012
<b>Routine Water</b>						
Bicarbonate	mg/L	464	479	714	550	426
Chloride	mg/L	182	150	274	234	180
Carbonate	mg/L	6.7	7.4	22.8	13.3	3.8
Electrical Conductivity (EC)	uS/cm	1490	1400	2010	1830	1,280
Calcium	mg/L	53.7	45.5	75	73.8	56.6
Potassium	mg/L	19.1	15.3	25.4	20.9	22.7
Magnesium	mg/L	28.2	21.0	34.7	32.3	13
Sodium	mg/L	266	233	367	312	219
Sulfate	mg/L	131	116	173	170	140
Phosphorus	mg/L	1.41	1.68	1.3	2.21	1.98
pH in H <sub>2</sub> O	pH	8.37	8.42	8.58	8.52	8.38
TDS (Calculated)	mg/L	915	824	1230	1180	848
Nitrate	mg/L	<0.020	<0.020	0.153	<0.020	<0.020
Nitrite	mg/L	<0.010	0.017	0.149	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	10.32	8.15	8.53	8.68	8.32
Electrical Conductivity (EC)	uS/cm	1940	1458	1307	1878	1022

**Notes:**

"-" Not required under previous permit

**Table 1.18: Chemical Analytical Results**

Sample ID:		Beaver D.2				
Site Number:		18				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	158	106	Not monitored	Not monitored	Not monitored
Ammonia-N	mg/L	<0.050	0.183			
Total Kjeldahl Nitrogen	mg/L	4.19	3.29			
Dissolved Organic Carbon	mg/L	39.2	27.5			
Phenols	mg/L	0.0081	0.0018			
Total Suspended Solids (TSS)	mg/L	-	12.4			
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	Not monitored	Not monitored	Not monitored
Toluene	mg/L	<0.00050	<0.00050			
Ethylbenzene	mg/L	<0.00050	<0.00050			
Xylenes	mg/L	<0.00071	<0.00071			
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10			
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10			
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0035	0.0195	Not monitored	Not monitored	Not monitored
Antimony	mg/L	0.00021	0.00015			
Arsenic	mg/L	0.00247	0.00172			
Barium	mg/L	0.0716	0.0934			
Boron	mg/L	0.053	0.017			
Cadmium	mg/L	<0.000010	<0.0000050			
Chromium	mg/L	<0.00020	0.00019			
Cobalt	mg/L	0.00040	0.00062			
Copper	mg/L	0.00049	0.00027			
Lead	mg/L	<0.00010	0.000172			
Manganese	mg/L	0.00533	0.713			
Mercury	mg/L	<0.0000050	<0.0000050			
Molybdenum	mg/L	0.00095	0.000111			
Nickel	mg/L	0.0042	0.00261			
Selenium	mg/L	0.00018	0.000429			
silver	mg/L	<0.000020	<0.000010			
Thallium	mg/L	<0.000020	<0.000010			
Tin	mg/L	<0.00020	<0.00010			
Uranium	mg/L	0.000974	0.000385			
Zinc	mg/L	<0.0020	0.0028			
<b>Routine Water</b>						
Bicarbonate	mg/L	784	598	Not monitored	Not monitored	Not monitored
Chloride	mg/L	285	235			
Carbonate	mg/L	<5.0	5.0			
Electrical Conductivity (EC)	uS/cm	2120	1690			
Calcium	mg/L	109	75.3			
Potassium	mg/L	26.1	15.2			
Magnesium	mg/L	43.8	25.2			
Sodium	mg/L	330	256			
Sulfate	mg/L	78.4	61.2			
Phosphorus	mg/L	1.02	0.732			
pH in H <sub>2</sub> O	pH	8.10	8.33			
TDS (Calculated)	mg/L	1260	968			
Nitrate	mg/L	<0.040	<0.020			
Nitrite	mg/L	0.022	0.013			
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	9.89	7.95	Not monitored	Not monitored	Not monitored
Electrical Conductivity (EC)	uS/cm	2.62	1801			

**Notes:**

"-" Not required under previous permit

**Table 1.19: Chemical Analytical Results**

Sample ID:		Winsnes D.1				
Site Number:		19				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	75	83	73	80	203
Ammonia-N	mg/L	<0.050	0.251	0.71	0.061	0.152
Total Kjeldahl Nitrogen	mg/L	2.52	3.99	1.4	3.03	2.04
Dissolved Organic Carbon	mg/L	24.2	21.7	24.9	24.1	26.7
Phenols	mg/L	0.0077	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	13.0	11.2	20.6	502
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0017	0.0022	0.0096	0.0037	0.0038
Antimony	mg/L	0.0002	0.00029	0.00037	0.00023	0.00023
Arsenic	mg/L	0.00471	0.00454	0.00579	0.00529	0.00438
Barium	mg/L	0.0412	0.0729	0.0779	0.0592	0.0644
Boron	mg/L	0.039	0.029	0.044	0.034	0.037
Cadmium	mg/L	<0.000050	<0.000050	0.0000071	<0.000050	<0.000050
Chromium	mg/L	<0.00010	<0.00010	0.00011	<0.00050	<0.00050
Cobalt	mg/L	0.00035	0.00062	0.00056	0.00051	0.00037
Copper	mg/L	0.00027	0.00026	0.00177	0.00042	0.00027
Lead	mg/L	<0.000050	<0.000050	0.000055	<0.000050	<0.000050
Manganese	mg/L	0.00135	0.0111	0.136	<0.0050	0.0994
Mercury	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050
Molybdenum	mg/L	0.000602	0.000589	0.000873	0.000873	0.000545
Nickel	mg/L	0.00287	0.00304	0.00361	0.0029	0.00246
Selenium	mg/L	0.000204	0.000192	0.000263	0.000169	0.000195
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	0.00024
Uranium	mg/L	0.00116	0.00136	0.00194	0.00143	0.000849
Zinc	mg/L	<0.0010	<0.0010	0.013	0.0011	<0.0010
<b>Routine Water</b>						
Bicarbonate	mg/L	416	359	370	305	312
Chloride	mg/L	71.6	76.8	103	89.1	75.8
Carbonate	mg/L	10.8	7.6	<5.0	18.4	2.9
Electrical Conductivity (EC)	uS/cm	1060	1020	1120	1070	872
Calcium	mg/L	39.2	44.7	33.1	35.9	28
Potassium	mg/L	15.7	12.7	16.5	15.8	18.9
Magnesium	mg/L	23.7	24.1	26.9	25.2	13.8
Sodium	mg/L	174	164	179	180	142
Sulfate	mg/L	106	123	166	160	131
Phosphorus	mg/L	0.263	0.425	0.306	0.249	0.77
pH in H <sub>2</sub> O	pH	8.51	8.46	8.32	8.86	8.36
TDS (Calculated)	mg/L	646	630	709	698	582
Nitrate	mg/L	0.025	0.064	0.035	<0.020	<0.020
Nitrite	mg/L	0.014	0.025	<0.010	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	10.44	8.50	8.57	9.22	8.36
Electrical Conductivity (EC)	uS/cm	1306	1049	608	1098	706

**Notes:**

"-" Not required under previous permit

**Table 1.20: Chemical Analytical Results**

Sample ID:		Balash D.1				
Site Number:		20				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	79	75	65	96	116
Ammonia-N	mg/L	0.824	0.356	1.32	0.117	0.033
Total Kjeldahl Nitrogen	mg/L	3.35	3.20	1.46	3.52	3.21
Dissolved Organic Carbon	mg/L	25.3	24.1	25.1	23.5	23.3
Phenols	mg/L	0.0052	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	34.8	8.2	41.2	52.6
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0052	0.0128	0.0067	0.0041	0.0028
Antimony	mg/L	0.00013	0.00017	0.00011	<0.00010	0.00011
Arsenic	mg/L	0.00283	0.00274	0.00397	0.00297	0.00267
Barium	mg/L	0.0997	0.0979	0.116	0.0992	0.0529
Boron	mg/L	0.028	<0.010	<0.010	0.023	0.038
Cadmium	mg/L	0.0000063	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Chromium	mg/L	0.00012	0.00016	0.00011	<0.00050	<0.00050
Cobalt	mg/L	0.00031	0.00027	0.00057	0.00029	0.00037
Copper	mg/L	0.00026	0.00023	0.0011	0.0002	0.00052
Lead	mg/L	0.000071	0.000138	0.0001	<0.000050	0.000058
Manganese	mg/L	0.00851	0.0070	0.6550	0.0800	0.105
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	0.0000113	<0.0000050
Molybdenum	mg/L	0.00039	0.000304	0.000301	0.000419	0.000683
Nickel	mg/L	0.00293	0.00282	0.00257	0.00277	0.00256
Selenium	mg/L	0.000188	0.000245	0.00019	0.00017	0.000225
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Uranium	mg/L	0.000199	0.000235	0.000194	0.000245	0.000122
Zinc	mg/L	<0.0010	<0.0010	0.0029	<0.0010	0.0017
<b>Routine Water</b>						
Bicarbonate	mg/L	277	259	322	291	190
Chloride	mg/L	43.9	55.5	63	49.2	25.5
Carbonate	mg/L	<5.0	<5.0	<5.0	<1.0	<1.0
Electrical Conductivity (EC)	uS/cm	574	654	696	651	388
Calcium	mg/L	43.6	45.2	49.8	45.5	27.8
Potassium	mg/L	14.8	10.6	13.7	14.2	9.62
Magnesium	mg/L	15.8	16.8	16.7	16.2	10.9
Sodium	mg/L	57.3	74.3	67.1	74.6	44.9
Sulfate	mg/L	12.1	47.5	36.6	42.4	21.2
Phosphorus	mg/L	0.463	0.552	0.454	0.463	0.482
pH in H <sub>2</sub> O	pH	8.13	8.09	8.28	8.24	8.13
TDS (Calculated)	mg/L	324	378	406	423	266
Nitrate	mg/L	0.037	0.053	<0.020	<0.020	<0.020
Nitrite	mg/L	<0.010	<0.010	<0.010	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	9.26	7.73	7.81	8.23	8.71
Electrical Conductivity (EC)	uS/cm	714	681	450.9	673	344

**Notes:**

"-" Not required under previous permit



**Table 1.21: Chemical Analytical Results**

Sample ID:		Balash D.2				
Site Number:		21				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	21-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	93	130	175	148	90
Ammonia-N	mg/L	<0.050	0.072	0.26	0.0622	0.0363
Total Kjeldahl Nitrogen	mg/L	2.75	4.86	2.69	5.08	2.78
Dissolved Organic Carbon	mg/L	29.5	35.3	56.8	36.7	27.2
Phenols	mg/L	0.0093	<0.0010	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	29.6	53	55.8	31.4
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2(&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0071	0.0118	0.0035	0.0069	0.0014
Antimony	mg/L	0.00024	0.0003	0.00053	0.00039	0.00018
Arsenic	mg/L	0.00575	0.0064	0.0155	0.00898	0.00549
Barium	mg/L	0.0766	0.0595	0.103	0.114	0.0733
Boron	mg/L	0.05	<0.010	<0.010	0.048	0.022
Cadmium	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.000010	<0.0000050
Chromium	mg/L	<0.00010	0.00014	<0.00010	<0.0010	<0.00050
Cobalt	mg/L	0.00056	0.00090	0.00198	0.00147	0.00053
Copper	mg/L	0.00071	0.00061	0.0025	0.00158	0.00056
Lead	mg/L	<0.000050	0.000061	<0.000050	<0.00010	<0.000050
Manganese	mg/L	0.00437	0.0204	0.0227	0.286	0.00433
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.000719	0.000283	0.00164	0.00129	0.000679
Nickel	mg/L	0.00398	0.00343	0.00751	0.00614	0.00316
Selenium	mg/L	0.000201	0.000239	0.000475	0.000267	0.000185
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000020	<0.000010
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000020	<0.000010
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00020	0.00105
Uranium	mg/L	0.0021	0.00127	0.00338	0.00362	0.0021
Zinc	mg/L	<0.0010	<0.0010	<0.0010	<0.0020	<0.0010
<b>Routine Water</b>						
Bicarbonate	mg/L	435	472	671	494	338
Chloride	mg/L	244	311	537	393	256
Carbonate	mg/L	<5.0	8.3	25.7	30.1	20.2
Electrical Conductivity (EC)	uS/cm	1580	1800	2580	2410	1,910
Calcium	mg/L	69.8	61.4	86.6	105	76.7
Potassium	mg/L	22.6	37.7	47.2	39.3	50.5
Magnesium	mg/L	47.4	47.2	74.1	69.9	28.1
Sodium	mg/L	210	295	442	331	250
Sulfate	mg/L	104	57.2	92.7	300	284
Phosphorus	mg/L	0.755	1.50	0.72	0.93	0.658
pH in H <sub>2</sub> O	pH	8.22	8.41	8.61	8.73	8.67
TDS (Calculated)	mg/L	912	1050	1430	1570	1,130
Nitrate	mg/L	<0.020	<0.020	0.031	<0.020	<0.020
Nitrite	mg/L	<0.010	<0.010	<0.010	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	9.22	8.07	8.86	8.8	8.38
Electrical Conductivity (EC)	uS/cm	1960	1869	799	2470	1333

**Notes:**

"-" Not required under previous permit

**Table 1.22: Chemical Analytical Results**

Sample ID:		Balash D.3				
Site Number:		22				
Date Sampled:	Units	29-Oct-2019	8-Oct-2020	22-Oct-2021	19-Oct-2022	16-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	535	127	186	156	112
Ammonia-N	mg/L	0.075	0.059	1.32	0.109	0.0814
Total Kjeldahl Nitrogen	mg/L	17.0	4.78	3.25	5.13	3.74
Dissolved Organic Carbon	mg/L	31.2	44.0	55.4	48.0	41.4
Phenols	mg/L	0.0067	0.0014	<0.0010	<0.0010	<0.0010
Total Suspended Solids (TSS)	mg/L	-	27.4	434	32	49.2
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00050	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0165	0.0065	0.641	0.0111	0.0037
Antimony	mg/L	0.00019	0.00022	0.00037	<0.00020	<0.00020
Arsenic	mg/L	0.0057	0.00519	0.00704	0.00847	0.00588
Barium	mg/L	0.0437	0.0434	0.107	0.0503	0.0487
Boron	mg/L	0.033	<0.010	<0.010	<0.02	0.024
Cadmium	mg/L	<0.0000050	<0.0000050	0.0000152	<0.000010	<0.0000100
Chromium	mg/L	0.00014	0.00014	0.00078	<0.0010	<0.00100
Cobalt	mg/L	0.00101	0.00050	0.00166	0.00085	0.00047
Copper	mg/L	0.00101	<0.00020	0.00283	0.00074	0.00058
Lead	mg/L	0.000139	<0.000050	0.000967	<0.00010	<0.000100
Manganese	mg/L	0.410	0.00827	0.288	0.0551	0.077
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.000865	0.000193	0.00154	0.000922	0.000474
Nickel	mg/L	0.00233	0.00188	0.00503	0.00269	0.00199
Selenium	mg/L	0.000201	0.000168	0.000324	0.000208	0.000161
Silver	mg/L	<0.000010	<0.000010	<0.000010	<0.000020	<0.000020
Thallium	mg/L	<0.000010	<0.000010	<0.000010	<0.000020	<0.000020
Tin	mg/L	<0.00010	<0.00010	<0.00010	<0.00020	0.00182
Uranium	mg/L	0.000959	0.000561	0.00331	0.00175	0.000809
Zinc	mg/L	0.0012	<0.0010	0.0074	<0.0020	<0.0020
<b>Routine Water</b>						
Bicarbonate	mg/L	264	408	607	334	337
Chloride	mg/L	246	294	515	469	384
Carbonate	mg/L	<5.0	<5.0	15.7	37.8	6.7
Electrical Conductivity (EC)	uS/cm	1230	1640	2450	2350	2,250
Calcium	mg/L	45.1	53.5	81.9	70.7	68.3
Potassium	mg/L	26.0	37.1	45.5	39.4	50.8
Magnesium	mg/L	29.2	40.4	55.6	57.4	33.8
Sodium	mg/L	173	269	359	359	319
Sulfate	mg/L	37.4	43.3	93.9	244	262
Phosphorus	mg/L	2.55	1.28	0.334	0.84	1.58
pH in H <sub>2</sub> O	pH	7.99	8.32	8.5	9.04	8.38
TDS (Calculated)	mg/L	687	941	1470	1490	1,340
Nitrate	mg/L	<0.020	<0.020	0.039	0.024	<0.020
Nitrite	mg/L	<0.010	<0.010	0.011	<0.010	<0.010
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	9.67	8.01	7.84	9.33	8.46
Electrical Conductivity (EC)	uS/cm	1545	1687	849.1	2430	1573

**Notes:**

"-" Not required under previous permit

**Table 1.23: Chemical Analytical Results**

Sample ID:		Lyons D.1
Site Number:		23
Date Sampled:	Units	17-Oct-2023
Chem. O <sub>2</sub> Demand	mg/L	101
Ammonia-N	mg/L	0.403
Total Kjeldahl Nitrogen	mg/L	3.43
Dissolved Organic Carbon	mg/L	32.8
Phenols	mg/L	<0.0010
Total Suspended Solids (TSS)	mg/L	24
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2(&gt;C<sub>10</sub>-C<sub>16</sub>)</b>		
Benzene	mg/L	<0.00050
Toluene	mg/L	<0.00050
Ethylbenzene	mg/L	<0.00050
Xylenes	mg/L	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.100
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10
<b>Dissolved Metals</b>		
Aluminium	mg/L	0.137
Antimony	mg/L	0.00014
Arsenic	mg/L	0.00469
Barium	mg/L	0.0473
Boron	mg/L	0.051
Cadmium	mg/L	<0.0000050
Chromium	mg/L	<0.00050
Cobalt	mg/L	0.00056
Copper	mg/L	0.00105
Lead	mg/L	0.000105
Manganese	mg/L	0.0372
Mercury	mg/L	<0.0000050
Molybdenum	mg/L	0.000758
Nickel	mg/L	0.00364
Selenium	mg/L	0.00023
Silver	mg/L	<0.000010
Thallium	mg/L	<0.000010
Tin	mg/L	0.00018
Uranium	mg/L	0.000569
Zinc	mg/L	0.0036
<b>Routine Water</b>		
Bicarbonate	mg/L	294
Chloride	mg/L	10.8
Carbonate	mg/L	4.9
Electrical Conductivity (EC)	uS/cm	541
Calcium	mg/L	15
Potassium	mg/L	7.02
Magnesium	mg/L	19.7
Sodium	mg/L	91.5
Sulfate	mg/L	21.3
Phosphorus	mg/L	0.44
pH in H <sub>2</sub> O	pH	8.35
TDS (Calculated)	mg/L	354
Nitrate	mg/L	0.165
Nitrite	mg/L	0.021
<b>Field Data</b>		
pH in H <sub>2</sub> O	pH	8.55
Electrical Conductivity (EC)	uS/cm	426

**Notes:**

"-" Not required under previous permit

**Table 2: Duplicate 1 Chemical Analytical Results**

Sample ID:			MAGNESON D.2			
Site Number:			MAGNESON D.2	DUPLICATE 1	% RPD	Pass/ Fail (>20%)
Date Sampled:			17-Oct-2023	17-Oct-2023		
Parameter	Units	RDL				
Chem. O <sub>2</sub> Demand	mg/L	10	192	134	36%	Fail
Ammonia-N	mg/L	0.05	0.902	0.89	1%	Pass
Total Kjeldahl Nitrogen	mg/L	0.2	6.35	6.29	1%	Pass
Dissolved Organic Carbon	mg/L	1	50.9	52.8	4%	Pass
Phenols	mg/L	0.001	<0.0010	<0.0010	-	Pass
Total Suspended Solids (TSS)	mg/L	3	86.4	92.2	6%	Pass
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>						
Benzene	mg/L	0.0005	<0.00050	<0.00050	-	Pass
Toluene	mg/L	0.0005	<0.00050	<0.00050	-	Pass
Ethylbenzene	mg/L	0.0005	<0.00050	<0.00050	-	Pass
Xylenes (m & p)	mg/L	0.0005	<0.00040	<0.00040	-	Pass
Xylene (o)	mg/L	0.0005	<0.00030	<0.00030	-	Pass
Xylenes	mg/L	0.00071	<0.00050	<0.00050	-	Pass
Styrene	mg/L	0.0005	<0.00050	<0.00050	-	Pass
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	0.1	<0.10	<0.10	-	Pass
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	0.1	<0.100	<0.100	-	Pass
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	0.1	<0.10	<0.10	-	Pass
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.001	0.356	0.418	16%	Pass
Antimony	mg/L	0.0001	0.00023	0.00021	-	Pass
Arsenic	mg/L	0.0001	0.00833	0.0085	2%	Pass
Barium	mg/L	0.0001	0.0858	0.0892	4%	Pass
Beryllium	mg/L	0.0001	0.000065	0.000065	-	Pass
Boron	mg/L	0.01	0.05	0.052	-	Pass
Cadmium	mg/L	0.000005	0.0000334	0.0000381	13%	Pass
Chromium	mg/L	0.0001	0.00069	0.00073	6%	Pass
Cobalt	mg/L	0.0001	0.00198	0.00201	2%	Pass
Copper	mg/L	0.0002	0.00294	0.00291	1%	Pass
Iron	mg/L	0.01	3.95	4.14	5%	Pass
Lead	mg/L	0.00005	0.00204	0.00206	1%	Pass
Lithium	mg/L	0.001	0.0115	0.0113	2%	Pass
Manganese	mg/L	0.0001	0.0885	0.089	1%	Pass
Mercury	mg/L	0.000005	<0.0000050	<0.0000050	-	Pass
Molybdenum	mg/L	0.00005	0.00272	0.00251	8%	Pass
Nickel	mg/L	0.0005	0.00893	0.00881	1%	Pass
Selenium	mg/L	0.00005	0.000392	0.000433	10%	Pass
Silver	mg/L	0.00001	0.000013	0.000011	-	Pass
Thallium	mg/L	0.00001	<0.000010	<0.000010	-	Pass
Tin	mg/L	0.0001	0.00029	<0.00010	-	Pass
Titanium	mg/L	0.0003	0.0116	0.0157	30%	Fail
Uranium	mg/L	0.00001	0.00158	0.00152	4%	Pass
Vanadium	mg/L	0.0005	0.00754	0.0078	3%	Pass
Zinc	mg/L	0.001	0.0066	0.0045	-	Pass
<b>Routine Water</b>						
Bicarbonate	mg/L	5	293	309	5%	Pass
Chloride	mg/L	0.5	20.9	20.9	0%	Pass
Carbonate	mg/L	5	2.9	<1.0	-	Pass
Conductivity (EC)	uS/cm	2	500	546	9%	Pass
Calcium	mg/L	0.5	22.1	21	5%	Pass
Potassium	mg/L	0.5	8.98	8.95	0%	Pass
Magnesium	mg/L	0.1	28.6	29.2	2%	Pass
Sodium	mg/L	1	75.1	73.9	2%	Pass
Sulfate	mg/L	0.3	4.18	4.23	1%	Pass
Phosphorus	mg/L	0.05	2.72	2.94	8%	Pass
pH in H <sub>2</sub> O	pH	0.1	8.38	8.23	2%	Pass
TDS (Calculated)	mg/L	10	383	389	2%	Pass
Nitrate	mg/L	0.02	0.503	0.518	3%	Pass
Nitrite	mg/L	0.01	0.065	0.07	7%	Pass
Nitrate and Nitrite (as N)	mg/L	0.022	0.568	0.588	3%	Pass
Hardness as CaCO <sub>3</sub>	mg/L	N/A	92.2	89.3	-	Pass
Alkalinity (total as CaCO <sub>3</sub> )	mg/L	2	245	253	3%	Pass
Hydroxide	mg/L	5	<1.0	<1.0	-	Pass
Fluoride	mg/L	0.02	0.361	0.342	5%	Pass

**Notes:**

RDL - Reportable detection limit

RPD - Relative Percentage Difference calculated as  $RPD(\%) = \frac{|V1-V2|}{(V1+V2)/2} * 100$  where V1, V2 = concentrations of parent and duplicate sample, respectively.

.\* Indicates RPD not calculated. RPDs have only been calculated where a concentration is greater than 5 times the RDL

N/A - Not applicable

Shaded- RPD value greater than 20%

**Table 3: Duplicate 2 Chemical Analytical Results**

Sample ID:			BOOTH D.1			
Site Number:			BOOTH D.1	DUPLICATE 2	% RPD	Pass/ Fail (>20%)
Date Sampled:			16-Oct-2023	16-Oct-2023		
Parameter	Units	RDL				
Chem. O <sub>2</sub> Demand	mg/L	10	127	67	62%	Fail
Ammonia-N	mg/L	0.005	0.128	0.127	1%	Pass
Total Kjeldahl Nitrogen	mg/L	0.2	4.36	4.06	7%	Pass
Dissolved Organic Carbon	mg/L	0.5	29.8	26.3	12%	Pass
Phenols	mg/L	0.001	<0.0010	<0.0010	-	Pass
Total Suspended Solids (TSS)	mg/L	3	29	20.8	33%	Fail
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>						
Benzene	mg/L	0.0005	<0.00050	<0.00050	-	Pass
Toluene	mg/L	0.0005	<0.00050	<0.00050	-	Pass
Ethylbenzene	mg/L	0.0005	<0.00050	<0.00050	-	Pass
Xylenes (m & p)	mg/L	0.0003	<0.00040	<0.00040	-	Pass
Xylene (o)	mg/L	0.0004	<0.00030	<0.00030	-	Pass
Xylenes	mg/L	0.0005	<0.00050	<0.00050	-	Pass
Styrene	mg/L	0.0005	<0.00050	<0.00050	-	Pass
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	0.1	<0.10	<0.10	-	Pass
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	0.1	<0.100	<0.100	-	Pass
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	0.1	<0.10	<0.10	-	Pass
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.001	0.0027	0.0016	-	Pass
Antimony	mg/L	0.0001	0.00023	0.00018	-	Pass
Arsenic	mg/L	0.0001	0.00647	0.00656	1%	Pass
Barium	mg/L	0.0001	0.0503	0.0486	3%	Pass
Beryllium	mg/L	0.00002	<0.000020	<0.000020	-	Pass
Boron	mg/L	0.01	0.048	0.05	-	Pass
Cadmium	mg/L	0.000005	0.0000052	0.0000061	-	Pass
Chromium	mg/L	0.0005	<0.00050	<0.00050	-	Pass
Cobalt	mg/L	0.0001	0.00035	0.00032	-	Pass
Copper	mg/L	0.0002	0.00054	0.0004	-	Pass
Iron	mg/L	0.03	0.142	0.134	-	Pass
Lead	mg/L	0.00005	0.000098	0.000074	-	Pass
Lithium	mg/L	0.001	0.0384	0.0358	7%	Pass
Manganese	mg/L	0.005	0.00556	0.00528	-	Pass
Mercury	mg/L	0.000005	<0.0000050	<0.0000050	-	Pass
Molybdenum	mg/L	0.00005	0.00106	0.000969	9%	Pass
Nickel	mg/L	0.0005	0.00384	0.00345	11%	Pass
Selenium	mg/L	0.00005	0.000132	0.000155	-	Pass
Silver	mg/L	0.00001	<0.000010	<0.000010	-	Pass
Thallium	mg/L	0.00001	<0.000010	<0.000010	-	Pass
Tin	mg/L	0.0001	0.0003	<0.00010	-	Pass
Titanium	mg/L	0.0003	0.00065	0.00049	-	Pass
Uranium	mg/L	0.00001	0.000525	0.00047	11%	Pass
Vanadium	mg/L	0.0005	0.0012	0.00118	-	Pass
Zinc	mg/L	0.001	<0.0010	<0.0010	-	Pass
<b>Routine Water</b>						
Bicarbonate	mg/L	1	350	342	2%	Pass
Chloride	mg/L	0.5	35	34.6	1%	Pass
Carbonate	mg/L	1	5.3	6.1	14%	Pass
Conductivity (EC)	uS/cm	2	689	765	10%	Pass
Calcium	mg/L	0.05	22.6	20.4	10%	Pass
Potassium	mg/L	0.05	10.2	9.58	6%	Pass
Magnesium	mg/L	0.005	13.2	12.7	4%	Pass
Sodium	mg/L	0.05	140	129	8%	Pass
Sulfate	mg/L	0.3	51.6	50.8	2%	Pass
Phosphorus	mg/L	0.05	0.607	0.619	2%	Pass
pH in H <sub>2</sub> O	pH	0.1	8.46	8.39	1%	Pass
TDS (Calculated)	mg/L	1	460	461	0%	Pass
Nitrate	mg/L	0.02	<0.020	<0.020	-	Pass
Nitrite	mg/L	0.01	<0.010	<0.010	-	Pass
Nitrate and Nitrite (as N)	mg/L	0.05	<0.0500	<0.0500	-	Pass
Hardness as CaCO <sub>3</sub>	mg/L	0.5	98.4	90.4	8%	Pass
Alkalinity (total as CaCO <sub>3</sub> )	mg/L	2	295	290	2%	Pass
Hydroxide	mg/L	1	<1.0	<1.0	-	Pass
Fluoride	mg/L	0.02	0.283	0.285	1%	Pass

**Notes:**

RDL - Reportable detection limit

RPD - Relative Percentage Difference calculated as  $RPD(\%) = \frac{|V1 - V2|}{(V1 + V2) / 2} * 100$  where V1, V2 = concentrations of parent and duplicate sample, respectively.

“-” Indicates RPD not calculated. RPDs have only been calculated where a concentration is greater than 5 times the RDL

N/A - Not applicable

Shaded- RPD value greater than 20%

**Table 4: Historical and 2023 Precipitation Data - Total Precipitation (mm)**

Year	January	February	March	April	May	June	July	August	September	October	November	December	Total Annual
1996	23	16	18	32.3	29.4	91.8	119.5	106.6	98.8	16.6	68.2	32.2	<b>652.4</b>
1997	11.1	12	24.5	27.7	50.7	143.3	52.3	71.4	96.6	31.6	7.2	4.5	<b>532.9</b>
1998	23	0	12.4	35.2	32.8	99.6	73	32.8	53.8	16.4	17.8	30	<b>426.8</b>
1999	64	4	19	19.6	64.8	21.6	123.8	60.8	11.4	9.4	14.6	12	<b>425</b>
2000	17.5	5	32	24	55.3	73.7	118	32.8	56.6	1	6.5	10	<b>432.4</b>
2001	1	5.8	6.5	0.8	55.2	94.2	260.2	8.4	37.4	23.4	34.5	6	<b>533.4</b>
2002	6	3.5	26	29.4	11.6	35.8	40	70	15.2	39.7	12	3	<b>292.2</b>
2003	39.7	19	20	46.9	64.3	110	80.8	40.8	27.2	23	19	8	<b>498.7</b>
2004	30.5	4	43	22.8	57.5	37.3	131.4	67.3	44.8	31.2	0	34.3	<b>504.1</b>
2005	10	5	35.5	18.6	43.6	95.3	82.8	59.3	24.4	18	3	14	<b>409.5</b>
2006	6	33	40	7.2	72.4	54.3	52.8	47.6	90.2	39.2	45	19.8	<b>507.5</b>
2007	7	23	5	46.9	51.5	78.8	59	59.1	9	5.8	9.6	27	<b>381.7</b>
2008	20.5	9	13.5	63.6	39	64.9	70.9	27.8	41.2	2.8	9	35	<b>397.2</b>
2009	22	9	24	32.7	7.6	20.6	67.6	19.2	5.8	31.1	8.6	41.5	<b>289.7</b>
2010	17	4	5	70.8	70	73.2	109	41.8	43.6	8.7	14	34	<b>491.1</b>
2011	69	20.5	8	14.4	6.8	146.6	113.4	61	12.4	14.8	19.2	16	<b>502.1</b>
2012	9	21.5	23	46.6	64.2	58.8	152.4	93.2	24.7	33.4	43	52	<b>621.8</b>
2013	39.5	10.5	31	17	23.9	96.6	101.4	71.6	4	9.8	61	41.5	<b>507.8</b>
2014	8.7	10.2	5.8	75.8	42.3	98.4	120.1	13.9	34.1	10.8	42.4	5.5	<b>468</b>
2015	19.8	24.9	31.3	16.5	37.3	59.7	108.6	10.3	71.1	22.7	17.4	3.5	<b>423.1</b>
2016	26.3	7.6	15.6	7.4	104	64.6	77.3	38.4	10.5	31.4	12.7	12	<b>407.8</b>
2017	10.2	1.9	5.9	45.9	56.5	32.4	44.5	41.3	27.1	25.2	2.4	5.7	<b>299</b>
2018	20.3	14.3	18.4	24.3	42.4	75.0	85.2	59.5	39.4	18.0	17.1	17.3	<b>431.2</b>
2019	26.8	18.6	7.1	29.6	49	155.8	153.7	31	43.7	27.3	25.3	11.1	<b>579</b>
2020	23.6	33	18.8	6	93.5	121.4	121.9	68.4	4.9	14.7	45.5	4.9	<b>556.6</b>
2021	10.8	12.2	7.3	13.2	65.5	38.9	25.3	63.5	22.4	9.1	21.1	39.2	<b>328.5</b>
2022	39.1	14.8	39.2	30	29	109.3	35	34.4	10.6	6.5	32.4	19.6	<b>399.9</b>
2023	3.3	6.1	3	23.8	40	128.8	110	56.3	11.8	4.8	2.6	6.2	<b>396.7</b>
<b>Mean</b>	<b>21.6</b>	<b>12.4</b>	<b>19.2</b>	<b>29.8</b>	<b>48.6</b>	<b>81.5</b>	<b>96.1</b>	<b>49.6</b>	<b>36.6</b>	<b>18.8</b>	<b>21.8</b>	<b>19.5</b>	<b>453.4</b>

1. Denotes - Based on Incomplete Data so annual total is not reliable.

2. Data collected from Elk Island National Park Station (2014-2015, 2019-2022), Holden AGDM Stations (2016-2018) and Tofield North (1996-2013)

3. Link to 1996-2013, 2014-2015, 2019-2023 Data: [http://climate.weather.gc.ca/historical\\_data/search\\_historic\\_data\\_e.html](http://climate.weather.gc.ca/historical_data/search_historic_data_e.html)


4. Link to 2016-2018 data: <http://agriculture.alberta.ca/acis/alberta-weather-data-viewer.jsp>

5. Blank - No data

## FIGURES

- Figure 1 Dugout Sampling Location Plan
- Figure 2 Parameters with 2023 Maximum Value Trend Charts

G:\SOLID\_WASTE\SWOP\SWOP04810-01\GIS\Maps\SWOP04810-01\_Fig01\_SamplingPlan.mxd modified 2/13/2024 by MEGAN BURNS



**LEGEND**

- Rural Residence
- Water Sample Location
- Westmancoat - Need Landowner Approval
- Removed
- Site Outline
- 1.6 km Buffer
- Road
- Abandoned Railway Bed (Approximate Centreline)
- ~ Bible Creek (Approximate Centreline)
- Bible Creek Flow Direction
- Potential Wetland

**NOTES**  
 Base data source:  
 CanVec 1:50,000 (2019)  
 Imagery from ESRI; Maxar (2017/2021)

STATUS  
ISSUED FOR USE

**2023 DUGOUT SAMPLING PROGRAM  
 CLASS 1 WASTE MANAGEMENT FACILITY  
 RYLEY, AB**

**Dugout Sampling Location Plan**

<b>PROJECTION</b> UTM Zone 12	<b>DATUM</b> NAD83	<b>CLIENT</b> 
Scale: 1:20,000		
<div style="display: flex; justify-content: space-between; width: 100%;"> <span>400</span> <span>200</span> <span>0</span> <span>400</span> </div> <div style="text-align: center; border-top: 1px solid black; width: 100%;"></div> <p style="text-align: center; margin-top: 5px;">Metres</p>		
<b>FILE NO.</b> SWOP04810-01_Fig01_SamplingPlan.mxd		
<b>OFFICE</b> TL-VANC	<b>DWN</b> SL	<b>CKD</b> BB
<b>DATE</b> February 13, 2024	<b>APVD</b> FN	<b>REV</b> 0
<b>PROJECT NO.</b> SWM.SWOP04810-01		<b>Figure 1</b>











**Figure 2: Trend Charts**





**Figure 2: Trend Charts**















**Figure 2: Trend Charts**








Figure 2: Trend Charts














Figure 2: Trend Charts








Figure 2: Trend Charts











Figure 2: Trend Charts



## APPENDIX A

### REGULATORY APPROVAL - ALBERTA ENVIRONMENT AND PARKS EPEA APPROVAL NO.10348-03-01

AMENDING APPROVAL

PROVINCE OF ALBERTA

ENVIRONMENTAL PROTECTION AND ENHANCEMENT ACT
R.S.A. 2000, c.E-12, as amended.

APPROVAL NO. 10348-03-01

APPLICATION NO. 015-10348

EFFECTIVE DATE: June 21, 2022

EXPIRY DATE: March 31, 2027

APPROVAL HOLDER: Clean Harbors Canada, Inc.

Pursuant to Division 2, of Part 2, of the Environmental Protection and Enhancement Act, R.S.A.2000, c.E-12, as amended, the approval for the following activity:

construction, operation and reclamation of Ryley Industrial Waste Management Facility, consisting of a Class I and Class II Industrial Landfill and a Hazardous Waste/Recyclable Storage and Processing Facility

is amended as per the attached terms and conditions.

[Handwritten Signature]

Designated Director under the Act Mohammad Habib, P. Eng.

Date Signed June 21, 2022

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

1. *Environmental Protection and Enhancement Act* Approval No. 10348-03-00 is hereby amended by this Amending Approval.
2. Parts 1, 2, 3, 4, 5, 6, 7 and 8 are deleted, and the following are substituted:

**PART 1: DEFINITIONS**

**SECTION 1.1: DEFINITIONS**

- 1.1.1 All definitions from the Act and the regulations apply except where expressly defined in this approval.
- 1.1.2 In all PARTS of this approval:
  - (a) "Act" means the *Environmental Protection and Enhancement Act*, R.S.A. 2000, c.E-12, as amended;
  - (b) "action leakage rate" means the leakage rate that would occur through the primary liner, based on two holes per hectare, each with a diameter of 2 mm and that is calculated to be 790L/ha/day;
  - (c) "active landfill area" means the portion of the landfill that has received or is receiving waste for disposal, where final cover has not been placed, and includes areas that are being used for interim management of waste prior to disposition;
  - (d) "active landfill life" means the period of landfill life during which waste is received for disposal at the landfill, beginning with the initial receipt of waste and ending with the start of final landfill closure activities;
  - (e) "AER" means Alberta Energy Regulator;
  - (f) "affected lands" means lands which have received substances released from the facility;
  - (g) "air effluent stream" means any substance in a gaseous medium released by or from a facility;
  - (h) "APEGA" means the Association of Professional Engineers and Geoscientists of Alberta;
  - (i) "application" means the written submissions from the approval holder to the Director in respect of application No. 014-10348 and any subsequent applications where amendments are issued for this approval;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (j) "application No. 005-10348" means the written submissions from the approval holder to the Director in respect of renewal application No. 005-10348;
- (k) "application No. 008-10348" means the written submissions from the approval holder to the Director in respect of amendment application No. 008-10348;
- (l) "application No. 012-10348" means the written submissions from the approval holder to the Director in respect of amendment application No. 012-10348;
- (m) "as-built plans" means survey plans, signed and stamped by a professional registered with APEGA, that document variances from design or construction plans that were either approved or authorized according to the terms and conditions of this approval;
- (n) "BTEX" means benzene, toluene, ethylbenzene and xylene;
- (o) "CAO" means Chief Administrative Officer;
- (p) "central waste receiving and stabilization area" means the central waste receiving and stabilization area as described in application No. 015-10348;
- (q) "COD" means Chemical Oxygen Demand;
- (r) "composite liner" means a liner that meets the specifications in 3.1.2(b) of this approval;
- (s) "container" means any portable device in which a substance is kept, including but not limited to the following:
  - (i) drums, barrels and pails which have a capacity greater than 18 litres but less than 210 litres,
  - (ii) 320 litre overpack drums, and
  - (iii) 1000 litre tote tanks or sacks;
- (t) "cover" means soil or other approved material that is used to cover compacted wastes in a landfill cell;
- (u) "day", when referring to sampling, means any sampling period of 24 consecutive hours;
- (v) "decommissioning" means the dismantling and decontamination of the facility undertaken subsequent to the termination or abandonment of any

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

activity or any part of any activity regulated under the Act, excluding the landfill cells and those infrastructure components and facilities that are required for the landfill post-closure;

- (w) "decontamination" means the treatment or removal of substances from the facility and affected lands;
- (x) "Director" means an employee of the Government of Alberta designated as a Director under the Act;
- (y) "dismantling" means the removal of buildings, structures, process and pollution abatement equipment, vessels, storage facilities, material handling facilities, railways, roadways, pipelines and any other installations that are being or have been used or held for or in connection with the facility;
- (z) "DOC" means Dissolved Organic Carbon;
- (aa) "domestic wastewater" means wastewater that is the composite of liquid and water-carried wastes associated with the use of water for drinking, cooking, cleaning, washing, hygiene, sanitation or other domestic purposes, together with any infiltration and inflow wastewater, that is released into a wastewater collection system;
- (bb) "domestic wastewater system" means the parts of the facility that collect, store, or treat domestic wastewater from the facility;
- (cc) "existing landfill cells" means Cell 1, Cell 2, Cell 3A, Cell 3B, and Cell 3C as described in application No. 005-10348;
- (dd) "facility" means all buildings, structures, process and pollution abatement equipment, vessels, storage facilities, material handling facilities, roadways, railways, pipelines and other installations, the Class I and Class II industrial landfill and the HWRSP Facility, and includes the land, located on the SE  $\frac{1}{4}$  and NE  $\frac{1}{4}$  of Section 9, Township 50, Range 17, West of the 4<sup>th</sup> Meridian, that is being or has been used or held for or in connection with the Ryley Industrial Waste Management Facility;
- (ee) "facility developed area" means the areas of the facility used for the storage, treatment, processing, transport, or handling of raw material, intermediate product, by-product, finished product, process chemicals, or waste material, and includes the active landfill area;
- (ff) "final cover" means a designed system, natural or man-made, that is placed on the surface of a landfill or landfill cell that has reached its maximum designated waste elevation to control transmission of moisture and landfill gas, and conforms to the end use plan;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (gg) “final landfill closure” means the period of time when waste is no longer placed in the defined portion of a landfill and activities are undertaken to complete the final cover system and decommission components and facilities that are no longer required, and includes the construction of any additional components or monitoring systems that are necessary for post-closure;
- (hh) “free liquids” means the liquids as determined by the US EPA SW-846 Test Method 9095B: Paint Filter Liquids Test, as specified in Test Methods for Evaluating Solid Waste: Physical/Chemical Methods, US EPA Publication No. SW-846, as amended;
- (ii) “fugitive emissions” means emissions of substances to the atmosphere other than ozone depleting substances, originating from a facility source other than a flue, vent, or stack but does not include sources which may occur due to breaks or ruptures in process equipment;
- (jj) “GCL” means geosynthetic clay liner that is made of a thin layer of bentonite either bonded to a geomembrane or fixed between two sheets of geotextile;
- (kk) “geomembrane” means a sheet of manufactured synthetic material designed to control migration of liquid and gas;
- (ll) “grab sample” means an individual sample collected in less than 30 minutes and which is representative of the substance sampled;
- (mm) “groundwater” means groundwater as defined in the *Water Act*, R.S.A. 2000, c.W-3, as amended;
- (nn) “groundwater monitoring well” means a well drilled at a site to measure groundwater levels and collect groundwater samples for the purpose of physical, chemical, or biological analysis to determine the concentration of groundwater constituents;
- (oo) “H<sub>2</sub>S” means hydrogen sulphide;
- (pp) “HDPE” means High Density Polyethylene;
- (qq) “HWRSP Facility” means the Hazardous Waste/Recyclable Storage and Processing Facility as described in the application for storage, processing and transfer of hazardous wastes and hazardous recyclables and which includes the Maintenance Shop, and is an integral part of the facility;
- (rr) “hydraulic conductivity” means the ease with which water can be transported through a material;



**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (ss) "hydrocarbon" means a chemical compound that consists entirely of hydrogen and carbon;
- (tt) "ISO/IEC 17025" means the international standard, developed and published by International Organization for Standardization (ISO), specifying management and technical requirements for laboratories;
- (uu) "incompatible waste" means waste materials which could cause dangerous reactions from direct contact with one another;
- (vv) "industrial wastewater" means the composite of liquid wastes and water-carried wastes, any portion of which results from any industrial process carried on at the HWRSP Facility;
- (ww) "landfill" means the Class I and Class II industrial landfill as described in the application and which includes the waste receiving area(s) and waste stabilization area(s), and is an integral part of the facility;
- (xx) "landfill cell" means a designed area of a landfill comprised of an excavation or earthen structure in which waste is enclosed;
- (yy) "landfill cell closure" means the construction of a final cover for landfill cell including placement of previously conserved top soil and upper subsoil and re-vegetation as required for the intended future use of the landfill;
- (zz) "landfill gas" means a mixture of gases generated by the microbial decomposition of and chemical reactions between wastes in a landfill;
- (aaa) "lateral expansion" means an expansion of landfill cell boundaries beyond the approved area;
- (bbb) "laydown area" means the laydown area as described in application No. 015-10348;
- (ccc) "leachate" means a liquid that has been in contact with waste in the landfill cell and has undergone chemical or physical changes;
- (ddd) "leachate collection system" means a system that gathers leachate so that it may be removed from a landfill, and includes a permeable drainage material, a network of perforated pipes and sumps or manholes from where leachate can be removed;
- (eee) "leak detection liquid" means any liquid collected within the leak detection system;
- (fff) "leak detection system" means a system that gathers liquid between a primary liner and a secondary liner system, and consists of a permeable

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

drainage material, a network of perforated pipes and sumps or manholes from where the liquid can be removed;

(ggg) “liner” means a continuous layer of synthetic material or compacted natural clay placed beneath and at the sides of a landfill cell that is compatible with the waste and restricts the migration of leachate, or landfill gas, or both;

(hhh) “local environmental authority” means the Department of Environment and Parks, in the Province of Alberta, or the agency that has the equivalent responsibilities for any jurisdiction outside the Province;

(iii) “major ions” means the following:

Calcium	Carbonate
Magnesium	Bicarbonate
Sodium	Chloride
Potassium	Sulfate

(jjj) “maximum acceptable leachate head” means the maximum depth of leachate above the lowest part of the primary liner, not including the sumps or leachate collection pipe trenches, and is:

(i) 1.0 m in each of the existing landfill cells, and

(ii) 0.3 m in each of the new landfill cells

during active landfill life, landfill cell closure, final landfill closure, and post-closure;

(kkk) “maximum designated waste elevation” means the maximum elevation of waste in metres above sea level that can be disposed of at the landfill prior to construction of final cover, and is 714 metres;

(lll) “metals” means the following:

Aluminum, dissolved	Chromium, dissolved (hexavalent)	Nickel, dissolved
Antimony, dissolved	Cobalt, dissolved	Selenium, dissolved
Arsenic, dissolved	Copper, dissolved	Silver, dissolved
Barium, dissolved	Lead, dissolved	Thallium, dissolved
Boron, dissolved	Manganese, dissolved	Tin, dissolved
Cadmium, dissolved	Mercury, total	Uranium, dissolved
Chromium, total	Molybdenum, dissolved	Zinc, dissolved

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (mmm) "monitoring system" means all equipment used for sampling, conditioning, analyzing or recording data in respect of any parameter listed or referred to in this approval, including equipment used for continuous monitoring;
- (nnn) "month" means calendar month;
- (ooo) "municipal solid waste" means solid waste resulting from or incidental to municipal, community, commercial, institutional and recreation activities, and includes garbage, rubbish, ashes, street cleanings, abandoned automobiles and all other solid wastes except hazardous waste, industrial solid waste, oilfield waste and biomedical wastes;
- (ppp) "NAPS" means the National Air Pollution Surveillance program;
- (qqq) "new landfill cells" means Cell 3D as described in application No. 005-10348, Cell 3E as described in application No. 012-10348, Cell 4 as described in application No. 014-10348, and Cell 5 as described in application No. 015-10348;
- (rrr) "new surface water detention pond" means the surface water detention pond(s) as described in application No. 012-10348 or No. 015-10348;
- (sss) "NORM" means Naturally Occurring Radioactive Materials;
- (ttt) "NORM waste" means any waste material with concentrations of NORM above the limits specified in Tables 5.1, 5.2, or 5.3 of the *Canadian Guidelines for the Management of Naturally Occurring Radioactive Materials (NORM)*, Health Canada, 2011, as amended;
- (uuu) "nutrients" means the following:

Ammonia nitrogen	Nitrite nitrogen
Total Kjeldahl nitrogen	Total phosphorus
Nitrate nitrogen	Dissolved phosphorus

- (vvv) "old surface water detention pond" means the surface water detention pond as described in application No. 005-10348;
- (www) "Petroleum Hydrocarbons Fractions F1 and F2" means the specific hydrocarbon fraction measured by the analytical methods described in the *Reference Method for the Canada-Wide Standard for Petroleum Hydrocarbons in Soil - Tier 1 Method*, published by the Canadian Council of Ministers of the Environment, 2001, as amended;
- (xxx) "PM" means particulate matter;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (yyy) "PM<sub>10</sub>" means particulate matter less than 10 microns in diameter;
- (zzz) "points of compliance" means the location or locations of the groundwater monitoring wells where measurements of groundwater quality are taken to assess landfill and waste treatment performance;
- (aaaa) "post-closure" means the period of time after completion of the final landfill closure;
- (bbbb) "ppm" means concentration in parts per million;
- (cccc) "primary liner" means the uppermost geomembrane liner;
- (dddd) "QA/QC" means quality assurance and quality control;
- (eeee) "quarter year" means a time period of three consecutive months designated as January, February and March; or April, May and June; or July, August and September; or October, November and December;
- (ffff) "regulations" means the regulations enacted pursuant to the Act, as amended;
- (gggg) "representative grab" means a sample consisting of equal volume portions of water collected from at least four sites between 0.20 to 0.30 metres below the water surface within a pond;
- (hhhh) "runoff" means any rainwater or melt water that drains as surface flow from the facility developed areas, excluding leachate;
- (iiii) "runoff control system" means the parts of the facility that collect, store or treat runoff from the facility, and includes but is not limited to runoff collection ditches, surface water detention ponds and tank farm bermed area;
- (jjjj) "run-on" means any rainwater or melt water that drains as surface flow toward the active landfill area;
- (kkkk) "run-on control system" means the parts of the facility that divert run-on away from the active landfill area;
- (llll) "scrubber exhaust stack" means the exhaust stack through which the air effluent streams that are:
- (i) collected from the exhaust vents of the Drum Processing Building or Staging Building or both, and
  - (ii) treated with the caustic scrubber and activated carbon filter

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

are released to the atmosphere as described in the application;

(mmmm) "secondary liner" means the lowermost geomembrane liner;

(nnnn) "soil" means mineral or organic earthen materials that can, have, or are being altered by weathering, biological processes, or human activity;

(oooo) "SOP" means Standard Operating Procedures;

(pppp) "storm event" means a 1 in 25 year, 24 hour duration rainfall event at Ryley, Alberta;

(qqqq) "tank" means a stationary device, designed to contain an accumulation of a substance, which is constructed primarily of non-earthen materials that provide structural support including wood, concrete, steel, and plastic;

(rrrr) "TDGR" means the *Transportation of Dangerous Goods Regulations* (SOR/2001-286) made under the *Transportation of Dangerous Goods Act, 1992* (Canada), as amended;

(ssss) "TDS" means Total Dissolved Solids;

(tttt) "TNMOCs" means total non-methane organic compounds;

(uuuu) "topsoil" means the uppermost layer of soil and consists of:

(i) the A-horizons and all organic horizons as defined in *The Canadian System of Soil Classification* (Third Edition), Agriculture and Agri-Food Canada, Publication 1646, 1998, as amended, and

(ii) the soil ordinarily moved during tillage;

(vvvv) "total metals" means the following:

Antimony	Cobalt	Selenium
Arsenic	Copper	Silver
Barium	Iron	Thallium
Beryllium	Lead	Tin
Boron	Manganese	Uranium
Cadmium	Mercury	Vanadium
Chromium	Nickel	Zinc

(wwww) "TSP" means total suspended particulate matter;

(xxxx) "TSS" means Total Suspended Solids;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (yyyy) "upper subsoil" means the layer of soil directly below the topsoil layer that consists of the B-horizons as defined in *The Canadian System of Soil Classification*, (Third Edition), Agriculture and Agri-Food Canada, Publication 1646, 1998, as amended;
- (zzzz) "VOCs" means volatile organic compounds;
- (aaaaa) "volume estimate" means a technical evaluation based on the sources contributing to the release including but not limited to pump capabilities, water meters, and batch release volumes;
- (bbbbb) "waste stabilization area" means the portion of the landfill that is used for waste stabilization or solidification or both, as described in application No. 008-10348 or No. 015-10348;
- (ccccc) "waste storage area" means the areas designated for storage of containers for waste or hazardous recyclable or both, or for storage of tanks for waste or hazardous recyclable or both, or for storage of both, as described in application No. 005-10348;
- (dddd) "week" means any consecutive 7-day period;
- (eeee) "working face" means that portion of the active landfill area where waste is currently being deposited, spread and compacted; and
- (ffff) "year" means calendar year.

**PART 2: GENERAL**

**SECTION 2.1: REPORTING**

- 2.1.1 The approval holder shall immediately report to the Director by telephone any contravention of the terms and conditions of this approval at 1-780-422-4505.
- 2.1.2 The approval holder shall submit a written report to the Director within 7 days of the reporting pursuant to 2.1.1.
- 2.1.3 The approval holder shall immediately notify the Director in writing if any of the following events occurs:
  - (a) the approval holder is served with a petition into bankruptcy;
  - (b) the approval holder files an assignment in bankruptcy or Notice of Intent to make a proposal;
  - (c) a receiver or receiver-manager is appointed;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (d) an application for protection from creditors is filed for the benefit of the approval holder under any creditor protection legislation; or
- (e) any of the assets which are the subject matter of this approval are seized for any reason.

2.1.4 If the approval holder monitors for any substances or parameters which are the subject of operational limits as set out in this approval more frequently than is required and uses procedures authorized in this approval, then the approval holder shall provide the results of such monitoring as an addendum to the reports required by this approval.

2.1.5 The approval holder shall submit all monthly reports required by this approval to be compiled or submitted to the Director on or before the end of the month following the month in which the information was collected, unless otherwise specified in this approval.

2.1.6 The approval holder shall submit all annual reports required by this approval to be compiled or submitted to the Director on or before March 31 of the year following the year in which the information was collected, unless otherwise specified in this approval.

**SECTION 2.2: RECORD KEEPING**

2.2.1 The approval holder shall:

- (a) record; and
- (b) retain

all the following information in respect of any sampling conducted or analyses performed in accordance with this approval for a minimum of ten years, unless otherwise authorized in writing by the Director:

- (i) the place, date and time of sampling,
- (ii) sample type,
- (iii) the dates the analyses were performed,
- (iv) the analytical techniques, methods or procedures used in the analyses,
- (v) the names of the persons who collected and analysed each sample, and
- (vi) the results of the analyses.

.....  
**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 2.2.2 The approval holder shall keep and maintain an Operating Record of the landfill as per 4.6.34(a) until the end of the landfill post-closure.
- 2.2.3 The Operating Record referred to in 2.2.2 shall include, at a minimum, all of the following information:
- (a) the information required in section 7.3(c) of the *Standards for Landfills in Alberta*, as amended;
  - (b) the name and contact information of all persons who discover any contravention;
  - (c) the names and contact information of all persons who take any remedial actions arising from the contravention of the Act, the regulations, or this approval; and
  - (d) a description of the remedial measures taken in respect of a contravention of the Act, the regulations, or this approval.
- 2.2.4 The approval holder shall submit a copy of the most recent Operating Record to the Director upon written request from the Director within the timeline specified in writing by the Director.

**SECTION 2.3: ANALYTICAL REQUIREMENTS**

2.3.1 With respect to any sample required to be taken pursuant to this approval, the approval holder shall ensure that:

- (a) collection;
- (b) preservation;
- (c) storage;
- (d) handling; and
- (e) analysis

shall be conducted in accordance with the following unless otherwise authorized in writing by the Director:

- (i) for air:
  - (A) the *Alberta Stack Sampling Code*, Alberta Environment, 1995, as amended,



**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (B) the *Methods Manual for Chemical Analysis of Atmospheric Pollutants*, Alberta Environment, 1993, as amended, and
  - (C) the *Air Monitoring Directive*, Alberta Environment, 1989, as amended;
- (ii) for industrial wastewater, industrial runoff, groundwater and domestic wastewater:
- (A) the *Standard Methods for the Examination of Water and Wastewater*, published jointly by the American Public Health Association, American Water Works Association, and the Water Environment Federation, 1998, as amended;
- (iii) for whole effluent toxicity tests:
- (A) the *Biological Test Method: Reference Method for Determining Acute Lethality of Effluents to Rainbow Trout*, Environment Canada, Environmental Protection Series 1/RM/13, December 2000, as amended,
  - (B) the *Biological Test Method: Reference Method for Determining Acute Lethality of Effluents to Daphnia Magna*, Environment Canada, Environmental Protection Series 1/RM/14, December 2000, as amended,
  - (C) the *Biological Test Method: Growth Inhibition Test Using the Freshwater Alga *Selenastrum capricornutum**, Environment Canada, Environmental Protection Series, November 1992, as amended,
  - (D) the *Biological Test Method: Test of Reproduction and Survival Using the Cladoceran *Ceriodaphnia dubia**, Environment Canada, Environmental Protection Series 1/RM/21, February 1992, as amended,
  - (E) the *Biological Test Method: Test of Larval Growth and Survival Using Fathead Minnows*, Environment Canada, Environmental Protection Series 1/RM/22, February 1992, as amended, and
  - (F) the *Biological Test Method: Toxicity Test Using Luminescent Bacteria (*Photobacterium phosphoreum*)*, Environment Canada, Environmental Protection Series, 1/RM/24, November 1992, as amended;
- (iv) for soil:

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (A) the *Soil Monitoring Directive*, Alberta Environment, May 2009, as amended, and
  - (B) the *Soil Quality Criteria Relative to Disturbance and Reclamation*, Alberta Agriculture, March 1987, as amended; and
  - (v) for waste:
    - (A) the *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods*, USEPA, SW-846, September 1986, as amended,
    - (B) the *Methods Manual for Chemical Analysis of Water and Wastes*, Alberta Environmental Centre, Vegreville, Alberta, 1996, AECV96-M1, as amended,
    - (C) the *Toxicity Characteristic Leaching Procedure (TCLP)* USEPA Regulation 40 CFR261, Appendix II, Method No. 1311, as amended, or
    - (D) the *Standard Methods for the Examination of Water and Wastewater*, American Public Health Association, American Water Works Association, and the Water Environment Federation, 2010, as amended.
- 2.3.2 The approval holder shall analyse all samples that are required to be obtained by this approval in a laboratory accredited pursuant to ISO/IEC 17025, as amended, for the specific parameter(s) to be analysed, unless otherwise authorized in writing by the Director.
- 2.3.3 The term sample used in 2.3.2 does not include samples directed to continuous monitoring equipment, unless specifically required in writing by the Director.
- 2.3.4 The approval holder shall comply with the terms and conditions of any written authorization issued by the Director under 2.3.2.

**SECTION 2.4: OTHER**

- 2.4.1 The terms and conditions of this approval are severable. If any term or condition of this approval or the application of any term or condition is held invalid, the application of such term or condition to other circumstances and the remainder of this approval shall not be affected thereby.
- 2.4.2 Any conflict between the *Standards for Landfills in Alberta*, as amended, and the terms and conditions of this approval shall be resolved in favour of this approval.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 2.4.3 *Environmental Protection and Enhancement Act* Approval No. 10348-02-00, as amended, is cancelled.
- 2.4.4 All tanks shall conform to the *Guidelines for Secondary Containment for Above Ground Storage Tanks*, Alberta Environmental Protection, 1997, as amended, unless otherwise authorized in writing by the Director.
- 2.4.5 All above ground storage tanks containing liquid hydrocarbons or organic compounds shall conform to the *Environmental Guidelines for Controlling Emissions of Volatile Organic Compounds from Aboveground Storage Tanks*, Canadian Council of Ministers of the Environment, PN 1180, 1995, as amended.

**PART 3: CONSTRUCTION****SECTION 3.1: LANDFILL**

- 3.1.1 The approval holder shall not commence construction of:
- (a) Cell 4, unless and until updated financial security of the facility has been provided to the Director to include Cell 4; and
  - (b) Cell 5, unless and until updated financial security of the facility has been provided to the Director to include Cell 5.
- 3.1.2 The approval holder shall construct each new Class I industrial landfill cell in such a way that each new Class I landfill cell shall consist of the following components, at a minimum, unless otherwise authorized in writing by the Director:
- (a) a minimum of 0.45 metre thick cover of clean sand or soil placed over top of the uppermost drainage layer;
  - (b) a composite liner that consists of, at a minimum:
    - (i) a geo-composite drainage layer placed in direct contact with an underlying 80 mil HDPE geomembrane liner as a primary liner;
    - (ii) a geo-composite drainage layer placed in direct contact with an underlying 80 mil HDPE geomembrane liner as a secondary liner; and
    - (iii) a GCL liner placed in direct contact with an underlying clay liner that has:
      - (A) a minimum thickness of 1.0 metre at all points, measured perpendicular to the slope, and
      - (B) been compacted to achieve an in-place hydraulic conductivity of  $1 \times 10^{-9}$  m/s or less;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (c) a leachate collection system that:
  - (i) is placed over the primary liner;
  - (ii) is capable of maintaining the maximum acceptable leachate head; and
  - (iii) consists of:
    - (A) a geo-composite drainage layer with a transmissivity of at least  $1 \times 10^{-4} \text{ m}^2/\text{s}$  placed over top of the primary liner,
    - (B) a network of perforated leachate collection pipes, and
    - (C) a leachate collection sump placed over the primary liner;
- (d) a leak detection system that:
  - (i) is installed over the secondary liner;
  - (ii) is capable of detecting the leakage through the primary liner; and
  - (iii) consists of:
    - (A) a geo-composite drainage layer with a transmissivity of at least  $1 \times 10^{-4} \text{ m}^2/\text{s}$  placed over top of the secondary liner,
    - (B) a network of perforated leak detection liquid collection pipes, and
    - (C) a leak detection liquid collection sump placed over the secondary liner;
- (e) a final cover:
  - (i) that meets the requirements in section 6.1(c) of the *Standards for Landfills in Alberta*, as amended; or
  - (ii) as specified in the Landfill Cell Closure Plan submitted by the approval holder and authorized in writing by the Director pursuant to 7.1.1 and 7.1.4;
- (f) a run-on control system capable of preventing flow onto the active landfill area from at least the peak discharge from a 1 in 25 year, 24 hour duration storm event at the facility; and

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (g) a runoff control system capable of collecting and controlling at least the runoff volume resulting from a 1 in 25 year, 24 hour duration storm event at the facility.

3.1.3 For any new landfill cell(s) to be constructed below the native ground surface in the NE 09-050-17-W4M area of the facility, the approval holder shall construct the cell(s) in the following manner:

- (a) shallow groundwater shall be dewatered and managed to ensure that construction specifications for the composite liner system referred to in 3.1.2 shall not be compromised;
- (b) measures of groundwater dewatering and management during construction shall be documented, and the document shall be maintained as part of the documentation for construction of the composite liner system;
- (c) the integrity of the composite liner system shall be verified and maintained to function as designed, and the verification shall be documented; and
- (d) the documentation referred to in (b) and (c) above shall be submitted as part of the summary report required in 3.1.9.

3.1.4 The composite liner for the landfill shall be constructed on a foundation or base such that there shall be no failure of the liners due to settlement, compression, or uplift.

3.1.5 The approval holder shall submit to the Director the following plans and specifications for the proposed construction of each of the items listed in 3.1.2, signed and stamped by a professional registered with APEGA at least three (3) months prior to construction:

- (a) a Detailed Construction Plan and Specifications prepared as per 3.1.2;
- (b) a Construction Quality Assurance Plan; and
- (c) a Construction Quality Control Plan.

3.1.6 If the Detailed Construction Plan and Specifications in 3.1.5 is found deficient by the Director, the approval holder shall correct all deficiencies as outlined in writing by the Director within the timeline specified in writing by the Director.

3.1.7 The approval holder shall implement the Detailed Construction Plan and Specifications in 3.1.5 as authorized in writing by the Director.

3.1.8 During construction of any of the items listed in 3.1.2, the approval holder shall not deviate from the Detailed Construction Plan and Specifications as authorized in writing by the Director in 3.1.7, unless the following conditions are met:

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (a) the deviation results in a minor adjustment to the Detailed Construction Plan and Specifications in order to suit field conditions encountered; and
  - (b) the deviation will result in an equivalent or better design performance of the landfill.
- 3.1.9 The approval holder shall submit to the Director a summary report of the Construction Quality Assurance and Construction Quality Control results signed and stamped by a professional registered with APEGA.
- 3.1.10 The summary report in 3.1.9 shall contain the following information, at a minimum:
- (a) confirmation that the landfill has been constructed according to:
    - (i) the Construction Quality Assurance Plan,
    - (ii) the Construction Quality Control Plan, and
    - (iii) the Detailed Construction Plan and Specifications as authorized in writing by the Director in 3.1.7, subject to the deviations as per 3.1.8;
  - (b) description of any minor deviations as per 3.1.8;
  - (c) confirmation by the professional registered with APEGA, that deviations as per 3.1.8 will result in an equivalent or better design performance of the landfill;
  - (d) “as-built” plans;
  - (e) photo-documentation of important stages of construction including any repair work or remediation activities to establish or maintain liner integrity;
  - (f) documentation required in 3.1.3; and
  - (g) any other information as required in writing by the Director.
- 3.1.11 The approval holder shall notify the Director in writing at least fourteen (14) days prior to commencing operations of any new landfill cell.
- 3.1.12 The approval holder shall construct the new surface water detention pond(s) in the:
- (a) SE 09-050-17-W4M area of the facility as described in application No. 012-10348; and
  - (b) NE 09-050-17-W4M area of the facility as described in application No. 015-10348 with a clay liner that has:

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (i) a minimum thickness of 1.0 metre at all points, measured perpendicular to the slope, and
- (ii) been compacted to achieve an in-place hydraulic conductivity of  $1 \times 10^{-9}$  m/s or less;

unless otherwise authorized in writing by the Director.

- 3.1.13 The approval holder shall construct the laydown area in the NE 09-050-17-W4M area of the facility as described in application No. 015-10348, unless otherwise authorized in writing by the Director.
- 3.1.14 The approval holder shall manage landfill progression in such a manner as to minimize off-site visual impacts of the landfill, as described in the Landfill Cell Closure Plan submitted by the approval holder and authorized in writing by the Director pursuant to 7.1.1 and 7.1.4.

**SECTION 3.2: WASTE RECEIVING AND STABILIZATION AREAS**

- 3.2.1 The approval holder shall construct the waste receiving area(s) in the SE 09-050-17-W4M area of the facility as described in the application, unless otherwise authorized in writing by the Director.
- 3.2.2 The approval holder shall construct the waste stabilization area(s) in the SE 09-050-17-W4M area of the facility in accordance with the following:
  - (a) application No. 008-10348; and
  - (b) within a Class I landfill cell;unless otherwise authorized in writing by the Director.
- 3.2.3 The approval holder shall construct the central waste receiving and stabilization area in the NE 09-050-17-W4M area of the facility as described in application No. 015-10348, unless otherwise authorized in writing by the Director.
- 3.2.4 The approval holder shall decommission and reclaim the waste receiving and stabilization area(s) in the SE 09-050-17-W4M area of the facility upon completing:
  - (a) construction; and
  - (b) commissioning

of the central waste receiving and stabilization area in the NE 09-050-17-W4M area of the facility, unless otherwise authorized in writing by the Director.

TERMS AND CONDITIONS ATTACHED TO APPROVAL

**SECTION 3.3: SOIL CONSERVATION**

3.3.1 The approval holder shall:

- (a) salvage; and
- (b) conserve

all topsoil for land reclamation of the landfill.

3.3.2 The approval holder shall:

- (a) salvage; and
- (b) conserve

all upper subsoil for land reclamation of the landfill.

3.3.3 The approval holder shall:

- (a) conserve; and
- (b) stockpile

all topsoil separately from the upper subsoil.

3.3.4 The approval holder shall place all:

- (a) topsoil stockpiles; and
- (b) upper subsoil stockpiles

at the landfill.

3.3.5 The approval holder shall stockpile all topsoil as follows:

- (a) on stable foundations; and
- (b) on undisturbed topsoil.

3.3.6 The approval holder shall stockpile all upper subsoil as follows:

- (a) on stable foundations; and
- (b) on areas where the topsoil has been removed.

3.3.7 The approval holder shall take all steps necessary to prevent any erosion (e.g., wind or water), including but not limited to, all of the following:



.....  
**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (a) revegetating the stockpiles; and
- (b) any other steps authorized in writing by the Director.

3.3.8 The approval holder shall immediately suspend conservation of:

- (a) topsoil; and
- (b) upper subsoil

when:

- (i) wet or frozen conditions will result in mixing, loss, degradation or compaction of topsoil or upper subsoil, or
- (ii) high wind velocities, any other field conditions or facility operations will result in mixing, loss, or degradation of topsoil or upper subsoil.

3.3.9 The approval holder shall recommence conservation of:

- (a) topsoil; and
- (b) upper subsoil

only when conditions in 3.3.8 no longer exist.

**PART 4: OPERATIONS, LIMITS, MONITORING AND REPORTING**

**SECTION 4.1: GENERAL**

4.1.1 The approval holder shall maintain the geographical boundaries of the facility to that located within SE ¼ and NE ¼ of Section 09, Township 050, Range 17, West of the 4<sup>th</sup> Meridian, as described in the application.

4.1.2 The approval holder shall limit the waste elevation of the landfill to no more than the maximum designated waste elevation.

4.1.3 The approval holder shall restrict access to the facility to only personnel authorized by the approval holder.

4.1.4 The approval holder shall maintain a publicly available 24 hour "HOTLINE" number for a prompt response during an emergency.

4.1.5 The approval holder shall:

- (a) operate; and

## **TERMS AND CONDITIONS ATTACHED TO APPROVAL**

(b) maintain the integrity of

the following waste management facilities at the facility:

- (i) the HWRSP Facility;
  - (ii) the Class I and Class II industrial landfill, including:
    - (A) Class I landfill cells,
    - (B) Class II landfill cell(s),
    - (C) waste receiving area(s), and
    - (D) waste stabilization area(s); and
  - (iii) waste storage area(s);
- as described in the application.

4.1.6 In addition to 4.1.5, the approval holder shall:

(a) operate; and

(b) maintain the integrity of

the following infrastructure components at the facility:

- (i) the composite liner;
  - (ii) the leachate collection system,
  - (iii) the leak detection system,
  - (iv) the run-on control system,
  - (v) the runoff control system,
  - (vi) the groundwater monitoring wells,
  - (vii) the weigh scale, and
  - (viii) the site access control;
- as described in the application.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

**FACILITY AUDIT**

- 4.1.7 The approval holder shall cause the facility to be audited by an independent third-party environmental consultant or organization to assess compliance with the terms and conditions of this approval:
- (a) at least once every three years; and
  - (b) commencing on or before October 1, 2018 for the first audit.
- 4.1.8 The approval holder shall submit the audit report required in 4.1.7 in the Annual Landfill Operations Report as required in 4.6.60(c).
- 4.1.9 The requirements in 4.1.7 and 4.1.8 shall not relieve the approval holder of any duty under the Act, or its associated regulations, or this approval.

**FACILITY WILDLIFE MANAGEMENT PLAN**

- 4.1.10 The approval holder shall:
- (a) develop; and
  - (b) implement
- a Facility Wildlife Management Plan at the facility to keep wildlife away from exposed waste areas within 120 days of the issuance of this approval, unless otherwise authorized in writing by the Director.
- 4.1.11 The approval holder shall:
- (a) review the Facility Wildlife Management Plan annually; and
  - (b) update the Facility Wildlife Management Plan if any of the following circumstances apply:
    - (i) there are facility expansions or changes in site operations, or
    - (ii) an update is requested in writing by the Director.
- 4.1.12 The approval holder shall retain a copy of the most recent Facility Wildlife Management Plan at the facility.
- 4.1.13 The approval holder shall submit a copy of the most recent Facility Wildlife Management Plan to the Director upon written request from the Director within the timeline specified in writing by the Director.

.....

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.1.14 If the Facility Wildlife Management Plan submitted pursuant to 4.1.13 is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.
- 4.1.15 The approval hold shall implement the latest Facility Wildlife Management Plan, unless otherwise authorized in writing by the Director.

**COMMUNITY COMPLAINT RESPONSE PLAN**

- 4.1.16 The approval holder shall:
  - (a) develop; and
  - (b) implementa Community Complaint Response Plan at the facility within 90 days of the issuance of this approval, unless otherwise authorized in writing by the Director.
- 4.1.17 The approval holder shall include, at a minimum, all of the following in the Community Complaint Response Plan referred to in 4.1.16:
  - (a) procedures and methods to be taken to respond to the complaint, which shall include but not limited to the following:
    - (i) recording of the complaint,
    - (ii) reviewing of the complaint records and other relevant information,
    - (iii) investigation of the complaint, and
    - (iv) timeline and follow-up actions for responding to the complaint based on the findings of the complaint review and investigation;
  - (b) the recording of the complaint referred to in (a)(i) above shall include but not limited to the following:
    - (i) contact information of the complainant(s) (names, phone numbers, e-mails and addresses),
    - (ii) detailed description of the event for which the complaint is filed,
    - (iii) date and time of the event occurring,
    - (iv) location where the event is noticed, and direction and distance of the event location relative to the facility,
    - (v) wind direction and speed at the facility, and

.....

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (vi) other local meteorological information at the time of the event occurring;
- (c) the reviewing of the complaint referred to in (a)(ii) above shall include but not limited to the following:
  - (i) reviewing complaint records,
  - (ii) reviewing the facility operating records,
  - (iii) reviewing additional local meteorological data, and
  - (iv) timeline for reviewing the complaint;
- (d) the investigation of the complaint referred to in (a)(iii) above shall include but not limited to the following:
  - (i) meeting complainant(s) to obtain further information related to the complaint,
  - (ii) visiting other local residents to collect additional information,
  - (iii) assessing other activities in the vicinity of the facility that may have potential for causing the event, and
  - (iv) timeline for the complaint investigation;
- (e) the timeline and follow-up actions referred to in (a)(iv) above shall include but not limited to the following:
  - (i) timeline for responding to the complaint; and
  - (ii) follow-up actions:
    - (A) if the complaint is found to be related to the facility operations, the follow-up actions shall include:
      - (A.1) notifying the complainant(s) of the findings of the complaint review and investigation within the timeline specified in (i) above,
      - (A.2) taking immediate measures to correct the source(s) of the complaint,
      - (A.3) taking measures to prevent the issue from occurring again in future, and

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (A.4) providing a summary of the complaint review and investigation in the Annual Landfill Operations Report pursuant to 4.6.60(n); or
  - (B) if the complaint is found not to be related to the facility operations, the follow-up actions shall include:
    - (B.1) notifying the complainant(s) of the findings of the complaint review and investigation within the timeline specified in (i) above, and
    - (B.2) providing a summary of the complaint review and investigation in the Annual Landfill Operations Report pursuant to 4.6.60(n).
- 4.1.18 The approval holder shall:
- (a) review the Community Complaint Response Plan annually; and
  - (b) update the Community Complaint Response Plan if any of the following circumstances apply:
    - (i) there are facility expansions or changes in site operations, or
    - (ii) an update is requested in writing by the Director.
- 4.1.19 The approval holder shall retain a copy of the most recent Community Complaint Response Plan at the facility.
- 4.1.20 The approval holder shall submit a copy of the most recent Community Complaint Response Plan to the Director upon written request from the Director within the timeline specified in writing by the Director.
- 4.1.21 If the Community Complaint Response Plan submitted pursuant to 4.1.20 is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.
- 4.1.22 The approval hold shall implement the latest Community Complaint Response Plan, unless otherwise authorized in writing by the Director.

**PARTICIPATION IN DEVELOPMENT OF LOCAL EMERGENCY MANAGEMENT PLANS**

- 4.1.23 The approval holder shall support the Village of Ryley and Beaver County in the development of Local Emergency Management Plans by providing assistance to the Village and County in, at a minimum, all of the following:
- (a) identifying hazards at the facility;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (b) assessing degree of risk of the hazards at the facility;
- (c) suggesting risk mitigation measures;
- (d) offering input to development of emergency notification and emergency evacuation procedures for local residents;
- (e) keeping the Village and County updated for any major new development at the facility; and
- (f) advising the Village and County of the need for updating the Local Emergency Management Plans following any major new development at the facility.

**FACILITY EMERGENCY MANAGEMENT PLAN**

4.1.24 The approval holder shall:

- (a) develop; and
- (b) implement

a Facility Emergency Management Plan at the facility within 90 days of the issuance of this approval, unless otherwise authorized in writing by the Director.

4.1.25 The Facility Emergency Management Plan referred to in 4.1.24 shall include, at a minimum, all of the following:

- (a) identification of hazards at the facility;
- (b) assessment of degree of risk and impact of hazards at the facility;
- (c) preventative measures for hazards at the facility;
- (d) mitigation measures for hazards at the facility;
- (e) emergency preparedness at the facility;
- (f) procedures for emergency management at the facility; and
- (g) emergency notification and emergency evacuation procedures for local residents.

4.1.26 The approval holder shall:

- (a) review the Facility Emergency Management Plan annually; and

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (b) update the Facility Emergency Management Plan if any of the following circumstances apply:
  - (i) there are facility expansions or changes in site operations, or
  - (ii) an update is requested in writing by the Director.
- 4.1.27 The approval holder shall retain a copy of the most recent Facility Emergency Management Plan at the facility.
- 4.1.28 The approval holder shall submit a copy of the most recent Facility Emergency Management Plan to the Director upon written request from the Director within the timeline specified in writing by the Director.
- 4.1.29 If the Facility Emergency Management Plan submitted pursuant to 4.1.28 is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.
- 4.1.30 The approval hold shall implement the latest Facility Emergency Management Plan, unless otherwise authorized in writing by the Director.

**COMMUNITY ACESIBLE WEBSITE**

- 4.1.31 The approval shall:
  - (a) develop; and
  - (b) maintain

a community accessible website available to all local residents within 120 days of the issuance of this approval, unless otherwise authorized in writing by the Director.
- 4.1.32 The community accessible website referred to in 4.1.31 shall include, at a minimum, all of the following information:
  - (a) Annual Landfill Operations Reports (including the three-year compliance audit report, Annual Dugout and Water Well Sampling Program Report, and Annual Landfill Cell Closure Report, etc.);
  - (b) Monthly Waste Management Report, and Annual Waste Management Summary Report;
  - (c) Monthly Ambient Air Monitoring Report, and Annual Ambient Air Monitoring Report;
  - (d) Monthly Runoff and Industrial Wastewater Report, and Annual Runoff and Industrial Wastewater Report;



**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (e) Annual Groundwater Monitoring Program Report;
- (f) Soil Monitoring Program Report, and Soil Management Program Report;
- (g) Facility Wildlife Management Plan;
- (h) Community Complaint Response Plan;
- (i) regulatory correspondences for incidents and complaints;
- (j) correspondences made to Alberta Environment and Parks and copied CAOs at the Village of Ryley and Beaver County;
- (k) Facility Emergency Management Plan, including emergency notification and emergency evacuation procedures;
- (l) Village of Ryley Emergency Management Plan, including emergency notification and emergency evacuation procedures;
- (m) Beaver County Emergency Management Plan, including emergency notification and emergency evacuation procedures; and
- (n) any other information as requested in writing by the Director.

4.1.33 The approval holder shall:

- (a) review the community accessible website annually; and
- (b) update the website if any of the following circumstances apply:
  - (i) there are facility expansions or changes in site operations, or
  - (ii) an update is requested in writing by the Director.

**SECTION 4.2: AIR**

**OPERATIONS**

4.2.1 The approval holder shall not release any air effluent streams to the atmosphere except as authorized by this approval.

4.2.2 The approval holder shall only release air effluent streams to the atmosphere from the following sources:

- (a) the scrubber exhaust stack;

.....

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (b) the Drum Processing Building natural gas fired air make up unit exhaust vent;
- (c) the Staging Building natural gas fired air make up unit exhaust vent;
- (d) the Administration Building natural gas fired furnaces exhaust vents;
- (e) the Laboratory fume hood and natural gas fired air make up unit exhaust vents;
- (f) the Maintenance Shop equipment and natural gas fired Radiant Heater exhaust vents;
- (g) the Leachate Collection Tanks natural gas fired heaters exhaust vents;
- (h) the leachate transfer lines passive gas vents; and
- (i) any other source authorized in writing by the Director.

4.2.3 The approval holder shall not operate any process equipment unless and until the pollution abatement equipment associated with the corresponding process equipment is:

- (a) operational; and
- (b) operating.

4.2.4 The approval holder shall treat all air effluent streams from the exhaust vents of the Drum Processing or Staging or both Buildings with a caustic scrubber and an activated carbon filter before directing the air effluent streams to the scrubber exhaust stack for release to the atmosphere while:

- (a) hazardous waste or hazardous recyclables or both are being processed;
- (b) hazardous waste or hazardous recyclables or both are being transferred; or
- (c) containers of hazardous waste or hazardous recyclables or both are open

in the Drum Processing or Staging or both Buildings.

4.2.5 The approval holder shall control fugitive emissions and any source not specified in 4.2.2 in accordance with 4.2.6 of this approval unless otherwise authorized in writing by the Director.

4.2.6 With respect to fugitive emissions and any source not specified in 4.2.2, the approval holder shall not release a substance or cause to be released a substance that causes or may cause any of the following:

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (a) impairment, degradation or alteration of the quality of natural resources;
- (b) material discomfort, harm or adverse effect to the well being or health of a person; or
- (c) harm to property or to vegetative or animal life.

4.2.7 The approval holder shall not burn any debris by means of an open fire unless authorized in writing by the Director.

4.2.8 If the approval holder receives complaints of offensive odours, or fugitive dust, or both, beyond the facility boundaries, the approval holder shall:

- (a) conduct the following to reduce the release of those odours, or fugitive dust, or both by:
  - (i) placing restrictions on types, or volumes, or both, of the wastes being handled or processed or deposited that are causing those odours, or fugitive dust, or both,
  - (ii) increasing the frequency of cover placement, or modifying waste handling activities, or performing both, at the landfill,
  - (iii) modifying waste handling activities at the HWRSP Facility, or
  - (iv) performing any combination of the above; and
- (b) activate the Odour and Fugitive Dust Response Program as specified in the Landfill Operations Plan in 4.6.34(I).

**LIMITS**

4.2.9 The approval holder shall maintain the pH of the scrubbing liquid of the caustic scrubber referred to in 4.2.4 at 8.0 or higher.

4.2.10 The approval holder shall replace activated carbon in the activated carbon filter referred to in 4.2.4 immediately when the concentration of total petroleum hydrocarbons in the air effluent streams released from the scrubber exhaust stack to the atmosphere exceeds 25 ppm.

**SOURCE MONITORING AND REPORTING**

4.2.11 The approval holder shall monitor, daily at a minimum, the pH of the scrubbing liquid of the caustic scrubber referred to in 4.2.4.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.2.12 The approval holder shall monitor, weekly at a minimum, the air effluent streams released from the scrubber exhaust stack, using a portable total petroleum hydrocarbon analyzer while:
- (a) hazardous waste or hazardous recyclables or both are being processed;
  - (b) hazardous waste or hazardous recyclables or both are being transferred; or
  - (c) containers of hazardous waste or hazardous recyclables or both are open in the Drum Processing or Staging or both Buildings.
- 4.2.13 The portable total petroleum hydrocarbon analyzer referred to in 4.2.12 shall:
- (a) have a detection limit of 1 ppm or lower for total petroleum hydrocarbons;
  - (b) be located in a straight section of the scrubber exhaust stack, a minimum of one (1) metre downstream from the last flow disturbance; and
  - (c) be calibrated regularly in accordance with the analyzer manufacturer's specifications.

**AMBIENT AIR MONITORING AND REPORTING**

- 4.2.14 The approval holder shall continue to implement the Ambient Air Monitoring Program as authorized in writing by the Director on June 24, 2009, unless and until otherwise authorized in writing by the Director pursuant to 4.2.21.
- 4.2.15 The approval holder shall submit to the Director the results of the Ambient Air Monitoring Program in 4.2.14 with the following reports:
- (a) a Monthly Ambient Air Monitoring Report; and
  - (b) an Annual Ambient Air Monitoring Report
- in accordance with the written authorization by the Director on June 24, 2009, unless and until otherwise authorized in writing by the Director pursuant to 4.2.21.
- 4.2.16 The approval holder shall submit:
- (a) a revised Ambient Air Monitoring Program;
  - (b) revised reporting requirements, or
  - (c) both of the above

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

to the Director upon written request from the Director within the timeline specified in writing by the Director.

- 4.2.17 The approval holder shall submit an enhanced Ambient Air Quality Monitoring Program to the Director within 90 days of the issuance of this approval, unless otherwise authorized in writing by the Director.
- 4.2.18 The approval holder shall include, at a minimum, all of the following in the enhanced Ambient Air Quality Monitoring Program referred to in 4.2.17:
- (a) three (3) intermittent ambient air quality monitoring stations:
    - (i) the existing Highway 854 station,
    - (ii) the existing Ryley School station, and
    - (iii) the existing Facility Site station, to be relocated as authorized in writing by the Director;
  - (b) the following monitoring parameters for the existing Highway 854 station:
    - (i) TSP,
    - (ii) PM<sub>10</sub> (for 2 year transition from PM<sub>10</sub> to TSP, starting from authorization of the enhanced Ambient Air Quality Monitoring Program by the Director),
    - (iii) total metals in:
      - (A) TSP, and
      - (B) PM<sub>10</sub> (for 2 year transition from PM<sub>10</sub> to TSP, starting from authorization of the enhanced Ambient Air Quality Monitoring Program by the Director),if concentration of TSP or PM<sub>10</sub> exceeds 50 µg/m<sup>3</sup>,
    - (iv) VOCs, and
    - (v) TNMOCs;
  - (c) the following monitoring parameters for the Ryley School and Facility Site stations:
    - (i) TSP, and
    - (ii) total metals in TSP, if concentration of TSP exceeds 50 µg/m<sup>3</sup>; and

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (d) the following monitoring frequencies for the three (3) stations referred to in (a) above:
  - (i) for the Highway 854 station, once every six (6) days in alignment with the NAPS sampling schedule, and
  - (ii) for the Ryley School and Facility Site stations, linking the two (2) stations in such a way that the two (2) stations will collect air samples whenever the wind direction is oriented in a northeast to southwest direction.

4.2.19 The approval holder shall include a minimum of one (1) meteorological station in each of the Ryley School and Facility Site intermittent ambient air quality monitoring stations referred to in 4.2.18(a) that measures and records, at a minimum, all of the following parameters:

- (a) wind speed; and
- (b) wind direction.

4.2.20 If the revised:

- (a) Ambient Air Monitoring Program;
- (b) reporting requirements; or
- (c) both of the above

submitted pursuant to 4.2.16 or 4.2.17 is found deficient by the Director, the approval holder shall correct all deficiencies as outlined in writing by the Director within the timeline specified in writing by the Director.

4.2.21 The approval holder shall implement the revised:

- (a) Ambient Air Monitoring Program;
- (b) reporting requirements; or
- (c) both of the above

submitted pursuant to 4.2.16 or 4.2.17 as authorized in writing by the Director within the timeline specified in writing by the Director.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL****SECTION 4.3: RUNOFF AND INDUSTRIAL WASTEWATER****OPERATIONS**

- 4.3.1 The approval holder shall not release any substances from the facility to the surrounding watershed except as authorized by this approval.
- 4.3.2 The approval holder shall operate and maintain the integrity of:
- (a) the run-on control system to prevent flow onto the active landfill area from at least the peak discharge from a 1 in 25 year, 24 hour duration storm event at the facility; and
  - (b) the runoff control system for the facility to collect and control at least the runoff volume resulting from a 1 in 25 year, 24 hour duration storm event at the facility.
- 4.3.3 All runoff from the facility developed area shall be directed to the runoff control system as described in:
- (a) application No. 012-10348, for the SE 09-050-17-W4M area of the facility, prior to decommissioning and reclamation of the old surface water detention pond;
  - (b) application No. 014-10348, for the SE 09-050-17-W4M area of the facility, after decommissioning and reclamation of the old surface water detention pond; and
  - (c) application No. 015-10348, for the NE 09-050-17-W4M area of the facility;
- unless otherwise authorized in writing by the Director.
- 4.3.4 Prior to decommissioning and reclamation of the old surface water detention pond and subject to 4.3.8, the approval holder shall only make or permit a release from the old surface water detention pond:
- (a) at the release point as designated in application No. 012-10348, which is:
    - (i) located in the south east corner of the old surface water detention pond, and
    - (ii) referred to as sampling location A1 in 4.3.12; and
  - (b) through
    - (i) a pump and a release hose over the south berm into the drainage control ditch, east of the landfill access road, to the new surface water

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

detention pond in the SE 09-050-17-W4M area of the facility, under normal operating conditions; or

- (ii) a pump and a release hose over the south berm directly to the culvert under Highway 854, during periods of high runoff exceeding the holding capacity of the new surface water detention pond in the SE 09-050-17-W4M area of the facility;

unless otherwise authorized in writing by the Director.

4.3.5 Subject to 4.3.8, the approval holder shall only make or permit a release from the new surface water detention pond in the SE 09-050-17-W4M area of the facility:

- (a) at the release point as designated in application No. 012-10348, which is:
  - (i) located in the north east corner of the new surface water detention pond in the SE 09-050-17-W4M area of the facility, and
  - (ii) referred to as sampling location B1 in 4.3.12; and
- (b) through a pump and a release hose over the east berm into the culvert under Highway 854;

unless otherwise authorized in writing by the Director.

4.3.6 Subject to 4.3.8, the approval holder shall only make or permit a release from each of the new surface water detention pond(s) in the NE 09-050-17-W4M area of the facility:

- (a) through a pump and a release hose into the drainage control ditch, east of the landfill access road, to the new surface water detention pond in the SE 09-050-17-W4M area of the facility, under normal operating conditions; or
- (b) through a pump and a release hose directly to the culvert under Highway 854, during periods of high runoff exceeding the holding capacity of the new surface water detention pond in the SE 09-050-17-W4M area of the facility;

unless otherwise authorized in writing by the Director.

4.3.7 The approval holder shall only dispose of industrial wastewaters, or specified runoff in TABLE 4.3-A, or both, by one or more of the following methods:

- (a) to facilities holding a current Act authorization to accept such waste;
- (b) to facilities approved by a local environmental authority outside of Alberta to accept such waste;



**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (c) to a disposal well approved by AER;
- (d) as per 4.6.52; or
- (e) as otherwise authorized in writing by the Director.

**TABLE 4.3-A: SPECIFIED RUNOFF**

SOURCES
Runoff that exceeds any of the limits for the parameters listed in TABLE 4.3-B.
Runoff for which the results of the parameters listed in TABLE 4.3-B are unavailable at the time that the runoff must be disposed of.
Runoff from within the tank farm bermed area.

**LIMITS**

4.3.8 Releases of runoff:

- (a) from the old surface water detention pond to the surrounding watershed;
- (b) from the new surface water detention pond in the SE 09-050-17-W4M area of the facility to the surrounding watershed;
- (c) from each of the new surface water detention pond(s) in the NE 09-050-17-W4M area of the facility to the surrounding watershed, or to the new surface water detention pond in the SE 09-050-17-W4M area of the facility; or
- (d) from any combination of the above

shall comply with the limits specified in TABLE 4.3-B.

**TABLE 4.3-B: RUNOFF LIMITS FOR SURFACE WATER DETENTION PONDS**

PARAMETER	LIMITS (Maximum unless otherwise indicated)
pH	6.0 – 9.5 pH units
COD	50 mg/L
TDS	2500 mg/L
TSS	25 mg/L
Ammonia (expressed as Nitrogen)	5 mg/L
Chloride	250 mg/L
Sodium	200 mg/L
Sulphate	500 mg/L
Oil or other substances	Not present in amounts sufficient to create a visible film or sheen
96-Hour Multiple Concentration Acute Lethality Test Using Rainbow Trout ( <i>Oncorhynchus mykiss</i> )	50% or greater survival

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

4.3.9 Releases of runoff from within the tank farm bermed area to the old or new or both surface water detention ponds shall comply with the limits specified in TABLE 4.3-C.

**TABLE 4.3-C: RUNOFF LIMITS FOR TANK FARM BERMED AREA**

PARAMETER	LIMITS Maximum unless otherwise indicated
pH	6.0 – 9.5 pH units
COD	50 mg/L
TSS	25 mg/L
Ammonia (expressed as Nitrogen)	5 mg/L
Oil or other substances	Not present in amounts sufficient to create a visible film or sheen

**MONITORING AND REPORTING**

- 4.3.10 The approval holder shall monitor the runoff control system as required in TABLE 4.3-D, subject to 4.3.13.
- 4.3.11 The approval holder shall report to the Director the results of the runoff control system monitoring as required in TABLE 4.3-D, subject to 4.3.13.
- 4.3.12 For the purpose of TABLE 4.3-D:
- (a) sampling location A1 is defined as the old surface water detention pond release point;
  - (b) sampling location A2 is defined as the old surface water detention pond;
  - (c) sampling location B1 is defined as the release point of the new surface water detention pond in the SE 09-050-17-W4M area of the facility;
  - (d) sampling location B2 is defined as the new surface water detention pond in the SE 09-050-17-W4M area of the facility;
  - (e) sampling location C1 is defined as the release point of each of the new surface water detention pond(s) in the NE 09-050-17-W4M area of the facility;
  - (f) sampling location C2 is defined as each of the new surface water detention pond(s) in the NE 09-050-17-W4M area of the facility; and
  - (g) sampling location D is defined as the tank farm bermed area.
- 4.3.13 The monitoring and reporting requirements in 4.3.10 and 4.3.11 for the old surface water detention pond (sampling locations A1 and A2) shall not apply after decommissioning and reclamation of the old surface water detention pond.

TERMS AND CONDITIONS ATTACHED TO APPROVAL

TABLE 4.3-D: RUNOFF CONTROL SYSTEM MONITORING AND REPORTING

MONITORING				REPORTING	
Parameter	Frequency	Sample Type	Sampling Location	Monthly	Annually
<b>Surface Water Detention Ponds</b>					
Flow (m <sup>3</sup> /day)	Daily during release	Estimate	A1, B1, C1	Monthly Runoff and Industrial Wastewater Report, for each month when release occurs	Annual Runoff and Industrial Wastewater Report
pH	Once per batch release, prior to release	Representative Grab	A2, B2, C2		
COD					
TDS					
TSS					
Ammonia (expressed as nitrogen)					
Chloride					
Sodium					
Sulphate					
Oil or other substances	Daily during release	Visual			
96-hour multiple concentration acute lethality test using rainbow trout ( <i>oncorhynchus mykiss</i> )	Each month when release occurs, prior to release, for the first batch release of the month	Representative Grab			
48-hour static acute lethality test using <i>daphnia magna</i>					
<b>Tank Farm Bermed Area</b>					
Volume (m <sup>3</sup> )	Total batch volume released	Estimate	D		
pH	Once per batch release, prior to release to the surface water detention pond(s)	Representative Grab			
COD					
TSS					
Ammonia (expressed as nitrogen)					
Oil or other substances				Visual	

4.3.14 The monitoring and reporting required in TABLE 4.3-D for the acute lethality tests shall comply with:

- (a) the *Biological Test Method: Reference Method for Determining Acute Lethality of Effluents to Rainbow Trout*, Environment Canada, Environmental Protection Series 1/RM/13, December 2000, as amended; and
- (b) the *Biological Test Method: Reference Method for Determining Acute Lethality of Effluents to Daphnia Magna*, Environment Canada, Environmental Protection Series 1/RM/14, December 2000, as amended.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.3.15 The approval holder shall:
- (a) treat any acute lethality test that deviates from the corresponding test method referred to in 4.3.14 as invalid; and
  - (b) repeat the test as soon as logistically possible.
- 4.3.16 In the event that less than 50% of the rainbow trout survived in the 100% concentration sample, the approval holder shall:
- (a) implement a program immediately to identify the source of the toxicity; and
  - (b) submit to the Director within 90 days after the test result is available, a proposed program to reduce the toxicity of the runoff.
- 4.3.17 The approval holder shall submit the Monthly Runoff and Industrial Wastewater Report in TABLE 4.3-D to the Director.
- 4.3.18 The Monthly Runoff and Industrial Wastewater Report shall include, at a minimum, all of the following information:
- (a) a monthly assessment of the monitoring results relative to the limits in TABLE 4.3-B;
  - (b) a monthly assessment of the monitoring results relative to the limits in TABLE 4.3-C;
  - (c) a monthly assessment of the performance of the:
    - (i) runoff control system,
    - (ii) pollution abatement equipment, and
    - (iii) monitoring equipment;
  - (d) a monthly summary of management and disposal of the:
    - (i) industrial wastewaters, and
    - (ii) specified runoffas per 4.3.7;
  - (e) a monthly summary of management and disposal of runoff in general;
  - (f) a monthly summary of runoff contraventions reported pursuant to 2.1.1; and

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (g) any other information as required in writing by the Director.
- 4.3.19 The approval holder shall submit the Annual Runoff and Industrial Wastewater Report in TABLE 4.3-D to the Director.
- 4.3.20 The Annual Runoff and Industrial Wastewater Report shall include, at a minimum, all of the following information:
- (a) an annual summary assessment of the monitoring results relative to the limits in TABLE 4.3-B;
  - (b) an annual summary assessment of the monitoring results relative to the limits in TABLE 4.3-C;
  - (c) an annual summary assessment of the performance of the:
    - (i) runoff control system,
    - (ii) pollution abatement equipment, and
    - (iii) monitoring equipment;
  - (d) an annual summary of management and disposal of the:
    - (i) industrial wastewaters, and
    - (ii) specified runoffas per 4.3.7;
  - (e) an annual summary and evaluation of management and disposal of runoff in general;
  - (f) an annual summary of the results pursuant to 4.3.22;
  - (g) an annual summary of runoff contraventions reported pursuant to 2.1.1; and
  - (h) any other information as required in writing by the Director.
- 4.3.21 The approval holder shall:
- (a) collect a representative grab sample from the old surface water detention pond at least once per year, prior to decommissioning and reclamation of the pond;
  - (b) collect a representative grab sample from each of the new surface water detention ponds at least once per year; and

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

(c) analyze the samples for all of the parameters specified in TABLE 4.3-E.

**TABLE 4.3-E: ANNUAL MONITORING OF SURFACE WATER DETENTION POND**

PARAMETERS			
pH	TDS; TSS	Fluoride, dissolved	Phenols
Electrical conductivity	Metals	Cyanide (weak acid dissociable)	Total chlorinated phenols
COD	Major ions	BTEX	Polychlorinated biphenyls, total
DOC	Nutrients	Petroleum Hydrocarbons Fractions F1 and F2	Total organic halogens

4.3.22 The approval holder shall submit the results of the analyses in 4.3.21 to the Director in the Annual Runoff and Industrial Wastewater Report.

**SECTION 4.4: LEACHATE COLLECTION AND LEAK DETECTION**

**OPERATIONS**

4.4.1 The approval holder shall only dispose of leachate removed from the leachate collection system by one or more of the following methods:

- (a) to facilities holding a current Act authorization to accept such waste;
- (b) to facilities approved by a local environmental authority outside of Alberta to accept such waste;
- (c) to a disposal well approved by AER; or
- (d) as per 4.6.52.

4.4.2 The approval holder shall only dispose of liquid removed from the leak detection system by one or more of the following methods:

- (a) to facilities holding a current Act authorization to accept such waste;
- (b) to facilities approved by a local environmental authority outside of Alberta to accept such waste;
- (c) to a disposal well approved by AER; or
- (d) as per 4.6.52.

.....

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

**LIMITS**

- 4.4.3 Subject to 4.4.4, the approval holder shall not exceed the maximum acceptable leachate head in any landfill cell.
- 4.4.4 Subsequent to a storm event, the leachate head in any landfill cell shall not exceed the maximum acceptable leachate head for more than fourteen (14) days, unless otherwise authorized in writing by the Director.
- 4.4.5 The volume of liquid in the leak detection system, as monitored in TABLE 4.6-D, shall not exceed the action leakage rate in any landfill cell.

**MONITORING AND REPORTING**

- 4.4.6 The approval holder shall monitor the leachate collection and leak detection systems as required in TABLE 4.6-D and for all parameters specified in TABLE 4.4-A, subject to 4.4.8 and 4.4.9.
- 4.4.7 The approval holder shall report to the Director the results of the leachate collection and leak detection systems monitoring as required in TABLE 4.6-D, including the results of the analyses for all parameters specified in TABLE 4.4-A, subject to 4.4.8 and 4.4.9.

**TABLE 4.4-A: LEACHATE AND LEAK DETECTION LIQUID MONITORING**

PARAMETERS		
pH (field and laboratory)	TDS	Nutrients
Electrical conductivity (field and laboratory)	TSS	BTEX
COD	Metals	Phenols
DOC	Major Ions	Petroleum Hydrocarbons Fractions F1 and F2

- 4.4.8 The requirements in 4.4.6 and 4.4.7 for monitoring and reporting the parameters in TABLE 4.4-A for leachate shall not apply if insufficient leachate is available for conducting the analyses.
- 4.4.9 The requirements in 4.4.6 and 4.4.7 for monitoring and reporting the parameters in TABLE 4.4-A for leak detection liquid shall not apply if insufficient leak detection liquid is available for conducting the analyses.
- 4.4.10 If the volume of liquid removed from the leak detection system exceeds the action leakage rate, in addition to reporting pursuant to 2.1.1, the approval holder shall submit a Response Action Plan to the Director within 30 days of the exceedance.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

**SECTION 4.5: DUGOUTS AND WATER WELLS IN SURROUNDING AREA**

**MONITORING AND REPORTING**

4.5.1 The approval holder shall:

(a) collect a representative sample from:

(i) each of the dugouts, and

(ii) each of the water wells

within an approximate 1.6 kilometre radius around the facility; and

(b) analyze the sample for the parameters listed in TABLE 4.5-A;

unless the approval holder is not granted access by the landowner.

**TABLE 4.5-A: DUGOUT AND WATER WELL MONITORING**

PARAMETERS		
pH (field and laboratory)	TDS	Nutrients
Electrical conductivity (field and laboratory)	TSS	BTEX
COD	Metals	Phenols
DOC	Major Ions	Petroleum Hydrocarbons Fractions F1 and F2

4.5.2 The monitoring required in 4.5.1 shall be conducted once each year in October unless otherwise authorized in writing by the Director.

4.5.3 The approval holder shall record the analytical results of the sampling information required in 4.5.1 in an Annual Dugout and Water Well Sampling Program Report.

4.5.4 The approval holder shall submit the Annual Dugout and Water Well Sampling Program Report to the Director pursuant to 4.6.60(i).

**SECTION 4.6: HWRSP FACILITY AND LANDFILL**

**GENERAL**

4.6.1 The approval holder shall not:

(a) receive;

(b) process;



**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (c) dispose of; or
- (d) perform any combination of the above for

any of the following wastes, individually or in any combination, at the respective locations specified below:

- (i) explosives (Class 1 TDGR wastes), at the facility;
- (ii) radioactive wastes (Class 7 TDGR wastes), at the facility;
- (iii) radioactive wastes regulated under the *Nuclear Safety and Control Act* (Canada), at the facility;
- (iv) biomedical waste, at the facility;
- (v) waste containing free liquids, at the landfill, excluding the waste stabilization area;
- (vi) material containing ozone depleting substances, at the landfill;
- (vii) municipal solid waste, at the facility;
- (viii) NORM waste, at the facility;
- (ix) waste generating offensive odours, at the facility, unless and until effective control measures are provided to prevent releases of offensive odours to the outside of the facility fenceline.

4.6.2 Incompatible wastes and incompatible hazardous recyclables shall be prevented from mixing.

4.6.3 The approval holder shall dispose of wastes generated at the facility only:

- (a) to facilities holding a current Act authorization;
- (b) to facilities approved by a local environmental authority outside of Alberta; or
- (c) as otherwise authorized in writing by the Director.

**HWRSP FACILITY**

**OPERATIONS PLAN**

4.6.4 The approval holder shall:

- (a) develop;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

(b) keep up-to-date; and

(c) implement

an HWRSP Facility Operations Plan.

4.6.5 The approval holder shall:

(a) review the HWRSP Facility Operations Plan annually, at a minimum; and

(b) update the HWRSP Facility Operations Plan if any of the following circumstances apply:

(i) there are facility expansions or changes in site operations or equipment,

(ii) there is an applicable change to an applicable regulation, or

(iii) an update is required in writing by the Director.

4.6.6 The approval holder shall retain a copy of the most recent HWRSP Facility Operations Plan at the facility.

4.6.7 The approval holder shall submit a copy of the most recent HWRSP Facility Operations Plan to the Director upon written request from the Director within the timeline specified in writing by the Director.

4.6.8 If the HWRSP Facility Operations Plan submitted pursuant to 4.6.7 is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.

4.6.9 The approval hold shall implement the latest HWRSP Facility Operations Plan, unless otherwise authorized in writing by the Director.

**OPERATIONS**

4.6.10 The approval holder shall only transfer wastes and hazardous recyclables at designated transfer areas designed to contain spills and leaks.

4.6.11 The approval holder shall use the following when transferring substances to, from, and between containers, tanks, and trucks:

(a) couplings equipped with seals that are compatible with the substance transferred;

(b) the necessary precautions to prevent spills when the couplings are disconnected;

.....

## **TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (c) emergency shut-off valves;
  - (d) established transfer areas and associated curbing, paving and catchment areas;
  - (e) drip trays to capture potential losses under coupling devices and other connections; and
  - (f) manual inspections of the transfer area for leaks and spills during and after waste transfer.
- 4.6.12 All wastes and all hazardous recyclables that are unloaded shall be immediately transferred to the waste storage area.
- 4.6.13 All containers and unrinsed empty containers shall be stored in the waste storage area.
- 4.6.14 The approval holder shall:
- (a) provide and maintain an adequate aisle space between containers in the waste storage area to allow:
    - (i) inspection, and
    - (ii) unobstructed movement of personnel, fire protection equipment, spill control equipment and decontamination equipment to any area of the waste storage area; and
  - (b) arrange inspection aisles in the waste storage area such that the identification label on each container is readable.
- 4.6.15 All tanks within the tank farm area shall be equipped, at a minimum, with all of the following:
- (a) sensors for detecting the level in each tank;
  - (b) high level alarms that activate when a tank overfill is imminent;
  - (c) automatic shut-off devices or sufficient free board space above the high level sensor to allow operators time to prevent overfill from occurring; and
  - (d) earthen dikes or equivalent secondary containment structures capable of containing 110% of the volume of the largest tank within the bermed area plus 10% of the aggregate capacity of all other tanks in the bermed area.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.6.16 All tanks containing hazardous waste and all tanks containing hazardous recyclables in each building shall be equipped, at a minimum, with all of the following:
- (a) sensors or gauges for detecting the level in each tank;
  - (b) a written operating procedure to prevent tank overflow; and
  - (c) secondary containment structures capable of containing 110% of the volume of the largest tank within the building plus 10% of the aggregate capacity of all other tanks containing hazardous waste and hazardous recyclables in the same building.
- 4.6.17 Hazardous waste and hazardous recyclables stored in containers and tanks shall be stored in accordance with the *Hazardous Waste Storage Guidelines*, June 1988, Alberta Environment, as amended.
- 4.6.18 The approval holder shall only carry out the following activities, individually or in any combination, at the HWRSP Facility in relation to hazardous waste or hazardous recyclables or both:
- (a) commingling of hazardous waste or hazardous recyclables to make maximum use of available container or tank capacity, only if the resultant mixture has the same TDGR hazard classification as any one of the individual components;
  - (b) phase separation by gravity settling, only without the addition of any chemicals designed to accelerate settling;
  - (c) dispersion of solids into liquids by natural or mechanical means, only if the resultant mixture has the same TDGR hazard classification as the original waste;
  - (d) physical segregation of hazardous from non-hazardous articles or components from the same container, only if no process equipment is used;
  - (e) washing of drums or other objects, only for the purpose of removing hazardous residue;
  - (f) crushing or shredding of used filters, rags, absorbent materials, or empty containers, only for the purpose of volume reduction or liquid recovery, unless otherwise authorized in writing by the Director; or
  - (g) treatment of hazardous waste, only as authorized in writing by the Director.
- 4.6.19 Notwithstanding 4.6.18(g), the approval holder shall not incinerate waste at the facility.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

**LIMITS**

4.6.20 The approval holder shall not store a total of more than 752,500 litres of hazardous waste or hazardous recyclables or both at the HWRSP Facility at any time.

4.6.21 In addition to the storage limits in 4.6.20, the approval holder shall not exceed the waste storage limits as specified in TABLE 4.6-A.

**TABLE 4.6-A: STORAGE LIMITS FOR HAZARDOUS WASTE OR HAZARDOUS RECYCLABLES OR BOTH AT HWRSP FACILITY**

Waste/Recyclable Type	Material	Maximum Quantity
<b>Containers:</b> Hazardous waste or hazardous recyclables or both	TDGR Classification 2, 3, 4, 5, 6, 8 or 9 waste type only	512,500 litres (consisting of 2,500 drum equivalents, each 205 litre capacity)
<b>Bulk Tanks:</b> Hazardous waste or hazardous recyclables or both	Waste flammable liquids, used oil, or wastewaters; or TDGR Classification 3, 5, 6, 8 or 9 waste type only	240,000 litres (consisting of a total of 135 m <sup>3</sup> in the tank farm area, and a total of 105 m <sup>3</sup> inside the buildings)

4.6.22 Containers other than 205 litre drums shall be prorated to 205 litre drum equivalents based on their nominal volumes, e.g., 10 X 20 litre pails = 1 X 205 litre drum.

4.6.23 The limits referred to in 4.6.20 and 4.6.21 shall be calculated based on the:

- (a) total nominal volumes of all containers, treating all partially filled containers as if they were full; and
- (b) total filled capacities of all tanks.

**MONITORING AND REPORTING**

4.6.24 The approval holder shall:

- (a) identify;
- (b) characterize; and
- (c) classify

all waste streams and all hazardous recyclables, generated or received at the HWRSP Facility, not including runoff, industrial wastewater streams and air effluent streams in accordance with the:

- (i) *Industrial Waste Identification and Management Options*, Alberta Environment, May 1996, as amended, and

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (ii) *Alberta User Guide for Waste Managers*, Alberta Environment, August 1996, as amended.

4.6.25 The approval holder shall measure or, when not feasible to measure, estimate, the quantity of each waste and hazardous recyclable identified in 4.6.24 each year.

4.6.26 The approval holder shall keep a daily:

- (a) total; and
- (b) inventory

of all materials being stored at the HWRSP Facility.

4.6.27 The daily total and inventory records in 4.6.26 shall be available at the facility at all times for inspection by the Director or an inspector.

4.6.28 The approval holder shall submit a Monthly Waste Management Report to the Director.

4.6.29 The approval holder shall compile all of the information indicated in TABLE 4.6-B in the Monthly Waste Management Report which shall contain, at minimum, all of the following information:

- (a) an opening waste and hazardous recyclables inventory balance in kilograms or litres by waste class or material type;
- (b) the amount and type of waste and hazardous recyclables received:
  - (i) within the province, and
  - (ii) from outside the province;
- (c) the amount and type of waste and hazardous recyclables:
  - (i) shipped for recycling or product,
  - (ii) shipped off-site for disposal, and
  - (iii) disposed on-site;
- (d) any adjustments, including but not limited to, consolidation, reclassification, losses to processing, spills, volume miscalculations, or any other

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

**TABLE 4.6-B: MONTHLY WASTE INVENTORY REPORT (BY WASTE CLASS)**

COMPANY NAME: \_\_\_\_\_ APPROVAL NO.: \_\_\_\_\_  
REPORT PERIOD: MONTH \_\_\_\_\_ YEAR \_\_\_\_\_

CLASS	UNIT (Kg or L)	OPENING BALANCE	+ RECEIVED IN PROVINCE	+ RECEIVED OUT OF PROVINCE	- SHIPPED *		- ON-SITE DISPOSAL	+ or - ADJUSTMENT **	CLOSING BALANCE	APPROVAL LIMIT
					RECYCLING / PRODUCT	OFF-SITE DISPOSAL				
2										
3										
4										
5										
6.1										
8										
9.1										
9.2										
9.3										
PCB										
NR										
TOTAL										XXXXX
							No. of Containers On site			XXXXX
							Total Litres in Bulk Tanks			XXXXX

Name of Company Official: \_\_\_\_\_ Title: \_\_\_\_\_ Signature: \_\_\_\_\_

Report Date: \_\_\_\_\_

\* Provide a list of the recycling and disposal locations.

\*\* Identify the amount and reason for each adjustment.  
Adjustments include consolidation/reclassification, losses to processing, spills, volume miscalculations, or any other circumstances, which would affect the mass balance of the monthly inventory report.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

circumstances, which would affect the mass balance of the monthly inventory report;

- (e) closing balance in kilograms or litres;
- (f) a summary of contraventions reported pursuant to 2.1.1 related to waste and hazardous recyclables; and
- (g) any other information as required in writing by the Director.

4.6.30 The approval holder shall compile all the information required by 4.6.24 and 4.6.25 in an Annual Waste Management Summary Report:

- (a) as specified in TABLE 4.6-C; and
- (b) in accordance with the:
  - (i) *Industrial Waste Identification and Management Options*, Alberta Environment, May 1996, as amended, and
  - (ii) *Alberta User Guide for Waste Managers*, Alberta Environment, August 1996, as amended.

**TABLE 4.6-C: ANNUAL WASTE MANAGEMENT SUMMARY**

Waste or Hazardous Recyclable Name	Uniform Waste Code				Quantity (kg or L)		Stored	Recycled		Disposed	
	WC	PIN	Class	Mgmt	Hazardous	Non-hazardous	On-site	On-site	Off-site	On-site	Off-site
<b>TOTAL</b>											

4.6.31 The approval holder shall submit the Annual Waste Management Summary Report to the Director.

**LANDFILL**

**OPERATIONS PLAN**

4.6.32 The approval holder shall:

- (a) develop;
- (b) keep up-to-date; and



**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

(c) implement

a Landfill Operations Plan that does not contravene with the requirements of this approval.

4.6.33 The approval holder shall:

- (a) review the Landfill Operations Plan annually, at a minimum; and
- (b) update the Landfill Operations Plan if any of the following circumstances apply:
  - (i) there are facility expansions or changes in site operations or equipment,
  - (ii) there is an applicable change to the *Standards for Landfills in Alberta*, as amended,
  - (iii) an update is required in writing by the Director, or
  - (iv) there is an update to an applicable regulation.

4.6.34 The Landfill Operations Plan shall include, at a minimum, all of the following:

- (a) SOP for keeping and maintaining an Operating Record;
- (b) SOP for waste control, run-on and runoff controls, and nuisance controls;
- (c) SOP for the waste stabilization area operations;
- (d) SOP for the acceptance, handling and disposal of wastes, including:
  - (i) waste characterization and classification at source,
  - (ii) waste manifesting and tracking,
  - (iii) QA/QC waste acceptance procedures, and
  - (iv) waste sampling;
- (e) SOP for detecting, preventing and disposal of unauthorized wastes;
- (f) SOP for placing waste in a landfill cell including:
  - (i) working face width,
  - (ii) lift depth,

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (iii) compaction, and
- (iv) waste placement location using a grid system;
- (g) SOP for managing contaminated sulphur and sulphur containing wastes;
- (h) SOP for managing asbestos wastes;
- (i) SOP for placing leachate, leak detection liquid, or other authorized wastes and liquids over the surface of the active landfill area for the purpose of evaporation or dust suppression;
- (j) SOP for lab screening of pyrophoric wastes for water quenching;
- (k) SOP for water quenching treatment of pyrophoric wastes;
- (l) an Odour and Fugitive Dust Response Program, including odour from the HWRSP Facility;
- (m) a Fugitive Dust and Odour Best Management Plan, including odour from the HWRSP Facility;
- (n) a runoff and industrial wastewater monitoring and management program;
- (o) a leachate monitoring and management program;
- (p) a leak detection liquid monitoring and management program;
- (q) a groundwater monitoring program;
- (r) a Remediation Plan to deal with groundwater quality deterioration;
- (s) a soil monitoring program;
- (t) a soil management program;
- (u) a landfill cell cover system;
- (v) a monitoring and maintenance program for the scale house and heavy operational equipment;
- (w) a health and safety program;
- (x) a Facility Wildlife Management Plan, pursuant to 4.1.15;
- (y) a Community Complaint Response Plan, pursuant to 4.1.22;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (z) a Facility Emergency Management Plan, pursuant to 4.1.30; and
  - (aa) an up-to-date plan of the landfill layout with survey records showing the location of all infrastructure components of the landfill including final cover elevations and contours.
- 4.6.35 The approval holder shall include, at a minimum, all of the following in the SOP referred to in 4.6.34(j) for lab screening of pyrophoric wastes to assess the suitability of using water quenching to neutralize the reactivity of the pyrophoric wastes:
- (a) procedures and methods for obtaining representative pyrophoric wastes sample for lab test;
  - (b) procedures and methods for conducting lab screening test using representative sample of pyrophoric wastes, including:
    - (i) setup of lab test equipment,
    - (ii) test procedures,
    - (iii) collection of samples of off-gases from lab water quenching test,
    - (iv) screening parameters, including, at a minimum, odour, ammonia, H<sub>2</sub>S, PM, total metals, VOCs, TNMOCs, and total hydrocarbons, and
    - (v) analytical methods for testing the screening parameters;
  - (c) assessment of lab test results and passing criteria for screening; and
  - (d) documentation and record keeping of lab screening test results.
- 4.6.36 The approval holder shall retain a copy of the most recent Landfill Operations Plan at the facility.
- 4.6.37 The approval holder shall submit to the Director the most recent Landfill Operations Plan when requested in writing by the Director within the timeline specified in writing by the Director.
- 4.6.38 The approval holder shall correct all deficiencies in the Landfill Operations Plan submitted pursuant to 4.6.37, as outlined in writing by the Director, within the timeline specified in writing by the Director.
- 4.6.39 The approval holder shall implement the latest Landfill Operations Plan, unless otherwise authorized in writing by the Director.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL****OPERATIONS**

- 4.6.40 The approval holder shall classify all materials entering the landfill in accordance with the:
- (a) *Waste Control Regulation (AR 192/96)*;
  - (b) *Industrial Waste Identification and Management Options*, Alberta Environment, May 1996, as amended; and
  - (c) *Alberta User Guide for Waste Managers*, May 1995, as amended.
- 4.6.41 The approval holder shall obtain a detailed representative physical and chemical analysis of a waste prior to disposal of the waste into the landfill at the following times, at a minimum:
- (a) the first time a waste is received from a new generator;
  - (b) the first time a delivery is received from a different process associated with a known waste generator;
  - (c) the first time a waste is received from a different location associated with a known waste generator; and
  - (d) when the nature or composition of the waste that was previously characterized by the generator changes.
- 4.6.42 The approval holder shall not dispose of hazardous waste in any Class II landfill cell.
- 4.6.43 The approval holder:
- (a) shall only carry out waste stabilization or solidification or both within the waste stabilization area(s);
  - (b) shall only operate waste:
    - (i) receiving, and
    - (ii) stabilizationarea(s) as described in the application;
  - (c) shall not transfer waste from the waste stabilization area to the Class I landfill cell before the waste stabilization or solidification or both have been completed; and

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (d) may treat pyrophoric wastes by water quenching only within the waste stabilization area, subject to passing lab screening criteria;

unless otherwise authorized in writing by the Director.

4.6.44 The approval holder shall only dispose of any liquid collected within the waste stabilization area by one or more of the following methods:

- (a) to facilities holding a current Act authorization to accept such waste;
- (b) to facilities approved by a local environmental authority outside of Alberta to accept such waste;
- (c) to a disposal well approved by AER; or
- (d) as otherwise authorized in writing by the Director.

4.6.45 The approval holder shall conduct:

- (a) annually, in-house visual inspections for corrosion; and
- (b) biennially, ultrasonic testing to monitor thickness

of the steel plate liner of the stabilization pits in the waste stabilization area, unless otherwise authorized in writing by the Director.

4.6.46 The approval holder shall dispose of asbestos wastes in accordance with "*Guidelines for the Disposal of Asbestos Waste*", Environmental Protection Services, Alberta Environment, 1989, as amended.

4.6.47 The approval holder shall dispose of sulphur waste in accordance with "*Guidelines for Landfill Disposal of Sulphur Wastes and Remediation of Sulphur Containing Soils*", Alberta Environment, 2011, as amended.

4.6.48 The approval holder shall only dispose of wastes that the landfill is not authorized to dispose of:

- (a) to facilities holding a current Act authorization;
- (b) to facilities approved by a local environmental authority outside of Alberta; or
- (c) as otherwise authorized in writing by the Director.

4.6.49 If an unauthorized waste is received at the landfill, the approval holder shall remove the waste from the landfill within seven (7) days of the receipt, unless otherwise authorized in writing by the Director.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.6.50 The approval holder shall restrict the working face of each landfill cell to the smallest practical area.
- 4.6.51 For any waste disposed of at the landfill that is subject to wind dispersal or release of offensive odours or both, the approval holder shall:
- (a) wet the waste to prevent dispersal of particulate matter; and
  - (b) immediately apply effective cover on top of the waste to control releases of:
    - (i) particulate matter, and
    - (ii) offensive odours.
- 4.6.52 Notwithstanding 4.6.1(v), the approval holder may place any of the following wastes over the surface of the active landfill area for the purpose of dust suppression:
- (a) specified runoff;
  - (b) leachate;
  - (c) leak detection liquid;
  - (d) sump waste of car wash bays or similar operations;
  - (e) waste from hydrovac excavation operations; or
  - (f) any other waste authorized by *the Alberta User Guide for Waste Managers*, May 1995, as amended;
- provided that placement of such wastes will not cause offensive odours.
- 4.6.53 The approval holder shall inspect the landfill, at a minimum:
- (a) weekly; and
  - (b) immediately after each storm event to:
    - (i) detect evidence of deterioration of any infrastructure components, including the composite liner,
    - (ii) detect any malfunction or improper operation of the run-on and runoff control systems, leachate collection system, or leak detection system, and
    - (iii) take corrective measures to repair any damage to infrastructure components, including the composite liner.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.6.54 The approval holder shall:
- (a) keep a record of inspections conducted pursuant to 4.6.53;
  - (b) have the record of inspections available for review upon written request from the Director; and
  - (c) immediately report any deficiencies detected by the inspection in 4.6.53 to the Director in writing along with any corrective measures taken or proposed.
- 4.6.55 The approval holder shall not stockpile waste exceeding the maximum designated waste elevation of the landfill for a period of more than two (2) weeks, unless otherwise authorized in writing by the Director.
- 4.6.56 The approval holder shall take all practical and effective measures to prevent off-site tracking of waste from vehicles and equipment leaving the facility.
- 4.6.57 The approval holder shall operate the laydown area in the NE 9-50-17 W4M area of the facility only as described in the application.

**MONITORING AND REPORTING**

- 4.6.58 The approval holder shall monitor the landfill operations as required in TABLE 4.6-D.
- 4.6.59 The approval holder shall report to the Director the results of the landfill operations monitoring as required in TABLE 4.6-D.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

**TABLE 4.6-D: LANDFILL OPERATIONS MONITORING AND REPORTING REQUIREMENTS**

MONITORING AND REPORTING				
Parameter	Frequency	Sample Type	Sampling Location	Reporting
Quantity and type of waste received	Continuously, When operating	Measured or estimated	At entrance to landfill	Annual Landfill Operations Report
Quantity and type of material removed	Continuously, when operating	Measured or estimated	At entrance to landfill	
General location of waste deposited	Continuously, when operating	As per survey, or using grid system	At active landfill area, or survey coordinates	
Leachate head	at least: - once every three working days; - after storm event; and - immediately prior to leachate removal	Calculated	At primary leachate collection system sumps for existing landfill Cell 1	
		Measured	At primary leachate collection system sumps for all other landfill cells	
Leachate analysis, as per TABLE 4.4-A	At least once every quarter year, unless insufficient sample volume is available	Grab sample	At each primary leachate collection system sump	
Volume of leachate removed from the leachate collection system	As removed	Measured or calculated	At leachate collection system sumps	
Leak detection liquid analysis, as per TABLE 4.4-A	At least once every quarter year, unless insufficient sample volume is available	Grab sample	At each leak detection system sump	
Volume of leak detection liquid removed from the leak detection system	At least once every working day, as removed	Measured or calculated	At leak detection system sumps	
Final cover	When final cover is applied	Final cover by survey cores or test pits or both	On each completed landfill cell	

4.6.60 The Annual Landfill Operations Report required in TABLE 4.6-D shall include, at a minimum, all of the following:

- (a) the name and contact information of the person responsible for the facility;
- (b) a summary of all information collected as required in TABLE 4.6-D;
- (c) a summary of the results of any audit conducted in accordance with 4.1.7;
- (d) a summary of the operations of the waste stabilization area;



**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (e) a summary of the performance of the run-on and runoff control systems, including a comparison to the limits in TABLES 4.3-B and 4.3-C;
- (f) a summary of the performance of the leachate collection system, including a comparison to the maximum acceptable leachate head;
- (g) a summary of the performance of the leak detection system, including a comparison to the action leakage rate limit;
- (h) the Response Action Plan for the leak detection system pursuant to 4.4.10;
- (i) the Annual Dugout and Water Well Sampling Program Report pursuant to 4.5.4;
- (j) a summary of all revisions to the Landfill Operations Plan pursuant to 4.6.33(b);
- (k) any groundwater remedial action taken pursuant to 4.6.34(r);
- (l) a summary of records of landfill inspections pursuant to 4.6.53;
- (m) a summary of:
  - (i) operational issues encountered,
  - (ii) emergencies occurred, and
  - (iii) measures or actions taken;
- (n) a summary of records of:
  - (i) public complaints, and
  - (ii) the approval holder's responses;
- (o) an up-to-date financial security estimate pursuant to 5.1.2;
- (p) an updated site development plan showing the status of the landfill progression at the end of the operating year, including but not limited to:
  - (i) contour mapping,
  - (ii) the location of active and inactive disposal areas,
  - (iii) areas where a final cover has been placed, and
  - (iv) the location of new landfill cell(s) constructed;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (q) the Annual Landfill Cell Closure Report pursuant to 7.1.7;
- (r) a summary of contraventions reported pursuant to 2.1.1 related to landfill operations; and
- (s) any other information as required in writing by the Director.

4.6.61 The approval holder shall submit the Annual Landfill Operations Report to the Director.

**SECTION 4.7: DOMESTIC WASTEWATER**

**OPERATIONS**

4.7.1 The approval holder shall not release any substances from the domestic wastewater system to the surrounding watershed except as authorized by this approval.

4.7.2 The approval holder shall direct all domestic wastewater to the domestic wastewater system.

4.7.3 The approval holder shall only dispose of substances from the domestic wastewater system:

- (a) to facilities holding a current Act authorization;
- (b) to facilities approved by a local environmental authority outside of Alberta; or
- (c) as otherwise authorized in writing by the Director.

**SECTION 4.8: WATERWORKS**

Not used at this time.

**SECTION 4.9: GROUNDWATER**

**BASELINE MONITORING AND REPORTING**

4.9.1 The approval holder shall submit a proposal for a Baseline Groundwater Monitoring Program for the NE 9-50-17 W4M area of the facility on or before October 31, 2022, unless otherwise authorized in writing by the Director.

4.9.2 If the Baseline Groundwater Monitoring Program proposal submitted pursuant to 4.9.1 is found deficient by the Director, the approval holder shall correct all deficiencies as outlined in writing by the Director within the timeline specified in writing by the Director.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.9.3 The approval holder shall implement the Baseline Groundwater Monitoring Program referred to in 4.9.1 as authorized in writing by the Director prior to commencing operation of any new landfill cell(s) in the NE 9-50-17 W4M area of the facility, unless otherwise authorized in writing by the Director.
- 4.9.4 The approval holder shall submit a Baseline Groundwater Monitoring Program Report to the Director within six (6) months of completing the Baseline Groundwater Monitoring Program, unless otherwise authorized in writing by the Director.

**MONITORING**

- 4.9.5 The approval holder shall continue to implement the existing Groundwater Monitoring Program as authorized in writing by the Director, unless and until otherwise authorized in writing by the Director pursuant to 4.9.8.
- 4.9.6 The approval holder shall submit a revised Groundwater Monitoring Program to the Director on or before December 31, 2022, unless otherwise authorized in writing by the Director.
- 4.9.7 If the revised Groundwater Monitoring Program submitted pursuant to 4.9.6 is found deficient by the Director, the approval holder shall correct all deficiencies as outlined in writing by the Director within the timeline specified in writing by the Director.
- 4.9.8 The approval holder shall implement the revised Groundwater Monitoring Program submitted pursuant to 4.9.6 as authorized in writing by the Director within the timeline specified in writing by the Director.
- 4.9.9 The approval holder shall:
  - (a) collect a representative groundwater sample from each of the groundwater monitor wells specified in the Groundwater Monitoring Program, including the groundwater monitoring wells designated as points of compliance; and
  - (b) analyze each sample for the parameters listed in TABLE 4.9-A.

**TABLE 4.9-A: GROUNDWATER MONITORING PROGRAM**

PARAMETERS	
pH	Metals
Electrical conductivity	Major ions
COD	Nutrients
DOC	BTEX
TDS	Petroleum Hydrocarbons Fractions F1 and F2

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.9.10 The monitoring required in 4.9.9 shall be conducted at the following frequencies, unless otherwise authorized in writing by the Director:
- (a) a minimum of once per year during each of the active landfill life, landfill cell closure, final landfill closure, and post-closure periods; and
  - (b) a minimum of four times per year following detection of leachate constituents in groundwater at levels above those specified in 4.9.11, and until the levels specified in 4.9.11 have been met.
- 4.9.11 The groundwater quality in the monitoring wells, designated as points of compliance in the Groundwater Monitoring Program, shall not exceed the higher of:
- (a) the objectives established in the water quality objectives in the *Canadian Environmental Quality Guidelines (CEQG)* for drinking water published by the Canadian Council of Ministers of the Environment (CCME), as amended; or
  - (b) background groundwater chemistry as determined through a statistical analysis, as a derived alternate groundwater performance standard.
- 4.9.12 The approval holder shall implement the Remediation Plan as specified in the Landfill Operations Plan, when groundwater quality exceeds the groundwater performance criteria in 4.9.11.
- 4.9.13 The samples extracted from the groundwater monitor wells shall be collected using scientifically acceptable purging, sampling and preservation procedures so that a representative groundwater sample is obtained.
- 4.9.14 The approval holder shall:
- (a) protect from damage; and
  - (b) keep locked except when being sampled
- all groundwater monitoring wells unless otherwise authorized in writing by the Director.
- 4.9.15 If a representative groundwater sample cannot be collected because the groundwater monitoring well is damaged or is no longer capable of producing a representative groundwater sample, the approval holder shall:
- (a) clean, repair or replace the groundwater monitoring well; and
  - (b) collect and analyse a representative groundwater sample prior to the next scheduled sampling event;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

unless otherwise authorized in writing by the Director.

- 4.9.16 In addition to the sampling information recorded in 2.2.1, the approval holder shall record the following sampling information for all groundwater samples collected:
- (a) a description of purging and sampling procedures;
  - (b) the static elevations above sea level, and depth below ground surface of fluid phases in the groundwater monitoring well prior to purging;
  - (c) the temperature of each sample at the time of sampling;
  - (d) the pH of each sample at the time of sampling; and
  - (e) the specific conductance of each sample at the time of sampling.
- 4.9.17 The approval holder shall carry out remediation of the groundwater in accordance with the following:
- (a) *Alberta Tier 1 Soil and Groundwater Remediation Guidelines*, Alberta Environment, February 2009, as amended; and
  - (b) *Alberta Tier 2 Soil and Groundwater Remediation Guidelines*, Alberta Environment, February 2009, as amended.

**REPORTING**

- 4.9.18 The approval holder shall compile an Annual Groundwater Monitoring Program Report which shall include, at a minimum, all of the following information:
- (a) a completed *Record of Site Condition Form*, Alberta Environment, 2009, as amended;
  - (b) a legal land description of the facility and a map illustrating the facility boundaries;
  - (c) a topographic map of the facility;
  - (d) a description of the industrial activity and processes;
  - (e) a map showing the location of all surface and groundwater users, and a listing describing surface water and water well use details, within at least a 1.6 kilometre radius of the facility;
  - (f) a general hydrogeological characterization of the region within a five kilometre radius of the facility;

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (g) a detailed hydrogeological characterization of the facility, including an interpretation of groundwater flow patterns;
- (h) cross-sections showing depth to water table, patterns of groundwater movement and hydraulic gradients at the facility;
- (i) borehole logs and completion details for groundwater monitoring wells;
- (j) a map showing locations of all known buried channels within at least five kilometre of the facility;
- (k) a map of surface drainage within the facility and surrounding area to include nearby water bodies;
- (l) a map of groundwater monitoring well locations and a table summarizing the existing groundwater monitoring program for the facility;
- (m) a summary of any changes to the groundwater monitoring program made since the last groundwater monitoring report;
- (n) analytical data recorded as required in 4.9.9 and 4.9.15(b);
- (o) a summary of fluid elevations recorded as required in 4.9.16(b) and an interpretation of changes in fluid elevations;
- (p) an interpretation of QA/QC program results;
- (q) an interpretation of all the data in this report, including the following:
  - (i) diagrams indicating the location and extent of any contamination,
  - (ii) a description of probable sources of contamination, and
  - (iii) a site map showing the location and type of current and historical potential sources of groundwater contamination;
- (r) a summary and interpretation of the data collected since the groundwater monitoring program began including:
  - (i) control charts which indicate trends in concentrations of parameters, and
  - (ii) the migration of contaminants;
- (s) a description of the following:
  - (i) contaminated groundwater remediation techniques employed,

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (ii) source elimination measures employed,
- (iii) risk assessment studies undertaken, and
- (iv) risk management studies undertaken;
- (t) a proposed sampling schedule for the following year(s);
- (u) a description of any contaminant remediation, risk assessment or risk management action conducted at the facility; and
- (v) recommendations for:
  - (i) changes to the groundwater monitoring program to make it more effective, and
  - (ii) remediation, risk assessment or risk management of contamination identified.

4.9.19 The approval holder shall submit the Annual Groundwater Monitoring Program Report to the Director.

4.9.20 If the Annual Groundwater Monitoring Program Report is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director, within the timeline specified in writing by the Director.

**SECTION 4.10: SOIL**

4.10.1 In addition to any other requirements specified in this approval, the approval holder shall conduct all of the following activities related to soil monitoring and soil management required by this approval in accordance with the *Soil Monitoring Directive*, Alberta Environment, 2009, as amended:

- (a) designing and developing proposals for the Soil Monitoring Program;
- (b) designing and developing proposals for the Soil Management Program;
- (c) all other actions, including sampling, analysing, and reporting, associated with the Soil Monitoring Program; and
- (d) all other actions, including sampling, analysing and reporting, associated with the Soil Management Program.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

**BASELINE MONITORING AND REPORTING**

- 4.10.2 The approval holder shall submit a proposal for a Baseline Soil Monitoring Program for the NE 9-50-17 W4M area of the facility on or before October 31, 2022, unless otherwise authorized in writing by the Director.
- 4.10.3 If the Baseline Soil Monitoring Program proposal submitted pursuant to 4.10.2 is found deficient by the Director, the approval holder shall correct all deficiencies as outlined in writing by the Director within the timeline specified in writing by the Director.
- 4.10.4 The approval holder shall implement the Baseline Soil Monitoring Program referred to in 4.10.2 as authorized in writing by the Director prior to commencing operation of any new landfill cell(s) in the NE 9-50-17 W4M area of the facility, unless otherwise authorized in writing by the Director.
- 4.10.5 The approval holder shall submit a Baseline Soil Monitoring Program Report to the Director within six (6) months of completing the Baseline Soil Monitoring Program, unless otherwise authorized in writing by the Director.

**MONITORING AND REPORTING**

- 4.10.6 The approval holder shall submit the Soil Monitoring Program proposal to the Director according to the following schedule:
  - (a) for the first soil monitoring event on or before January 31, 2019; and
  - (b) for the second soil monitoring event on or before January 31, 2024;unless otherwise authorized in writing by the Director.
- 4.10.7 If any Soil Monitoring Program proposal is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.
- 4.10.8 Subject to 4.10.7, the approval holder shall implement the Soil Monitoring Program as authorized in writing by the Director.
- 4.10.9 If an authorization or a deficiency letter is not issued within 120 days of the applicable date required by 4.10.6, the approval holder shall implement the Soil Monitoring Program:
  - (a) in accordance with the program as set out in the proposal submitted by the approval holder; and
  - (b) within 270 days after the applicable date required by 4.10.6.



**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 4.10.10 The approval holder shall submit to the Director each Soil Monitoring Program Report obtained from the soil monitoring referred to in 4.10.8 and 4.10.9 according to the following schedule:
- (a) for the first Soil Monitoring Program Report on or before January 31, 2020; and
  - (b) for the second Soil Monitoring Program Report on or before January 31, 2025;
- unless otherwise authorized in writing by the Director.
- 4.10.11 If any Soil Monitoring Program Report is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.

**SOIL MANAGEMENT PROGRAM**

- 4.10.12 If the Soil Monitoring Program, or any other soil monitoring, reveals that there are substances present in the soil at concentrations greater than any of the applicable concentrations set out in the standards in the *Soil Monitoring Directive*, Alberta Environment, 2009, as amended, the approval holder shall develop a Soil Management Program Proposal.
- 4.10.13 If a Soil Management Program Proposal is required pursuant to 4.10.12, the approval holder shall submit a Soil Management Program Proposal to the Director according to the following schedule:
- (a) for Soil Management Program Proposal that is triggered by the findings from the first soil monitoring event on or before the date in 4.10.10(a);
  - (b) for Soil Management Program Proposal that is triggered by the findings from a second soil monitoring event on or before the date in 4.10.10(b); or
  - (c) for any other soil monitoring event not specified in this approval within six months of completion of the soil monitoring event.
- 4.10.14 If any Soil Management Program Proposal is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.
- 4.10.15 The approval holder shall implement the Soil Management Program as authorized in writing by the Director.
- 4.10.16 If the approval holder is required to implement a Soil Management Program pursuant to 4.10.15, the approval holder shall submit a written Soil Management

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

Program Report to the Director on or before March 31 of each year following the year in which the information was collected.

- 4.10.17 If any Soil Management Program Report is found deficient by the Director, the approval holder shall correct all deficiencies identified by the Director by the date specified in writing by the Director.

**PART 5: FINANCIAL SECURITY REQUIREMENTS**

- 5.1.1 The approval holder shall annually review and revise the cost estimate for reclamation of the facility including decommissioning and land reclamation.
- 5.1.2 The annual revised cost estimate for the facility shall be submitted to the Director by March 31 of each year.
- 5.1.3 The approval holder shall review and revise the cost estimate for reclamation of the facility when one or more of the following occurs:
- (a) the cost estimate of future conservation and reclamation of the facility changes;
  - (b) the extent of the operation of the facility is increased or reduced;
  - (c) the facility or any portion of it is conserved and reclaimed;
  - (d) the conservation and reclamation plan required by this approval is changed;  
or
  - (e) the activities conducted at the facility for which security is required is increased or decreased.
- 5.1.4 The approval holder shall submit the revised cost estimate arising from 5.1.3 to the Director within 30 days after the occurrence of any of the circumstances described in 5.1.3.
- 5.1.5 The approval holder shall provide additional financial security as required in writing by the Director.
- 5.1.6 The approval holder shall renew the financial security for the facility at least 30 days prior to the date it expires.
- 5.1.7 The approval holder shall maintain the financial security for the facility until returned in accordance with the Act or the regulations.

TERMS AND CONDITIONS ATTACHED TO APPROVAL

**PART 6: DECOMMISSIONING AND LAND RECLAMATION OF HWRSP FACILITY**

**SECTION 6.1: GENERAL**

6.1.1 The approval holder shall apply for an amendment to this approval to reclaim the HWRSP Facility by submitting to the Director:

- (a) a Decommissioning Plan; and
- (b) a Land Reclamation Plan.

6.1.2 The approval holder shall submit the:

- (a) Decommissioning Plan; and
- (b) Land Reclamation Plan

referred to in 6.1.1 within six (6) months of the HWRSP Facility ceasing operation, except for repairs and maintenance, unless otherwise authorized in writing by the Director.

**SECTION 6.2: DECOMMISSIONING**

6.2.1 The Decommissioning Plan referred to in 6.1.1 shall include, at a minimum, all of the following:

- (a) a plan for dismantling the HWRSP Facility;
- (b) a comprehensive study to determine the nature, degree and extent of contamination at the HWRSP Facility and affected lands;
- (c) a plan to manage all wastes at the HWRSP Facility;
- (d) evaluation of remediation technologies proposed to be used at the HWRSP Facility and affected lands;
- (e) a plan for decontamination of the HWRSP Facility and affected lands in accordance with the following:
  - (iii) for soil or groundwater, *Alberta Tier 1 Soil and Groundwater Remediation Guidelines*, Alberta Environment, February 2009, as amended,
  - (iv) for soil or groundwater, *Alberta Tier 2 Soil and Groundwater Remediation Guidelines*, Alberta Environment, February 2009, as amended,

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- (v) for drinking water, *Canadian Environmental Quality Guidelines*, Canadian Council of Ministers of the Environment, PN 1299, 1999, as amended, and
- (vi) for surface water, *Surface Water Quality Guidelines for Use in Alberta*, Alberta Environment, November 1999, as amended;
- (f) confirmatory testing to indicate compliance with the remediation objectives;
- (g) a plan for maintaining and operating contaminant monitoring systems;
- (h) a schedule for activities (a) through (g) above; and
- (i) any other information as required in writing by the Director.

6.2.2 If the Decommissioning Plan is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.

**SECTION 6.3: LAND RECLAMATION**

6.3.1 The Land Reclamation Plan referred to in 6.1.1 shall include, at a minimum, all of the following:

- (a) the final use of the reclaimed area and how equivalent land capability will be achieved;
- (b) removal of infrastructure;
- (c) restoration of drainage;
- (d) soil replacement;
- (e) erosion control;
- (f) revegetation and conditioning of the HWRSP Facility including:
  - (i) species list, seed source and quality, seeding rates and methods,
  - (ii) fertilization rates and methods, and
  - (iii) wildlife habitat plans where applicable;
- (g) reclamation schedule; and
- (h) any other information as required in writing by the Director.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 6.3.2 If the Land Reclamation Plan is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.

**PART 7: FINAL LANDFILL CLOSURE AND POST-CLOSURE**

**SECTION 7.1: LANDFILL CELL CLOSURE AND MAINTENANCE**

- 7.1.1 The approval holder shall submit a Landfill Cell Closure Plan for individual landfill cell closure to the Director on or before September 30, 2017, unless otherwise authorized in writing by the Director.
- 7.1.2 The Landfill Cell Closure Plan submitted pursuant to 7.1.1 shall be signed and stamped by a professional registered with APEGA.
- 7.1.3 If the Landfill Cell Closure Plan submitted pursuant to 7.1.1 is found deficient by the Director, the approval holder shall correct all deficiencies as outlined in writing by the Director within the timeline specified in writing by the Director.
- 7.1.4 The approval holder shall implement the Landfill Cell Closure Plan submitted pursuant to 7.1.1 as authorized in writing by the Director.
- 7.1.5 The approval holder shall maintain the closed landfill cells to:
- (a) protect and maintain the integrity of the final cover and surface water drainage systems;
  - (b) prevent erosion;
  - (c) prevent surface water ponding;
  - (d) remediate areas affected by subsidence and differential settlement; and
  - (e) prevent leachate break out.
- 7.1.6 If the approval holder completes landfill cell closure in a year, the approval holder shall prepare an Annual Landfill Cell Closure Report, and include, at a minimum, all of the following information in the Report:
- (a) as-built plans and details on the location of landfill cells that have been closed;
  - (b) certified construction QA/QC procedures employed during cover construction and installation; and
  - (c) survey reports showing the final cover depths.

## **TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 7.1.7 The approval holder shall submit the Annual Landfill Cell Closure Report with the Annual Landfill Operations Report required in 4.6.60.

### **SECTION 7.2: FINAL LANDFILL CLOSURE AND POST-CLOSURE**

- 7.2.1 The approval holder shall apply for an amendment to this approval for final landfill closure by submitting to the Director:

- (a) a Detailed Final Landfill Closure Plan ; and
- (b) a Landfill Post-Closure Plan.

- 7.2.2 The approval holder shall submit the:

- (a) Detailed Final Landfill Closure Plan; and
- (b) Landfill Post-Closure Plan

referred to in 7.2.1 within six (6) months of the landfill ceasing operations, unless otherwise authorized in writing by the Director.

### **DETAILED FINAL LANDFILL CLOSURE PLAN**

- 7.2.3 The Detailed Final Landfill Closure Plan shall be developed in accordance with sections 6.1(b) and 6.1(c) of the *Standards for Landfills in Alberta*, as amended.

- 7.2.4 In addition to 7.2.3, the Detailed Final Landfill Closure Plan shall include, at a minimum, all of the following:

- (a) a plan for replacement of soil;
- (b) a QA/QC Program; and
- (c) any deviations from the most recently submitted closure plan.

- 7.2.5 The Detailed Final Landfill Closure Plan shall be signed and stamped by a professional registered with APEGA.

- 7.2.6 If the Detailed Final Landfill Closure Plan is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.

- 7.2.7 The approval holder shall implement the Detailed Final Landfill Closure Plan as authorized in writing by the Director.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL****LANDFILL POST-CLOSURE PLAN**

- 7.2.8 The Landfill Post-Closure Plan shall be developed in accordance with sections 6.2 and 6.3 of the *Standards for Landfills in Alberta*, as amended.
- 7.2.9 In addition to 7.2.8, the Landfill Post-Closure Plan shall include, at a minimum, all of the following:
- (a) the groundwater monitoring program including performance standards and points of compliance;
  - (b) the subsurface landfill gas monitoring program and performance standards at points of compliance;
  - (c) a plan for erosion control;
  - (d) a plan for maintaining vegetative cover; and
  - (e) any other information requested in writing by the Director.
- 7.2.10 The Landfill Post-Closure Plan shall be signed and stamped by a professional registered with APEGA.
- 7.2.11 If the Landfill Post-Closure Plan is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.
- 7.2.12 The approval holder shall implement the Landfill Post-Closure Plan as authorized in writing by the Director.

**PART 8: DECOMMISSIONING AND LAND RECLAMATION OF OLD SURFACE WATER DETENTION POND**

- 8.1.1 The approval holder shall:
- (a) decommission; and
  - (b) reclaim
- the old surface water detention pond prior to construction of Cell 4.
- 8.1.2 The approval holder shall submit a Decommissioning and Land Reclamation Plan for the old surface water detention pond to the Director a minimum of six (6) months prior to decommissioning and land reclamation of the pond.

**TERMS AND CONDITIONS ATTACHED TO APPROVAL**

- 8.1.3 If the Decommissioning and Land Reclamation Plan is found deficient by the Director, the approval holder shall correct all deficiencies identified in writing by the Director by the date specified in writing by the Director.



June 21, 2022

DATE SIGNED

\_\_\_\_\_  
DESIGNATED DIRECTOR UNDER THE ACT  
Mohammad Habib, P. Eng.



## APPENDIX B

### TETRA TECH'S LIMITATIONS ON THE USE OF THIS DOCUMENT

# LIMITATIONS ON USE OF THIS DOCUMENT

## GEOENVIRONMENTAL

### 1.1 USE OF DOCUMENT AND OWNERSHIP

This document pertains to a specific site, a specific development, and a specific scope of work. The document may include plans, drawings, profiles and other supporting documents that collectively constitute the document (the "Professional Document").

The Professional Document is intended for the sole use of TETRA TECH's Client (the "Client") as specifically identified in the TETRA TECH Services Agreement or other Contractual Agreement entered into with the Client (either of which is termed the "Contract" herein). TETRA TECH does not accept any responsibility for the accuracy of any of the data, analyses, recommendations or other contents of the Professional Document when it is used or relied upon by any party other than the Client, unless authorized in writing by TETRA TECH.

Any unauthorized use of the Professional Document is at the sole risk of the user. TETRA TECH accepts no responsibility whatsoever for any loss or damage where such loss or damage is alleged to be or, is in fact, caused by the unauthorized use of the Professional Document.

Where TETRA TECH has expressly authorized the use of the Professional Document by a third party (an "Authorized Party"), consideration for such authorization is the Authorized Party's acceptance of these Limitations on Use of this Document as well as any limitations on liability contained in the Contract with the Client (all of which is collectively termed the "Limitations on Liability"). The Authorized Party should carefully review both these Limitations on Use of this Document and the Contract prior to making any use of the Professional Document. Any use made of the Professional Document by an Authorized Party constitutes the Authorized Party's express acceptance of, and agreement to, the Limitations on Liability.

The Professional Document and any other form or type of data or documents generated by TETRA TECH during the performance of the work are TETRA TECH's professional work product and shall remain the copyright property of TETRA TECH.

The Professional Document is subject to copyright and shall not be reproduced either wholly or in part without the prior, written permission of TETRA TECH. Additional copies of the Document, if required, may be obtained upon request.

### 1.2 ALTERNATIVE DOCUMENT FORMAT

Where TETRA TECH submits electronic file and/or hard copy versions of the Professional Document or any drawings or other project-related documents and deliverables (collectively termed TETRA TECH's "Instruments of Professional Service"), only the signed and/or sealed versions shall be considered final. The original signed and/or sealed electronic file and/or hard copy version archived by TETRA TECH shall be deemed to be the original. TETRA TECH will archive a protected digital copy of the original signed and/or sealed version for a period of 10 years.

Both electronic file and/or hard copy versions of TETRA TECH's Instruments of Professional Service shall not, under any circumstances, be altered by any party except TETRA TECH. TETRA TECH's Instruments of Professional Service will be used only and exactly as submitted by TETRA TECH.

Electronic files submitted by TETRA TECH have been prepared and submitted using specific software and hardware systems. TETRA TECH makes no representation about the compatibility of these files with the Client's current or future software and hardware systems.

### 1.3 STANDARD OF CARE

Services performed by TETRA TECH for the Professional Document have been conducted in accordance with the Contract, in a manner

consistent with the level of skill ordinarily exercised by members of the profession currently practicing under similar conditions in the jurisdiction in which the services are provided. Professional judgment has been applied in developing the conclusions and/or recommendations provided in this Professional Document. No warranty or guarantee, express or implied, is made concerning the test results, comments, recommendations, or any other portion of the Professional Document.

If any error or omission is detected by the Client or an Authorized Party, the error or omission must be immediately brought to the attention of TETRA TECH.

### 1.4 DISCLOSURE OF INFORMATION BY CLIENT

The Client acknowledges that it has fully cooperated with TETRA TECH with respect to the provision of all available information on the past, present, and proposed conditions on the site, including historical information respecting the use of the site. The Client further acknowledges that in order for TETRA TECH to properly provide the services contracted for in the Contract, TETRA TECH has relied upon the Client with respect to both the full disclosure and accuracy of any such information.

### 1.5 INFORMATION PROVIDED TO TETRA TECH BY OTHERS

During the performance of the work and the preparation of this Professional Document, TETRA TECH may have relied on information provided by persons other than the Client.

While TETRA TECH endeavours to verify the accuracy of such information, TETRA TECH accepts no responsibility for the accuracy or the reliability of such information even where inaccurate or unreliable information impacts any recommendations, design or other deliverables and causes the Client or an Authorized Party loss or damage.

### 1.6 GENERAL LIMITATIONS OF DOCUMENT

This Professional Document is based solely on the conditions presented and the data available to TETRA TECH at the time the data were collected in the field or gathered from available databases.

The Client, and any Authorized Party, acknowledges that the Professional Document is based on limited data and that the conclusions, opinions, and recommendations contained in the Professional Document are the result of the application of professional judgment to such limited data.

The Professional Document is not applicable to any other sites, nor should it be relied upon for types of development other than those to which it refers. Any variation from the site conditions present, or variation in assumed conditions which might form the basis of design or recommendations as outlined in this report, at or on the development proposed as of the date of the Professional Document requires a supplementary investigation and assessment.

TETRA TECH is neither qualified to, nor is it making, any recommendations with respect to the purchase, sale, investment or development of the property, the decisions on which are the sole responsibility of the Client.

### 1.7 NOTIFICATION OF AUTHORITIES

In certain instances, the discovery of hazardous substances or conditions and materials may require that regulatory agencies and other persons be informed and the client agrees that notification to such bodies or persons as required may be done by TETRA TECH in its reasonably exercised discretion.

## APPENDIX C

### LABORATORY CERTIFICATE OF ANALYSIS



## CERTIFICATE OF ANALYSIS

<p><b>Work Order</b> : <b>EO2309502</b></p> <p><b>Amendment</b> : <b>1</b></p> <p><b>Client</b> : <b>Tetra Tech Canada Inc.</b></p> <p><b>Contact</b> : Brent Finnestad</p> <p><b>Address</b> : North Building 14940 123 Ave NW Edmonton AB Canada T5V 1B4</p> <p><b>Telephone</b> : 780-718-9317</p> <p><b>Project</b> : 704-SWM.SWOP04810-01</p> <p><b>PO</b> : 704-SWM.SWOP04810-01</p> <p><b>C-O-C number</b> : ----</p> <p><b>Sampler</b> : ----</p> <p><b>Site</b> : ----</p> <p><b>Quote number</b> : EO23-EBAE100-006 (Q83988)</p> <p><b>No. of samples received</b> : 23</p> <p><b>No. of samples analysed</b> : 23</p>	<p><b>Page</b> : 1 of 23</p> <p><b>Laboratory</b> : ALS Environmental - Edmonton</p> <p><b>Account Manager</b> : Kieran Tordoff</p> <p><b>Address</b> : 9450 - 17 Avenue NW Edmonton AB Canada T6N 1M9</p> <p><b>Telephone</b> : +1 780 413 5227</p> <p><b>Date Samples Received</b> : 17-Oct-2023 15:36</p> <p><b>Date Analysis Commenced</b> : 18-Oct-2023</p> <p><b>Issue Date</b> : 02-Nov-2023 14:51</p>
--	---

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results
- Surrogate Control Limits

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QC Interpretive report to assist with Quality Review and Sample Receipt Notification (SRN).

## Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is conducted in accordance with US FDA 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Laboratory Department</i>
Alex Drake	Lab Analyst	Inorganics, Edmonton, Alberta
Alex Drake	Lab Analyst	Metals, Edmonton, Alberta
Brayden Ginther	Laboratory Analyst	Metals, Edmonton, Alberta
Brooke Miller	Laboratory Analyst	Inorganics, Edmonton, Alberta
Dan Nguyen	Team Leader - Inorganics	Inorganics, Edmonton, Alberta
Dan Nguyen	Team Leader - Inorganics	Metals, Edmonton, Alberta
Daniel Nguyen	Lab Assistant	Metals, Edmonton, Alberta
Elke Tabora		Inorganics, Calgary, Alberta
Fahad Husain	Analyst	Inorganics, Edmonton, Alberta
Garrett Nodin	Lab Analyst	Inorganics, Edmonton, Alberta
Jing Liu	Lab Assistant	Inorganics, Edmonton, Alberta
Kari Mulroy	Lab Supervisor - Environmental	Organics, Edmonton, Alberta
Kevin Baxter	Team Leader - Inorganics	Inorganics, Calgary, Alberta
Logan Carroll	Laboratory Analyst	Inorganics, Edmonton, Alberta
Michelle Schroder	Laboratory Analyst	Inorganics, Edmonton, Alberta
Yan Zhang	Lab Analyst	Organics, Edmonton, Alberta



## General Comments

The analytical methods used by ALS are developed using internationally recognized reference methods (where available), such as those published by US EPA, APHA Standard Methods, ASTM, ISO, Environment Canada, BC MOE, and Ontario MOE. Refer to the ALS Quality Control Interpretive report (QCI) for applicable references and methodology summaries. Reference methods may incorporate modifications to improve performance.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

Please refer to Quality Control Interpretive report (QCI) for information regarding Holding Time compliance.

Key : CAS Number: Chemical Abstracts Services number is a unique identifier assigned to discrete substances  
LOR: Limit of Reporting (detection limit).

<i>Unit</i>	<i>Description</i>
-	no units
%	percent
µg/L	micrograms per litre
µS/cm	microsiemens per centimetre
meq/L	milliequivalents per litre
mg/L	milligrams per litre
pH units	pH units

<: less than.

>: greater than.

Surrogate: An analyte that is similar in behavior to target analyte(s), but that does not occur naturally in environmental samples. For applicable tests, surrogates are added to samples prior to analysis as a check on recovery.

Test results reported relate only to the samples as received by the laboratory.

UNLESS OTHERWISE STATED on SRN or QCI Report, ALL SAMPLES WERE RECEIVED IN ACCEPTABLE CONDITION.

## Qualifiers

<i>Qualifier</i>	<i>Description</i>
DLDS	Detection Limit Raised: Dilution required due to high Dissolved Solids / Electrical Conductivity.
DLM	Detection Limit Adjusted due to sample matrix effects (e.g. chemical interference, colour, turbidity).
RRV	Reported result verified by repeat analysis.



## Analytical Results

Sub-Matrix: Water					Client sample ID	1Booth D.1	2 Ewert D.1	3 Ewert D.2	4 Ewert D.3	5 Ewert D.4
(Matrix: Water)					Client sampling date / time	16-Oct-2023 17:45	16-Oct-2023 16:20	16-Oct-2023 16:45	16-Oct-2023 16:00	16-Oct-2023 17:00
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-001	EO2309502-002	EO2309502-003	EO2309502-004	EO2309502-005	
					Result	Result	Result	Result	Result	
<b>Physical Tests</b>										
Hardness (as CaCO <sub>3</sub> ), dissolved	----	EC100/EO	0.50	mg/L	98.4	118	103	105	109	
Solids, total dissolved [TDS]	----	E162/EO	10	mg/L	460	824	566	419	388	
Solids, total suspended [TSS]	----	E160/EO	3.0	mg/L	29.0	91.4	152	80.0	38.8	
Conductivity	----	E100/CG	2.0	µS/cm	689	1180	804	575	589	
pH	----	E108/CG	0.10	pH units	8.46	9.45	8.23	8.38	8.47	
Alkalinity, bicarbonate (as HCO <sub>3</sub> )	71-52-3	E290/CG	1.0	mg/L	350	501	385	308	339	
Alkalinity, carbonate (as CO <sub>3</sub> )	3812-32-6	E290/CG	1.0	mg/L	5.3	90.4	<1.0	3.0	5.4	
Alkalinity, hydroxide (as OH)	14280-30-9	E290/CG	1.0	mg/L	<1.0	<1.0	<1.0	<1.0	<1.0	
Alkalinity, total (as CaCO <sub>3</sub> )	----	E290/CG	2.0	mg/L	295	561	316	257	287	
Solids, total dissolved [TDS], calculated	----	EC103/EO	1.0	mg/L	483	849	577	430	414	
<b>Anions and Nutrients</b>										
Ammonia, total (as N)	7664-41-7	E298/EO	0.0050	mg/L	0.128	0.0547	0.341	0.168	0.143	
Kjeldahl nitrogen, total [TKN]	----	E318/EO	0.050	mg/L	4.36	4.40	7.96	4.55	3.50	
Phosphorus, total	7723-14-0	E372-S/EO	0.0010	mg/L	0.607	0.980	1.69	1.60	0.988	
Chloride	16887-00-6	E235.Cl/EO	0.50	mg/L	35.0	55.8	32.6	49.0	10.6	
Fluoride	16984-48-8	E235.F/EO	0.020	mg/L	0.283	0.492	0.324	0.262	0.403	
Nitrate (as N)	14797-55-8	E235.NO <sub>3</sub> /EO	0.020	mg/L	<0.020	<0.020	0.392	<0.020	<0.020	
Nitrite (as N)	14797-65-0	E235.NO <sub>2</sub> /EO	0.010	mg/L	<0.010	<0.010	0.084	<0.010	<0.010	
Sulfate (as SO <sub>4</sub> )	14808-79-8	E235.SO <sub>4</sub> /EO	0.30	mg/L	51.6	84.2	108	7.13	46.0	
Nitrate + Nitrite (as N)	----	EC235.N+N/E O	0.0500	mg/L	<0.0500	<0.0500	0.476	<0.0500	<0.0500	
<b>Organic / Inorganic Carbon</b>										
Carbon, dissolved organic [DOC]	----	E358-L/CG	0.50	mg/L	29.8	41.3	36.4	47.2	28.3	
<b>Ion Balance</b>										
Anion sum	----	EC101/EO	0.10	meq/L	7.97	14.6	9.53	6.68	7.01	
Cation sum	----	EC101/EO	0.10	meq/L	8.41	14.7	9.25	6.94	6.99	
Ion balance (APHA)	----	EC101/EO	0.01	%	2.69	0.34	-1.49	1.91	-0.14	
Ion balance (cations/anions)	----	EC101/EO	0.010	%	106	101	97.1	104	99.7	
<b>Dissolved Metals</b>										



## Analytical Results

Sub-Matrix: Water					Client sample ID	1Booth D.1	2 Ewert D.1	3 Ewert D.2	4 Ewert D.3	5 Ewert D.4
(Matrix: Water)					Client sampling date / time	16-Oct-2023 17:45	16-Oct-2023 16:20	16-Oct-2023 16:45	16-Oct-2023 16:00	16-Oct-2023 17:00
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-001	EO2309502-002	EO2309502-003	EO2309502-004	EO2309502-005	
					Result	Result	Result	Result	Result	
<b>Dissolved Metals</b>										
Aluminum, dissolved	7429-90-5	E421/EO	0.0010	mg/L	0.0027	0.0062	0.0036	0.0071	0.0025	
Antimony, dissolved	7440-36-0	E421/EO	0.00010	mg/L	0.00023	0.00042	0.00022	0.00018	0.00024	
Arsenic, dissolved	7440-38-2	E421/EO	0.00010	mg/L	0.00647	0.0128	0.00503	0.00447	0.00595	
Barium, dissolved	7440-39-3	E421/EO	0.00010	mg/L	0.0503	0.0501	0.0230	0.0247	0.0338	
Beryllium, dissolved	7440-41-7	E421/EO	0.000020	mg/L	<0.000020	<0.000020	<0.000020	<0.000020	<0.000020	
Bismuth, dissolved	7440-69-9	E421/EO	0.000050	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	
Boron, dissolved	7440-42-8	E421/EO	0.010	mg/L	0.048	0.022	0.033	0.038	0.029	
Cadmium, dissolved	7440-43-9	E421/EO	0.0000050	mg/L	0.0000052	<0.0000050	0.0000061	0.0000071	<0.0000050	
Calcium, dissolved	7440-70-2	E421/EO	0.050	mg/L	22.6	24.0	23.4	25.5	24.4	
Cesium, dissolved	7440-46-2	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010	
Chromium, dissolved	7440-47-3	E421/EO	0.00050	mg/L	<0.00050	0.00054	<0.00050	<0.00050	<0.00050	
Cobalt, dissolved	7440-48-4	E421/EO	0.00010	mg/L	0.00035	0.00049	0.00077	0.00059	0.00049	
Copper, dissolved	7440-50-8	E421/EO	0.00020	mg/L	0.00054	0.00113	0.00168	0.00159	0.00055	
Iron, dissolved	7439-89-6	E421/EO	0.010	mg/L	0.142	0.038	0.186	0.544	0.160	
Lead, dissolved	7439-92-1	E421/EO	0.000050	mg/L	0.000098	0.000078	0.000229	0.000081	0.000067	
Lithium, dissolved	7439-93-2	E421/EO	0.0010	mg/L	0.0384	0.0377	0.0238	0.0130	0.0146	
Magnesium, dissolved	7439-95-4	E421/EO	0.0050	mg/L	10.2	14.2	10.8	10.1	11.6	
Manganese, dissolved	7439-96-5	E421/EO	0.00010	mg/L	0.00556	0.0259	0.0429	0.0634	0.0127	
Mercury, dissolved	7439-97-6	E509/EO	0.0000050	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050	
Molybdenum, dissolved	7439-98-7	E421/EO	0.000050	mg/L	0.00106	0.00131	0.000870	0.00104	0.00108	
Nickel, dissolved	7440-02-0	E421/EO	0.00050	mg/L	0.00384	0.00320	0.00485	0.00332	0.00348	
Phosphorus, dissolved	7723-14-0	E421/EO	0.050	mg/L	0.344	0.657	0.332	0.716	0.429	
Potassium, dissolved	7440-09-7	E421/EO	0.050	mg/L	13.2	21.0	16.4	16.1	14.4	
Rubidium, dissolved	7440-17-7	E421/EO	0.00020	mg/L	0.00131	0.00097	0.00175	0.00154	0.00174	
Selenium, dissolved	7782-49-2	E421/EO	0.000050	mg/L	0.000132	0.000350	0.000254	0.000262	0.000256	
Silicon, dissolved	7440-21-3	E421/EO	0.050	mg/L	1.01	<0.050	0.541	7.09	1.26	
Silver, dissolved	7440-22-4	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010	
Sodium, dissolved	7440-23-5	E421/EO	0.050	mg/L	140	271	155	101	102	
Strontium, dissolved	7440-24-6	E421/EO	0.00020	mg/L	0.243	0.252	0.246	0.200	0.218	
Sulfur, dissolved	7704-34-9	E421/EO	0.50	mg/L	21.0	32.2	38.5	4.22	17.6	





## Analytical Results

Sub-Matrix: Water					Client sample ID	1Booth D.1	2 Ewert D.1	3 Ewert D.2	4 Ewert D.3	5 Ewert D.4
(Matrix: Water)					Client sampling date / time	16-Oct-2023 17:45	16-Oct-2023 16:20	16-Oct-2023 16:45	16-Oct-2023 16:00	16-Oct-2023 17:00
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-001	EO2309502-002	EO2309502-003	EO2309502-004	EO2309502-005	
					Result	Result	Result	Result	Result	
<b>Dissolved Metals</b>										
Tellurium, dissolved	13494-80-9	E421/EO	0.00020	mg/L	<0.00020	<0.00020	<0.00020	<0.00020	<0.00020	
Thallium, dissolved	7440-28-0	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010	
Thorium, dissolved	7440-29-1	E421/EO	0.00010	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Tin, dissolved	7440-31-5	E421/EO	0.00010	mg/L	0.00030	<0.00010	0.00015	0.00011	<0.00010	
Titanium, dissolved	7440-32-6	E421/EO	0.00030	mg/L	0.00065	0.00040	0.00042	0.00065	<0.00030	
Tungsten, dissolved	7440-33-7	E421/EO	0.00010	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Uranium, dissolved	7440-61-1	E421/EO	0.000010	mg/L	0.000525	0.00192	0.000728	0.000174	0.000551	
Vanadium, dissolved	7440-62-2	E421/EO	0.00050	mg/L	0.00120	0.00280	0.00172	0.00161	0.00146	
Zinc, dissolved	7440-66-6	E421/EO	0.0010	mg/L	<0.0010	0.0028	0.0016	0.0033	0.0015	
Zirconium, dissolved	7440-67-7	E421/EO	0.00020	mg/L	0.00066	0.00065	0.00063	0.00084	0.00034	
Dissolved mercury filtration location	----	EP509/EO	-	-	Field	Field	Field	Field	Field	
Dissolved metals filtration location	----	EP421/EO	-	-	Field	Field	Field	Field	Field	
<b>Aggregate Organics</b>										
Chemical oxygen demand [COD]	----	E559-L/EO	10	mg/L	127 <sup>RRV</sup>	144	226	166	109	
Phenols, total (4AAP)	----	E562/EO	0.0010	mg/L	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
<b>Volatile Organic Compounds</b>										
Benzene	71-43-2	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	100-41-4	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Styrene	100-42-5	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	108-88-3	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Xylene, m+p-	179601-23-1	E611A/EO	0.00040	mg/L	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	
Xylene, o-	95-47-6	E611A/EO	0.00030	mg/L	<0.00030	<0.00030	<0.00030	<0.00030	<0.00030	
Xylenes, total	1330-20-7	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
<b>Hydrocarbons</b>										
F1 (C6-C10)	----	E581.F1/EO	0.10	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 (C10-C16)	----	E601/EO	0.10	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10	
F1-BTEX	----	EC580/EO	0.100	mg/L	<0.100	<0.100	<0.100	<0.100	<0.100	
<b>Hydrocarbons Surrogates</b>										
Bromobenzotrifluoride, 2- (F2-F4 surrogate)	392-83-6	E601/EO	1.0	%	105	102	99.2	98.9	102	
Dichlorotoluene, 3,4-	95-75-0	E581.F1/EO	1.0	%	85.5	81.2	81.2	71.1	71.9	



## Analytical Results

Sub-Matrix: Water

(Matrix: Water)

					Client sample ID	1Booth D.1	2 Ewert D.1	3 Ewert D.2	4 Ewert D.3	5 Ewert D.4
					Client sampling date / time	16-Oct-2023 17:45	16-Oct-2023 16:20	16-Oct-2023 16:45	16-Oct-2023 16:00	16-Oct-2023 17:00
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-001	EO2309502-002	EO2309502-003	EO2309502-004	EO2309502-005	
					Result	Result	Result	Result	Result	
<b>Volatile Organic Compounds Surrogates</b>										
Bromofluorobenzene, 4-	460-00-4	E611A/EO	1.0	%	77.3	80.7	77.6	81.4	82.0	
Difluorobenzene, 1,4-	540-36-3	E611A/EO	1.0	%	101	100	101	102	98.7	

Please refer to the General Comments section for an explanation of any result qualifiers detected.

Please refer to the Accreditation section for an explanation of analyte accreditations.



## Analytical Results

Sub-Matrix: Water (Matrix: Water)					Client sample ID	10 Magneson D.1	11 Magneson D.2	13 Magneson D.4	14 Magneson D.5	15 Magneson D.6
Client sampling date / time					16-Oct-2023 12:30	16-Oct-2023 13:30	16-Oct-2023 11:00	16-Oct-2023 13:00	16-Oct-2023 11:50	
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-006	EO2309502-007	EO2309502-008	EO2309502-009	EO2309502-010	
					Result	Result	Result	Result	Result	
<b>Physical Tests</b>										
Hardness (as CaCO3), dissolved	---	EC100/EO	0.50	mg/L	405	92.2	364	179	292	
Solids, total dissolved [TDS]	---	E162/EO	10	mg/L	2620	428	3140	1170	1630	
Solids, total suspended [TSS]	---	E160/EO	3.0	mg/L	192	86.4	48.7	74.6	62.4	
Conductivity	---	E100/CG	2.0	µS/cm	2890	500	3380	1560	2190	
pH	---	E108/CG	0.10	pH units	8.64	8.38	8.51	8.84	8.43	
Alkalinity, bicarbonate (as HCO3)	71-52-3	E290/CG	1.0	mg/L	1040	293	1240	705	349	
Alkalinity, carbonate (as CO3)	3812-32-6	E290/CG	1.0	mg/L	39.6	2.9	24.7	36.5	5.8	
Alkalinity, hydroxide (as OH)	14280-30-9	E290/CG	1.0	mg/L	<1.0	<1.0	<1.0	<1.0	<1.0	
Alkalinity, total (as CaCO3)	---	E290/CG	2.0	mg/L	923	245	1060	639	296	
Solids, total dissolved [TDS], calculated	---	EC103/EO	1.0	mg/L	2400	383	2800	1180	1630	
<b>Anions and Nutrients</b>										
Ammonia, total (as N)	7664-41-7	E298/EO	0.0050	mg/L	6.33	0.902	3.38	0.198	0.0361	
Kjeldahl nitrogen, total [TKN]	---	E318/EO	0.050	mg/L	23.7	6.35	41.0	4.93	2.95	
Phosphorus, total	7723-14-0	E372-S/EO	0.0010	mg/L	12.4	2.72	20.3	3.88	0.335	
Chloride	16887-00-6	E235.Cl/EO	0.50	mg/L	323 <sup>DLDS</sup>	20.9	461 <sup>DLDS</sup>	114	189 <sup>DLDS</sup>	
Fluoride	16984-48-8	E235.F/EO	0.020	mg/L	<0.100 <sup>DLDS</sup>	0.361	<0.100 <sup>DLDS</sup>	0.685	0.278 <sup>DLDS</sup>	
Nitrate (as N)	14797-55-8	E235.NO3/EO	0.020	mg/L	<0.100 <sup>DLDS</sup>	0.503	0.102 <sup>DLDS</sup>	0.243	<0.100 <sup>DLDS</sup>	
Nitrite (as N)	14797-65-0	E235.NO2/EO	0.010	mg/L	0.235 <sup>DLDS</sup>	0.065	1.90 <sup>DLDS</sup>	0.011	<0.050 <sup>DLDS</sup>	
Sulfate (as SO4)	14808-79-8	E235.SO4/EO	0.30	mg/L	388 <sup>DLDS</sup>	4.18	213 <sup>DLDS</sup>	168	686 <sup>DLDS</sup>	
Nitrate + Nitrite (as N)	---	EC235.N+N/E O	0.0500	mg/L	0.235	0.568	2.00	0.254	<0.112	
<b>Organic / Inorganic Carbon</b>										
Carbon, dissolved organic [DOC]	---	E358-L/CG	0.50	mg/L	204	50.9	326	68.3	29.7	
<b>Ion Balance</b>										
Anion sum	---	EC101/EO	0.10	meq/L	35.6	5.63	38.8	19.5	25.5	
Cation sum	---	EC101/EO	0.10	meq/L	37.8	6.09	40.9	18.6	25.4	
Ion balance (APHA)	---	EC101/EO	0.01	%	3.00	3.92	2.63	-2.36	-0.20	
Ion balance (cations/anions)	---	EC101/EO	0.010	%	106	108	105	95.4	99.6	
<b>Dissolved Metals</b>										
Aluminum, dissolved	7429-90-5	E421/EO	0.0010	mg/L	0.0166	0.356	0.0529	0.0041	0.0035	



## Analytical Results

Sub-Matrix: Water (Matrix: Water)					Client sample ID	10 Magneson D.1	11 Magneson D.2	13 Magneson D.4	14 Magneson D.5	15 Magneson D.6
Client sampling date / time					16-Oct-2023 12:30	16-Oct-2023 13:30	16-Oct-2023 11:00	16-Oct-2023 13:00	16-Oct-2023 11:50	
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-006	EO2309502-007	EO2309502-008	EO2309502-009	EO2309502-010	
					Result	Result	Result	Result	Result	
<b>Dissolved Metals</b>										
Antimony, dissolved	7440-36-0	E421/EO	0.00010	mg/L	0.00062	0.00023	0.00070	0.00058	0.00059	
Arsenic, dissolved	7440-38-2	E421/EO	0.00010	mg/L	0.0249	0.00833	0.0311	0.0232	0.00977	
Barium, dissolved	7440-39-3	E421/EO	0.00010	mg/L	0.0254	0.0858	0.132	0.0185	0.0237	
Beryllium, dissolved	7440-41-7	E421/EO	0.000020	mg/L	<0.000040 DLDS	0.000065	0.000113	<0.000020	<0.000040 DLDS	
Bismuth, dissolved	7440-69-9	E421/EO	0.000050	mg/L	<0.000100 DLDS	<0.000050	<0.000100 DLDS	<0.000050	<0.000100 DLDS	
Boron, dissolved	7440-42-8	E421/EO	0.010	mg/L	0.166	0.050	0.210	0.071	0.082	
Cadmium, dissolved	7440-43-9	E421/EO	0.0000050	mg/L	0.0000371	0.0000334	0.0000700	0.0000084	<0.0000100 DLDS	
Calcium, dissolved	7440-70-2	E421/EO	0.050	mg/L	81.3	22.1	67.4	40.6	54.7	
Cesium, dissolved	7440-46-2	E421/EO	0.000010	mg/L	<0.000020 DLDS	0.000020	<0.000020 DLDS	<0.000010	<0.000020 DLDS	
Chromium, dissolved	7440-47-3	E421/EO	0.00050	mg/L	<0.00100 DLDS	0.00069	0.00337	<0.00050	<0.00100 DLDS	
Cobalt, dissolved	7440-48-4	E421/EO	0.00010	mg/L	0.00519	0.00198	0.0123	0.00362	0.00044	
Copper, dissolved	7440-50-8	E421/EO	0.00020	mg/L	0.00543	0.00294	0.00846	0.00334	0.00207	
Iron, dissolved	7439-89-6	E421/EO	0.010	mg/L	0.741	3.95	2.76	0.044	0.065	
Lead, dissolved	7439-92-1	E421/EO	0.000050	mg/L	0.000583	0.00204	0.00268	<0.000050	0.000101	
Lithium, dissolved	7439-93-2	E421/EO	0.0010	mg/L	0.0712	0.0115	0.109	0.0491	0.0852	
Magnesium, dissolved	7439-95-4	E421/EO	0.0050	mg/L	49.1	8.98	47.6	18.9	37.7	
Manganese, dissolved	7439-96-5	E421/EO	0.00010	mg/L	0.300	0.0885	0.643	0.0996	0.0442	
Mercury, dissolved	7439-97-6	E509/EO	0.0000050	mg/L	0.0000059	<0.0000050	0.0000132	<0.0000050	<0.0000050	
Molybdenum, dissolved	7439-98-7	E421/EO	0.000050	mg/L	0.00278	0.00272	0.00388	0.0106	0.00140	
Nickel, dissolved	7440-02-0	E421/EO	0.00050	mg/L	0.0186	0.00893	0.0522	0.0180	0.00514	
Phosphorus, dissolved	7723-14-0	E421/EO	0.050	mg/L	6.73	1.60	17.4	3.28	0.127	
Potassium, dissolved	7440-09-7	E421/EO	0.050	mg/L	203	28.6	586	69.6	20.6	
Rubidium, dissolved	7440-17-7	E421/EO	0.00020	mg/L	0.0200	0.00219	0.0804	0.00419	0.00249	
Selenium, dissolved	7782-49-2	E421/EO	0.000050	mg/L	0.000830	0.000392	0.00209	0.000752	0.000334	
Silicon, dissolved	7440-21-3	E421/EO	0.050	mg/L	13.6	6.31	11.8	3.27	0.487	
Silver, dissolved	7440-22-4	E421/EO	0.000010	mg/L	<0.000020 DLDS	0.000013	0.000050	<0.000010	<0.000020 DLDS	
Sodium, dissolved	7440-23-5	E421/EO	0.050	mg/L	553	75.1	420	305	437	
Strontium, dissolved	7440-24-6	E421/EO	0.00020	mg/L	0.527	0.145	0.572	0.402	0.690	
Sulfur, dissolved	7704-34-9	E421/EO	0.50	mg/L	158	3.02	88.2	62.2	258	
Tellurium, dissolved	13494-80-9	E421/EO	0.00020	mg/L	<0.00040 DLDS	<0.00020	<0.00040 DLDS	<0.00020	<0.00040 DLDS	



## Analytical Results

Sub-Matrix: Water (Matrix: Water)					Client sample ID	10 Magneson D.1	11 Magneson D.2	13 Magneson D.4	14 Magneson D.5	15 Magneson D.6
Client sampling date / time					16-Oct-2023 12:30	16-Oct-2023 13:30	16-Oct-2023 11:00	16-Oct-2023 13:00	16-Oct-2023 11:50	
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-006	EO2309502-007	EO2309502-008	EO2309502-009	EO2309502-010	
					Result	Result	Result	Result	Result	
<b>Dissolved Metals</b>										
Thallium, dissolved	7440-28-0	E421/EO	0.000010	mg/L	<0.000020 <sup>DLDS</sup>	<0.000010	<0.000020 <sup>DLDS</sup>	<0.000010	<0.000020 <sup>DLDS</sup>	
Thorium, dissolved	7440-29-1	E421/EO	0.00010	mg/L	<0.00020 <sup>DLDS</sup>	0.00016	0.00091	<0.00010	<0.00020 <sup>DLDS</sup>	
Tin, dissolved	7440-31-5	E421/EO	0.00010	mg/L	0.00029	0.00029	0.0103	0.00013	<0.00020 <sup>DLDS</sup>	
Titanium, dissolved	7440-32-6	E421/EO	0.00030	mg/L	0.00434	0.0116	0.0396	0.00055	<0.00060 <sup>DLDS</sup>	
Tungsten, dissolved	7440-33-7	E421/EO	0.00010	mg/L	<0.00020 <sup>DLDS</sup>	<0.00010	<0.00020 <sup>DLDS</sup>	0.00047	<0.00020 <sup>DLDS</sup>	
Uranium, dissolved	7440-61-1	E421/EO	0.000010	mg/L	0.00436	0.00158	0.00263	0.00268	0.00251	
Vanadium, dissolved	7440-62-2	E421/EO	0.00050	mg/L	0.0161	0.00754	0.0315	0.0149	0.00156	
Zinc, dissolved	7440-66-6	E421/EO	0.0010	mg/L	0.0028	0.0066	0.0221	<0.0010	0.0034	
Zirconium, dissolved	7440-67-7	E421/EO	0.00020	mg/L	0.00623	0.00241	0.0262	0.00218	0.00068	
Dissolved mercury filtration location	----	EP509/EO	-	-	Field	Field	Field	Field	Field	
Dissolved metals filtration location	----	EP421/EO	-	-	Field	Field	Field	Field	Field	
<b>Aggregate Organics</b>										
Chemical oxygen demand [COD]	----	E559-L/EO	10	mg/L	578	192 <sup>RRV</sup>	1180 <sup>DLM</sup>	202	89	
Phenols, total (4AAP)	----	E562/EO	0.0010	mg/L	0.0014	<0.0010	<0.0020 <sup>DLM</sup>	<0.0010	<0.0010	
<b>Volatile Organic Compounds</b>										
Benzene	71-43-2	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	100-41-4	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Styrene	100-42-5	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	108-88-3	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Xylene, m+p-	179601-23-1	E611A/EO	0.00040	mg/L	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	
Xylene, o-	95-47-6	E611A/EO	0.00030	mg/L	<0.00030	<0.00030	<0.00030	<0.00030	<0.00030	
Xylenes, total	1330-20-7	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
<b>Hydrocarbons</b>										
F1 (C6-C10)	----	E581.F1/EO	0.10	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 (C10-C16)	----	E601/EO	0.10	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10	
F1-BTEX	----	EC580/EO	0.100	mg/L	<0.100	<0.100	<0.100	<0.100	<0.100	
<b>Hydrocarbons Surrogates</b>										
Bromobenzotrifluoride, 2- (F2-F4 surrogate)	392-83-6	E601/EO	1.0	%	100	102	97.2	95.6	102	
Dichlorotoluene, 3,4-	95-75-0	E581.F1/EO	1.0	%	73.4	85.6	75.5	76.9	72.8	
<b>Volatile Organic Compounds Surrogates</b>										



## Analytical Results

Sub-Matrix: Water (Matrix: Water)					Client sample ID	10 Magneson D.1	11 Magneson D.2	13 Magneson D.4	14 Magneson D.5	15 Magneson D.6
					Client sampling date / time	16-Oct-2023 12:30	16-Oct-2023 13:30	16-Oct-2023 11:00	16-Oct-2023 13:00	16-Oct-2023 11:50
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-006	EO2309502-007	EO2309502-008	EO2309502-009	EO2309502-010	
					Result	Result	Result	Result	Result	
<b>Volatile Organic Compounds Surrogates</b>										
Bromofluorobenzene, 4-	460-00-4	E611A/EO	1.0	%	79.9	79.1	81.0	75.6	79.7	
Difluorobenzene, 1,4-	540-36-3	E611A/EO	1.0	%	100	97.8	98.5	100	99.8	

Please refer to the General Comments section for an explanation of any result qualifiers detected.

Please refer to the Accreditation section for an explanation of analyte accreditations.



## Analytical Results

Sub-Matrix: Water					Client sample ID				
(Matrix: Water)					16 Beaver County D.1	19 Winsnes D.1	20 Balash D.1	21 Balash D.2	22 Balash D.3
Client sampling date / time					16-Oct-2023 15:30	16-Oct-2023 18:15	16-Oct-2023 15:00	16-Oct-2023 14:15	16-Oct-2023 14:30
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-011	EO2309502-012	EO2309502-013	EO2309502-014	EO2309502-015
					Result	Result	Result	Result	Result
<b>Physical Tests</b>									
Hardness (as CaCO3), dissolved	----	EC100/EO	0.50	mg/L	235	148	109	399	380
Solids, total dissolved [TDS]	----	E162/EO	10	mg/L	848	582	266	1130	1350
Solids, total suspended [TSS]	----	E160/EO	3.0	mg/L	113	502	52.6	31.4	49.2
Conductivity	----	E100/CG	2.0	µS/cm	1280	872	388	1910	2250
pH	----	E108/CG	0.10	pH units	8.38	8.36	8.13	8.67	8.38
Alkalinity, bicarbonate (as HCO3)	71-52-3	E290/CG	1.0	mg/L	426	312	190	338	337
Alkalinity, carbonate (as CO3)	3812-32-6	E290/CG	1.0	mg/L	3.8	2.9	<1.0	20.2	6.7
Alkalinity, hydroxide (as OH)	14280-30-9	E290/CG	1.0	mg/L	<1.0	<1.0	<1.0	<1.0	<1.0
Alkalinity, total (as CaCO3)	----	E290/CG	2.0	mg/L	355	261	156	310	288
Solids, total dissolved [TDS], calculated	----	EC103/EO	1.0	mg/L	883	594	276	1170	1340
<b>Anions and Nutrients</b>									
Ammonia, total (as N)	7664-41-7	E298/EO	0.0050	mg/L	0.0495	0.152	0.0330	0.0363	0.0814
Kjeldahl nitrogen, total [TKN]	----	E318/EO	0.050	mg/L	3.54	2.04	3.21	2.78	3.74
Phosphorus, total	7723-14-0	E372-S/EO	0.0010	mg/L	1.98	0.770	0.482	0.658	1.58
Chloride	16887-00-6	E235.Cl/EO	0.50	mg/L	180	75.8	25.5	256	384
Fluoride	16984-48-8	E235.F/EO	0.020	mg/L	0.246	0.270	0.179	0.185	0.133
Nitrate (as N)	14797-55-8	E235.NO3/EO	0.020	mg/L	<0.020	<0.020	<0.020	<0.020	<0.020
Nitrite (as N)	14797-65-0	E235.NO2/EO	0.010	mg/L	<0.010	<0.010	<0.010	<0.010	<0.010
Sulfate (as SO4)	14808-79-8	E235.SO4/EO	0.30	mg/L	140	131	21.2	284	262
Nitrate + Nitrite (as N)	----	EC235.N+N/E O	0.0500	mg/L	<0.0500	<0.0500	<0.0500	<0.0500	<0.0500
<b>Organic / Inorganic Carbon</b>									
Carbon, dissolved organic [DOC]	----	E358-L/CG	0.50	mg/L	33.2	26.7	23.3	27.2	41.4
<b>Ion Balance</b>									
Anion sum	----	EC101/EO	0.10	meq/L	15.1	10.1	4.29	19.3	22.0
Cation sum	----	EC101/EO	0.10	meq/L	14.6	9.50	4.42	19.6	22.3
Ion balance (APHA)	----	EC101/EO	0.01	%	-1.68	-3.06	1.49	0.77	0.68
Ion balance (cations/anions)	----	EC101/EO	0.010	%	96.7	94.0	103	102	101
<b>Dissolved Metals</b>									
Aluminum, dissolved	7429-90-5	E421/EO	0.0010	mg/L	0.0022	0.0038	0.0028	0.0014	0.0037



## Analytical Results

Sub-Matrix: Water					Client sample ID	16 Beaver County D.1	19 Winsnes D.1	20 Balash D.1	21 Balash D.2	22 Balash D.3
(Matrix: Water)					Client sampling date / time	16-Oct-2023 15:30	16-Oct-2023 18:15	16-Oct-2023 15:00	16-Oct-2023 14:15	16-Oct-2023 14:30
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-011	EO2309502-012	EO2309502-013	EO2309502-014	EO2309502-015	
					Result	Result	Result	Result	Result	
<b>Dissolved Metals</b>										
Antimony, dissolved	7440-36-0	E421/EO	0.00010	mg/L	0.00022	0.00023	0.00011	0.00018	<0.00020	DLDS
Arsenic, dissolved	7440-38-2	E421/EO	0.00010	mg/L	0.00557	0.00438	0.00267	0.00549	0.00588	
Barium, dissolved	7440-39-3	E421/EO	0.00010	mg/L	0.0220	0.0644	0.0529	0.0733	0.0487	
Beryllium, dissolved	7440-41-7	E421/EO	0.000020	mg/L	<0.000020	<0.000020	<0.000020	<0.000020	<0.000040	DLDS
Bismuth, dissolved	7440-69-9	E421/EO	0.000050	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	<0.000100	DLDS
Boron, dissolved	7440-42-8	E421/EO	0.010	mg/L	0.050	0.037	0.038	0.022	0.024	
Cadmium, dissolved	7440-43-9	E421/EO	0.0000050	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000100	DLDS
Calcium, dissolved	7440-70-2	E421/EO	0.050	mg/L	56.6	28.0	27.8	76.7	68.3	
Cesium, dissolved	7440-46-2	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000020	DLDS
Chromium, dissolved	7440-47-3	E421/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00100	DLDS
Cobalt, dissolved	7440-48-4	E421/EO	0.00010	mg/L	0.00072	0.00037	0.00037	0.00053	0.00047	
Copper, dissolved	7440-50-8	E421/EO	0.00020	mg/L	0.00049	0.00027	0.00052	0.00056	0.00058	
Iron, dissolved	7439-89-6	E421/EO	0.010	mg/L	0.087	0.048	0.202	0.010	0.086	
Lead, dissolved	7439-92-1	E421/EO	0.000050	mg/L	0.000052	<0.000050	0.000058	<0.000050	<0.000100	DLDS
Lithium, dissolved	7439-93-2	E421/EO	0.0010	mg/L	0.0278	0.0200	0.0134	0.0487	0.0238	
Magnesium, dissolved	7439-95-4	E421/EO	0.0050	mg/L	22.7	18.9	9.62	50.5	50.8	
Manganese, dissolved	7439-96-5	E421/EO	0.00010	mg/L	0.229	0.0994	0.105	0.00433	0.0770	
Mercury, dissolved	7439-97-6	E509/EO	0.0000050	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050	
Molybdenum, dissolved	7439-98-7	E421/EO	0.000050	mg/L	0.00113	0.000545	0.000683	0.000679	0.000474	
Nickel, dissolved	7440-02-0	E421/EO	0.00050	mg/L	0.00387	0.00246	0.00256	0.00316	0.00199	
Phosphorus, dissolved	7723-14-0	E421/EO	0.050	mg/L	1.27	0.195	0.204	0.399	1.28	
Potassium, dissolved	7440-09-7	E421/EO	0.050	mg/L	13.0	13.8	10.9	28.1	33.8	
Rubidium, dissolved	7440-17-7	E421/EO	0.00020	mg/L	0.00152	0.00136	0.00225	0.00222	0.00397	
Selenium, dissolved	7782-49-2	E421/EO	0.000050	mg/L	0.000167	0.000195	0.000225	0.000185	0.000161	
Silicon, dissolved	7440-21-3	E421/EO	0.050	mg/L	1.84	0.195	6.77	3.05	4.00	
Silver, dissolved	7440-22-4	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000020	DLDS
Sodium, dissolved	7440-23-5	E421/EO	0.050	mg/L	219	142	44.9	250	319	
Strontium, dissolved	7440-24-6	E421/EO	0.00020	mg/L	0.460	0.354	0.171	0.640	0.517	
Sulfur, dissolved	7704-34-9	E421/EO	0.50	mg/L	52.3	44.1	8.18	107	102	
Tellurium, dissolved	13494-80-9	E421/EO	0.00020	mg/L	<0.00020	<0.00020	<0.00020	<0.00020	<0.00040	DLDS





## Analytical Results

Sub-Matrix: Water (Matrix: Water)					Client sample ID	16 Beaver County D.1	19 Winsnes D.1	20 Balash D.1	21 Balash D.2	22 Balash D.3
Client sampling date / time					16-Oct-2023 15:30	16-Oct-2023 18:15	16-Oct-2023 15:00	16-Oct-2023 14:15	16-Oct-2023 14:30	
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-011	EO2309502-012	EO2309502-013	EO2309502-014	EO2309502-015	
					Result	Result	Result	Result	Result	
<b>Dissolved Metals</b>										
Thallium, dissolved	7440-28-0	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000020 <sup>DLDS</sup>	
Thorium, dissolved	7440-29-1	E421/EO	0.00010	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00020 <sup>DLDS</sup>	
Tin, dissolved	7440-31-5	E421/EO	0.00010	mg/L	<0.00010	0.00024	<0.00010	0.00105	0.00182	
Titanium, dissolved	7440-32-6	E421/EO	0.00030	mg/L	<0.00030	<0.00030	0.00060	<0.00030	<0.00060 <sup>DLDS</sup>	
Tungsten, dissolved	7440-33-7	E421/EO	0.00010	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00020 <sup>DLDS</sup>	
Uranium, dissolved	7440-61-1	E421/EO	0.000010	mg/L	0.00126	0.000849	0.000122	0.00210	0.000809	
Vanadium, dissolved	7440-62-2	E421/EO	0.00050	mg/L	0.00317	0.00155	0.00096	0.00132	0.00138	
Zinc, dissolved	7440-66-6	E421/EO	0.0010	mg/L	0.0012	<0.0010	0.0017	<0.0010	<0.0020 <sup>DLDS</sup>	
Zirconium, dissolved	7440-67-7	E421/EO	0.00020	mg/L	0.00055	0.00035	0.00058	0.00022	<0.00040 <sup>DLDS</sup>	
Dissolved mercury filtration location	----	EP509/EO	-	-	Field	Field	Field	Field	Field	
Dissolved metals filtration location	----	EP421/EO	-	-	Field	Field	Field	Field	Field	
<b>Aggregate Organics</b>										
Chemical oxygen demand [COD]	----	E559-L/EO	10	mg/L	132	203	116	90 <sup>DLM</sup>	112 <sup>DLM</sup>	
Phenols, total (4AAP)	----	E562/EO	0.0010	mg/L	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
<b>Volatile Organic Compounds</b>										
Benzene	71-43-2	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	100-41-4	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Styrene	100-42-5	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	108-88-3	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Xylene, m+p-	179601-23-1	E611A/EO	0.00040	mg/L	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	
Xylene, o-	95-47-6	E611A/EO	0.00030	mg/L	<0.00030	<0.00030	<0.00030	<0.00030	<0.00030	
Xylenes, total	1330-20-7	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
<b>Hydrocarbons</b>										
F1 (C6-C10)	----	E581.F1/EO	0.10	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 (C10-C16)	----	E601/EO	0.10	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10	
F1-BTEX	----	EC580/EO	0.100	mg/L	<0.100	<0.100	<0.100	<0.100	<0.100	
<b>Hydrocarbons Surrogates</b>										
Bromobenzotrifluoride, 2- (F2-F4 surrogate)	392-83-6	E601/EO	1.0	%	95.0	99.9	95.1	107	96.2	
Dichlorotoluene, 3,4-	95-75-0	E581.F1/EO	1.0	%	76.4	81.2	91.3	93.0	95.8	
<b>Volatile Organic Compounds Surrogates</b>										



## Analytical Results

Sub-Matrix: Water (Matrix: Water)					Client sample ID	16 Beaver County D.1	19 Winsnes D.1	20 Balash D.1	21 Balash D.2	22 Balash D.3
Client sampling date / time					16-Oct-2023 15:30	16-Oct-2023 18:15	16-Oct-2023 15:00	16-Oct-2023 14:15	16-Oct-2023 14:30	
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-011	EO2309502-012	EO2309502-013	EO2309502-014	EO2309502-015	
Volatile Organic Compounds Surrogates					Result	Result	Result	Result	Result	
Bromofluorobenzene, 4-	460-00-4	E611A/EO	1.0	%	79.9	72.1	77.6	82.1	78.2	
Difluorobenzene, 1,4-	540-36-3	E611A/EO	1.0	%	99.4	103	102	101	106	

Please refer to the General Comments section for an explanation of any result qualifiers detected.

Please refer to the Accreditation section for an explanation of analyte accreditations.



## Analytical Results

Sub-Matrix: Water					Client sample ID				
(Matrix: Water)					21 D.Lyons D.1	6 B.Lyons D.1	7 B.Lyons D.2	8 B.Lyons D.3	9 B.Lyons D.4
Client sampling date / time					17-Oct-2023 12:45	17-Oct-2023 10:30	17-Oct-2023 10:45	17-Oct-2023 11:15	17-Oct-2023 11:40
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-016	EO2309502-017	EO2309502-018	EO2309502-019	EO2309502-020
					Result	Result	Result	Result	Result
<b>Physical Tests</b>									
Hardness (as CaCO3), dissolved	----	EC100/EO	0.50	mg/L	66.4	74.0	75.0	158	116
Solids, total dissolved [TDS]	----	E162/EO	10	mg/L	358	286	308	571	468
Solids, total suspended [TSS]	----	E160/EO	3.0	mg/L	24.0	17.8	25.2	176	44.0
Conductivity	----	E100/CG	2.0	µS/cm	541	419	455	896	660
pH	----	E108/CG	0.10	pH units	8.35	7.95	7.95	8.61	8.49
Alkalinity, bicarbonate (as HCO3)	71-52-3	E290/CG	1.0	mg/L	294	185	233	373	385
Alkalinity, carbonate (as CO3)	3812-32-6	E290/CG	1.0	mg/L	4.9	<1.0	<1.0	14.9	10.2
Alkalinity, hydroxide (as OH)	14280-30-9	E290/CG	1.0	mg/L	<1.0	<1.0	<1.0	<1.0	<1.0
Alkalinity, total (as CaCO3)	----	E290/CG	2.0	mg/L	250	152	191	331	332
Solids, total dissolved [TDS], calculated	----	EC103/EO	1.0	mg/L	354	276	291	567	429
<b>Anions and Nutrients</b>									
Ammonia, total (as N)	7664-41-7	E298/EO	0.0050	mg/L	0.403	0.241	0.204	0.0594	0.105
Kjeldahl nitrogen, total [TKN]	----	E318/EO	0.050	mg/L	3.43	3.74	4.45	3.15	3.90
Phosphorus, total	7723-14-0	E372-S/EO	0.0010	mg/L	0.440	1.78	1.68	0.536	1.27
Chloride	16887-00-6	E235.Cl/EO	0.50	mg/L	10.8	11.2	15.0	18.0	17.2
Fluoride	16984-48-8	E235.F/EO	0.020	mg/L	0.277	0.161	0.180	0.591	0.388
Nitrate (as N)	14797-55-8	E235.NO3/EO	0.020	mg/L	0.165	<0.020	0.024	<0.020	0.112
Nitrite (as N)	14797-65-0	E235.NO2/EO	0.010	mg/L	0.021	<0.010	<0.010	<0.010	<0.010
Sulfate (as SO4)	14808-79-8	E235.SO4/EO	0.30	mg/L	21.3	36.0	19.5	122	4.85
Nitrate + Nitrite (as N)	----	EC235.N+N/E O	0.0500	mg/L	0.186	<0.0500	<0.0500	<0.0500	0.112
<b>Organic / Inorganic Carbon</b>									
Carbon, dissolved organic [DOC]	----	E358-L/CG	0.50	mg/L	32.8	30.2	29.6	27.6	43.6
<b>Ion Balance</b>									
Anion sum	----	EC101/EO	0.10	meq/L	5.77	4.11	4.66	9.69	7.25
Cation sum	----	EC101/EO	0.10	meq/L	5.86	4.24	4.63	9.18	7.01
Ion balance (APHA)	----	EC101/EO	0.01	%	0.77	1.56	-0.32	-2.70	-1.68
Ion balance (cations/anions)	----	EC101/EO	0.010	%	102	103	99.4	94.7	96.7
<b>Dissolved Metals</b>									
Aluminum, dissolved	7429-90-5	E421/EO	0.0010	mg/L	0.137	0.0067	0.0043	0.0046	0.0467



## Analytical Results

Sub-Matrix: Water					Client sample ID				
(Matrix: Water)					21 D.Lyons D.1	6 B.Lyons D.1	7 B.Lyons D.2	8 B.Lyons D.3	9 B.Lyons D.4
Client sampling date / time					17-Oct-2023 12:45	17-Oct-2023 10:30	17-Oct-2023 10:45	17-Oct-2023 11:15	17-Oct-2023 11:40
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-016	EO2309502-017	EO2309502-018	EO2309502-019	EO2309502-020
					Result	Result	Result	Result	Result
<b>Dissolved Metals</b>									
Antimony, dissolved	7440-36-0	E421/EO	0.00010	mg/L	0.00014	0.00011	0.00012	0.00035	0.00029
Arsenic, dissolved	7440-38-2	E421/EO	0.00010	mg/L	0.00469	0.00516	0.00422	0.00360	0.00467
Barium, dissolved	7440-39-3	E421/EO	0.00010	mg/L	0.0473	0.0276	0.00746	0.0418	0.0348
Beryllium, dissolved	7440-41-7	E421/EO	0.000020	mg/L	<0.000020	<0.000020	<0.000020	<0.000020	<0.000020
Bismuth, dissolved	7440-69-9	E421/EO	0.000050	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050
Boron, dissolved	7440-42-8	E421/EO	0.010	mg/L	0.051	0.058	0.046	0.059	0.056
Cadmium, dissolved	7440-43-9	E421/EO	0.0000050	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	0.0000064
Calcium, dissolved	7440-70-2	E421/EO	0.050	mg/L	15.0	17.2	18.5	34.9	25.2
Cesium, dissolved	7440-46-2	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Chromium, dissolved	7440-47-3	E421/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Cobalt, dissolved	7440-48-4	E421/EO	0.00010	mg/L	0.00056	0.00052	0.00027	0.00134	0.00101
Copper, dissolved	7440-50-8	E421/EO	0.00020	mg/L	0.00105	0.00037	0.00038	0.00306	0.00172
Iron, dissolved	7439-89-6	E421/EO	0.010	mg/L	0.241	0.467	0.131	0.022	0.278
Lead, dissolved	7439-92-1	E421/EO	0.000050	mg/L	0.000105	0.000080	<0.000050	0.000051	0.000111
Lithium, dissolved	7439-93-2	E421/EO	0.0010	mg/L	0.0249	0.0099	0.0097	0.0160	0.0192
Magnesium, dissolved	7439-95-4	E421/EO	0.0050	mg/L	7.02	7.54	6.99	17.2	12.9
Manganese, dissolved	7439-96-5	E421/EO	0.00010	mg/L	0.0372	0.119	0.00983	0.0235	0.0273
Mercury, dissolved	7439-97-6	E509/EO	0.0000050	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum, dissolved	7439-98-7	E421/EO	0.000050	mg/L	0.000758	0.000750	0.000500	0.00625	0.00203
Nickel, dissolved	7440-02-0	E421/EO	0.00050	mg/L	0.00364	0.00274	0.00201	0.00808	0.00649
Phosphorus, dissolved	7723-14-0	E421/EO	0.050	mg/L	0.345	1.37	1.19	0.054	0.397
Potassium, dissolved	7440-09-7	E421/EO	0.050	mg/L	19.7	16.2	18.0	17.7	23.5
Rubidium, dissolved	7440-17-7	E421/EO	0.00020	mg/L	0.00183	0.00186	0.00179	0.00090	0.00109
Selenium, dissolved	7782-49-2	E421/EO	0.000050	mg/L	0.000230	0.000184	0.000155	0.000608	0.000396
Silicon, dissolved	7440-21-3	E421/EO	0.050	mg/L	1.44	4.73	2.79	0.759	2.82
Silver, dissolved	7440-22-4	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Sodium, dissolved	7440-23-5	E421/EO	0.050	mg/L	91.5	53.0	61.0	128	93.6
Strontium, dissolved	7440-24-6	E421/EO	0.00020	mg/L	0.156	0.138	0.145	0.374	0.187
Sulfur, dissolved	7704-34-9	E421/EO	0.50	mg/L	9.23	14.5	8.52	44.5	3.32
Tellurium, dissolved	13494-80-9	E421/EO	0.00020	mg/L	<0.00020	<0.00020	<0.00020	<0.00020	<0.00020



## Analytical Results

Sub-Matrix: Water					Client sample ID				
(Matrix: Water)					21 D.Lyons D.1	6 B.Lyons D.1	7 B.Lyons D.2	8 B.Lyons D.3	9 B.Lyons D.4
Client sampling date / time					17-Oct-2023 12:45	17-Oct-2023 10:30	17-Oct-2023 10:45	17-Oct-2023 11:15	17-Oct-2023 11:40
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-016	EO2309502-017	EO2309502-018	EO2309502-019	EO2309502-020
					Result	Result	Result	Result	Result
<b>Dissolved Metals</b>									
Thallium, dissolved	7440-28-0	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010
Thorium, dissolved	7440-29-1	E421/EO	0.00010	mg/L	<0.00010	<0.00010	0.00010	<0.00010	<0.00010
Tin, dissolved	7440-31-5	E421/EO	0.00010	mg/L	0.00018	<0.00010	<0.00010	<0.00010	<0.00010
Titanium, dissolved	7440-32-6	E421/EO	0.00030	mg/L	0.00634	0.00110	0.00040	<0.00030	0.00242
Tungsten, dissolved	7440-33-7	E421/EO	0.00010	mg/L	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Uranium, dissolved	7440-61-1	E421/EO	0.000010	mg/L	0.000569	0.000116	0.000138	0.00441	0.00124
Vanadium, dissolved	7440-62-2	E421/EO	0.00050	mg/L	0.00179	0.00176	0.00126	0.00183	0.00302
Zinc, dissolved	7440-66-6	E421/EO	0.0010	mg/L	0.0036	<0.0010	0.0031	<0.0010	0.0010
Zirconium, dissolved	7440-67-7	E421/EO	0.00020	mg/L	0.00069	0.00064	0.00038	0.00074	0.00092
Dissolved mercury filtration location	----	EP509/EO	-	-	Field	Field	Field	Field	Field
Dissolved metals filtration location	----	EP421/EO	-	-	Field	Field	Field	Field	Field
<b>Aggregate Organics</b>									
Chemical oxygen demand [COD]	----	E559-L/EO	10	mg/L	101	84	90	113	111
Phenols, total (4AAP)	----	E562/EO	0.0010	mg/L	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010
<b>Volatile Organic Compounds</b>									
Benzene	71-43-2	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	100-41-4	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Styrene	100-42-5	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	108-88-3	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylene, m+p-	179601-23-1	E611A/EO	0.00040	mg/L	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040
Xylene, o-	95-47-6	E611A/EO	0.00030	mg/L	<0.00030	<0.00030	<0.00030	<0.00030	<0.00030
Xylenes, total	1330-20-7	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
<b>Hydrocarbons</b>									
F1 (C6-C10)	----	E581.F1/EO	0.10	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
F2 (C10-C16)	----	E601/EO	0.10	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
F1-BTEX	----	EC580/EO	0.100	mg/L	<0.100	<0.100	<0.100	<0.100	<0.100
<b>Hydrocarbons Surrogates</b>									
Bromobenzotrifluoride, 2- (F2-F4 surrogate)	392-83-6	E601/EO	1.0	%	96.4	96.8	97.2	97.1	98.6
Dichlorotoluene, 3,4-	95-75-0	E581.F1/EO	1.0	%	79.5	81.9	70.6	83.6	82.6
<b>Volatile Organic Compounds Surrogates</b>									



## Analytical Results

Sub-Matrix: Water					Client sample ID	21 D.Lyons D.1	6 B.Lyons D.1	7 B.Lyons D.2	8 B.Lyons D.3	9 B.Lyons D.4
(Matrix: Water)					Client sampling date / time	17-Oct-2023 12:45	17-Oct-2023 10:30	17-Oct-2023 10:45	17-Oct-2023 11:15	17-Oct-2023 11:40
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-016	EO2309502-017	EO2309502-018	EO2309502-019	EO2309502-020	
Volatile Organic Compounds Surrogates					Result	Result	Result	Result	Result	
Bromofluorobenzene, 4-	460-00-4	E611A/EO	1.0	%	81.4	76.2	77.7	79.0	110	
Difluorobenzene, 1,4-	540-36-3	E611A/EO	1.0	%	102	104	99.8	102	111	

Please refer to the General Comments section for an explanation of any result qualifiers detected.

Please refer to the Accreditation section for an explanation of analyte accreditations.



## Analytical Results

Sub-Matrix: Water					Client sample ID	9A B.Lyons D.5	DUP 01	Dup 02	----	----
(Matrix: Water)					Client sampling date / time	17-Oct-2023 12:00	17-Oct-2023 00:00	17-Oct-2023 00:00	----	----
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-021	EO2309502-022	EO2309502-023	-----	-----	
					Result	Result	Result	----	----	
<b>Physical Tests</b>										
Hardness (as CaCO3), dissolved	---	EC100/EO	0.50	mg/L	110	89.3	90.4	----	----	
Solids, total dissolved [TDS]	---	E162/EO	10	mg/L	398	442	490	----	----	
Solids, total suspended [TSS]	---	E160/EO	3.0	mg/L	28.6	92.2	20.8	----	----	
Conductivity	---	E100/CG	2.0	µS/cm	602	546	765	----	----	
pH	---	E108/CG	0.10	pH units	8.47	8.23	8.39	----	----	
Alkalinity, bicarbonate (as HCO3)	71-52-3	E290/CG	1.0	mg/L	347	309	342	----	----	
Alkalinity, carbonate (as CO3)	3812-32-6	E290/CG	1.0	mg/L	8.5	<1.0	6.1	----	----	
Alkalinity, hydroxide (as OH)	14280-30-9	E290/CG	1.0	mg/L	<1.0	<1.0	<1.0	----	----	
Alkalinity, total (as CaCO3)	----	E290/CG	2.0	mg/L	298	253	290	----	----	
Solids, total dissolved [TDS], calculated	----	EC103/EO	1.0	mg/L	385	389	461	----	----	
<b>Anions and Nutrients</b>										
Ammonia, total (as N)	7664-41-7	E298/EO	0.0050	mg/L	0.100	0.890	0.127	----	----	
Kjeldahl nitrogen, total [TKN]	---	E318/EO	0.050	mg/L	2.57	6.29	4.06	----	----	
Phosphorus, total	7723-14-0	E372-S/EO	0.0010	mg/L	0.172	2.94	0.619	----	----	
Chloride	16887-00-6	E235.Cl/EO	0.50	mg/L	7.94	20.9	34.6	----	----	
Fluoride	16984-48-8	E235.F/EO	0.020	mg/L	0.280	0.342	0.285	----	----	
Nitrate (as N)	14797-55-8	E235.NO3/EO	0.020	mg/L	0.021	0.518	<0.020	----	----	
Nitrite (as N)	14797-65-0	E235.NO2/EO	0.010	mg/L	<0.010	0.070	<0.010	----	----	
Sulfate (as SO4)	14808-79-8	E235.SO4/EO	0.30	mg/L	23.9	4.23	50.8	----	----	
Nitrate + Nitrite (as N)	----	EC235.N+N/E O	0.0500	mg/L	<0.0500	0.588	<0.0500	----	----	
<b>Organic / Inorganic Carbon</b>										
Carbon, dissolved organic [DOC]	---	E358-L/CG	0.50	mg/L	31.1	52.8	26.3	----	----	
<b>Ion Balance</b>										
Anion sum	---	EC101/EO	0.10	meq/L	6.69	5.79	7.84	----	----	
Cation sum	---	EC101/EO	0.10	meq/L	6.57	6.01	7.76	----	----	
Ion balance (APHA)	---	EC101/EO	0.01	%	-0.90	1.86	-0.51	----	----	
Ion balance (cations/anions)	---	EC101/EO	0.010	%	98.2	104	99.0	----	----	
<b>Dissolved Metals</b>										
Aluminum, dissolved	7429-90-5	E421/EO	0.0010	mg/L	0.0068	0.418	0.0016	----	----	



## Analytical Results

Sub-Matrix: Water					Client sample ID	9A B.Lyons D.5	DUP 01	Dup 02	----	----
(Matrix: Water)					Client sampling date / time	17-Oct-2023 12:00	17-Oct-2023 00:00	17-Oct-2023 00:00	----	----
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-021	EO2309502-022	EO2309502-023	-----	-----	
					Result	Result	Result	----	----	
<b>Dissolved Metals</b>										
Antimony, dissolved	7440-36-0	E421/EO	0.00010	mg/L	0.00020	0.00021	0.00018	----	----	
Arsenic, dissolved	7440-38-2	E421/EO	0.00010	mg/L	0.00296	0.00850	0.00656	----	----	
Barium, dissolved	7440-39-3	E421/EO	0.00010	mg/L	0.0626	0.0892	0.0486	----	----	
Beryllium, dissolved	7440-41-7	E421/EO	0.000020	mg/L	<0.000020	0.000065	<0.000020	----	----	
Bismuth, dissolved	7440-69-9	E421/EO	0.000050	mg/L	<0.000050	<0.000050	<0.000050	----	----	
Boron, dissolved	7440-42-8	E421/EO	0.010	mg/L	0.029	0.052	0.050	----	----	
Cadmium, dissolved	7440-43-9	E421/EO	0.0000050	mg/L	<0.0000050	0.0000381	0.0000061	----	----	
Calcium, dissolved	7440-70-2	E421/EO	0.050	mg/L	24.3	21.0	20.4	----	----	
Cesium, dissolved	7440-46-2	E421/EO	0.000010	mg/L	<0.000010	0.000022	<0.000010	----	----	
Chromium, dissolved	7440-47-3	E421/EO	0.00050	mg/L	<0.00050	0.00073	<0.00050	----	----	
Cobalt, dissolved	7440-48-4	E421/EO	0.00010	mg/L	0.00043	0.00201	0.00032	----	----	
Copper, dissolved	7440-50-8	E421/EO	0.00020	mg/L	0.00088	0.00291	0.00040	----	----	
Iron, dissolved	7439-89-6	E421/EO	0.010	mg/L	0.241	4.14	0.134	----	----	
Lead, dissolved	7439-92-1	E421/EO	0.000050	mg/L	0.000177	0.00206	0.000074	----	----	
Lithium, dissolved	7439-93-2	E421/EO	0.0010	mg/L	0.0133	0.0113	0.0358	----	----	
Magnesium, dissolved	7439-95-4	E421/EO	0.0050	mg/L	11.9	8.95	9.58	----	----	
Manganese, dissolved	7439-96-5	E421/EO	0.00010	mg/L	0.00360	0.0890	0.00528	----	----	
Mercury, dissolved	7439-97-6	E509/EO	0.0000050	mg/L	<0.0000050	<0.0000050	<0.0000050	----	----	
Molybdenum, dissolved	7439-98-7	E421/EO	0.000050	mg/L	0.00103	0.00251	0.000969	----	----	
Nickel, dissolved	7440-02-0	E421/EO	0.00050	mg/L	0.00500	0.00881	0.00345	----	----	
Phosphorus, dissolved	7723-14-0	E421/EO	0.050	mg/L	0.058	1.69	0.319	----	----	
Potassium, dissolved	7440-09-7	E421/EO	0.050	mg/L	14.4	29.2	12.7	----	----	
Rubidium, dissolved	7440-17-7	E421/EO	0.00020	mg/L	0.00153	0.00226	0.00132	----	----	
Selenium, dissolved	7782-49-2	E421/EO	0.000050	mg/L	0.000225	0.000433	0.000155	----	----	
Silicon, dissolved	7440-21-3	E421/EO	0.050	mg/L	0.192	6.33	0.996	----	----	
Silver, dissolved	7440-22-4	E421/EO	0.000010	mg/L	<0.000010	0.000011	<0.000010	----	----	
Sodium, dissolved	7440-23-5	E421/EO	0.050	mg/L	91.8	73.9	129	----	----	
Strontium, dissolved	7440-24-6	E421/EO	0.00020	mg/L	0.185	0.148	0.214	----	----	
Sulfur, dissolved	7704-34-9	E421/EO	0.50	mg/L	10.0	2.85	20.8	----	----	
Tellurium, dissolved	13494-80-9	E421/EO	0.00020	mg/L	<0.00020	<0.00020	<0.00020	----	----	





## Analytical Results

Sub-Matrix: Water					Client sample ID	9A B.Lyons D.5	DUP 01	Dup 02	----	----
(Matrix: Water)					Client sampling date / time	17-Oct-2023 12:00	17-Oct-2023 00:00	17-Oct-2023 00:00	----	----
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-021	EO2309502-022	EO2309502-023	-----	-----	
					Result	Result	Result	----	----	
<b>Dissolved Metals</b>										
Thallium, dissolved	7440-28-0	E421/EO	0.000010	mg/L	<0.000010	<0.000010	<0.000010	----	----	
Thorium, dissolved	7440-29-1	E421/EO	0.00010	mg/L	<0.00010	0.00021	<0.00010	----	----	
Tin, dissolved	7440-31-5	E421/EO	0.00010	mg/L	0.00017	<0.00010	<0.00010	----	----	
Titanium, dissolved	7440-32-6	E421/EO	0.00030	mg/L	0.00109	0.0157	0.00049	----	----	
Tungsten, dissolved	7440-33-7	E421/EO	0.00010	mg/L	<0.00010	<0.00010	<0.00010	----	----	
Uranium, dissolved	7440-61-1	E421/EO	0.000010	mg/L	0.000756	0.00152	0.000470	----	----	
Vanadium, dissolved	7440-62-2	E421/EO	0.00050	mg/L	0.00070	0.00780	0.00118	----	----	
Zinc, dissolved	7440-66-6	E421/EO	0.0010	mg/L	0.0012	0.0045	<0.0010	----	----	
Zirconium, dissolved	7440-67-7	E421/EO	0.00020	mg/L	0.00086	0.00256	0.00056	----	----	
Dissolved mercury filtration location	----	EP509/EO	-	-	Field	Field	Field	----	----	
Dissolved metals filtration location	----	EP421/EO	-	-	Field	Field	Field	----	----	
<b>Aggregate Organics</b>										
Chemical oxygen demand [COD]	----	E559-L/EO	10	mg/L	100	134 <sup>RRV</sup>	67	----	----	
Phenols, total (4AAP)	----	E562/EO	0.0010	mg/L	<0.0010	<0.0010	<0.0010	----	----	
<b>Volatile Organic Compounds</b>										
Benzene	71-43-2	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	----	----	
Ethylbenzene	100-41-4	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	----	----	
Styrene	100-42-5	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	----	----	
Toluene	108-88-3	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	----	----	
Xylene, m+p-	179601-23-1	E611A/EO	0.00040	mg/L	<0.00040	<0.00040	<0.00040	----	----	
Xylene, o-	95-47-6	E611A/EO	0.00030	mg/L	<0.00030	<0.00030	<0.00030	----	----	
Xylenes, total	1330-20-7	E611A/EO	0.00050	mg/L	<0.00050	<0.00050	<0.00050	----	----	
<b>Hydrocarbons</b>										
F1 (C6-C10)	----	E581.F1/EO	0.10	mg/L	<0.10	<0.10	<0.10	----	----	
F2 (C10-C16)	----	E601/EO	0.10	mg/L	<0.10	<0.10	<0.10	----	----	
F1-BTEX	----	EC580/EO	0.100	mg/L	<0.100	<0.100	<0.100	----	----	
<b>Hydrocarbons Surrogates</b>										
Bromobenzotrifluoride, 2- (F2-F4 surrogate)	392-83-6	E601/EO	1.0	%	99.7	98.0	99.9	----	----	
Dichlorotoluene, 3,4-	95-75-0	E581.F1/EO	1.0	%	91.6	84.2	84.5	----	----	
<b>Volatile Organic Compounds Surrogates</b>										



## Analytical Results

Sub-Matrix: Water					Client sample ID	9A B.Lyons D.5	DUP 01	Dup 02	----	----
(Matrix: Water)					Client sampling date / time	17-Oct-2023 12:00	17-Oct-2023 00:00	17-Oct-2023 00:00	----	----
Analyte	CAS Number	Method/Lab	LOR	Unit	EO2309502-021	EO2309502-022	EO2309502-023	-----	-----	
Volatile Organic Compounds Surrogates					Result	Result	Result	----	----	
Bromofluorobenzene, 4-	460-00-4	E611A/EO	1.0	%	107	106	101	----	----	
Difluorobenzene, 1,4-	540-36-3	E611A/EO	1.0	%	109	111	110	----	----	

Please refer to the General Comments section for an explanation of any result qualifiers detected.

Please refer to the Accreditation section for an explanation of analyte accreditations.



## QUALITY CONTROL INTERPRETIVE REPORT

<p><b>Work Order</b> : <b>EO2309502</b></p> <p><b>Amendment</b> : <b>1</b></p> <p><b>Client</b> : <b>Tetra Tech Canada Inc.</b></p> <p><b>Contact</b> : Brent Finnestad</p> <p><b>Address</b> : North Building 14940 123 Ave NW Edmonton AB Canada T5V 1B4</p> <p><b>Telephone</b> : 780-718-9317</p> <p><b>Project</b> : 704-SWM.SWOP04810-01</p> <p><b>PO</b> : 704-SWM.SWOP04810-01</p> <p><b>C-O-C number</b> : ----</p> <p><b>Sampler</b> : ----</p> <p><b>Site</b> : ----</p> <p><b>Quote number</b> : EO23-EBAE100-006 (Q83988)</p> <p><b>No. of samples received</b> : 23</p> <p><b>No. of samples analysed</b> : 23</p>	<p><b>Page</b> : 1 of 64</p> <p><b>Laboratory</b> : ALS Environmental - Edmonton</p> <p><b>Account Manager</b> : Kieran Tordoff</p> <p><b>Address</b> : 9450 - 17 Avenue NW Edmonton, Alberta Canada T6N 1M9</p> <p><b>Telephone</b> : +1 780 413 5227</p> <p><b>Date Samples Received</b> : 17-Oct-2023 15:36</p> <p><b>Issue Date</b> : 02-Nov-2023 14:52</p>
--	---

This report is automatically generated by the ALS LIMS (Laboratory Information Management System) through evaluation of Quality Control (QC) results and other QA parameters associated with this submission, and is intended to facilitate rapid data validation by auditors or reviewers. The report highlights any exceptions and outliers to ALS Data Quality Objectives, provides holding time details and exceptions, summarizes QC sample frequencies, and lists applicable methodology references and summaries.

**Key**

- Anonymous: Refers to samples which are not part of this work order, but which formed part of the QC process lot.
- CAS Number: Chemical Abstracts Service number is a unique identifier assigned to discrete substances.
- DQO: Data Quality Objective.
- LOR: Limit of Reporting (detection limit).
- RPD: Relative Percent Difference.

### Workorder Comments

Holding times are displayed as "----" if no guidance exists from CCME, Canadian provinces, or broadly recognized international references.

### Summary of Outliers

#### Outliers : Quality Control Samples

- No Method Blank value outliers occur.
- No Matrix Spike outliers occur.
- Duplicate outliers occur - please see following pages for full details.
- Laboratory Control Sample (LCS) outliers occur - please see following pages for full details.
- No Test sample Surrogate recovery outliers exist.

#### Outliers: Reference Material (RM) Samples

- No Reference Material (RM) Sample outliers occur.

### ***Outliers : Analysis Holding Time Compliance (Breaches)***

- Analysis Holding Time Outliers exist - please see following pages for full details.

### ***Outliers : Frequency of Quality Control Samples***

- No Quality Control Sample Frequency Outliers occur.



**Outliers : Quality Control Samples**

*Duplicates, Method Blanks, Laboratory Control Samples and Matrix Spikes*

Matrix: **Water**

Analyte Group	Laboratory sample ID	Client/Ref Sample ID	Analyte	CAS Number	Method	Result	Limits	Comment
<b>Duplicate (DUP) RPDs</b>								
Anions and Nutrients	Anonymous	Anonymous	Chloride	16887-00-6	E235.Cl	54.2 %	20%	Duplicate RPD does not meet the DQO for this test.
<b>Laboratory Control Sample (LCS) Recoveries</b>								
Dissolved Metals	QC-1197253-002	----	Iron, dissolved	7439-89-6	E421	121 % <sup>MES</sup>	80.0-120%	Recovery greater than upper control limit
Dissolved Metals	QC-1197253-002	----	Potassium, dissolved	7440-09-7	E421	121 % <sup>MES</sup>	80.0-120%	Recovery greater than upper control limit
Dissolved Metals	QC-1197253-002	----	Selenium, dissolved	7782-49-2	E421	129 % <sup>MES</sup>	80.0-120%	Recovery greater than upper control limit
Dissolved Metals	QC-1197254-002	----	Selenium, dissolved	7782-49-2	E421	130 % <sup>MES</sup>	80.0-120%	Recovery greater than upper control limit
Dissolved Metals	QC-1197253-002	----	Sodium, dissolved	7440-23-5	E421	122 % <sup>MES</sup>	80.0-120%	Recovery greater than upper control limit
Dissolved Metals	QC-1197254-002	----	Sulfur, dissolved	7704-34-9	E421	122 % <sup>MES</sup>	80.0-120%	Recovery greater than upper control limit
Dissolved Metals	QC-1197254-002	----	Zinc, dissolved	7440-66-6	E421	124 % <sup>MES</sup>	80.0-120%	Recovery greater than upper control limit

**Result Qualifiers**

Qualifier	Description
MES	Data Quality Objective was marginally exceeded (by < 10% absolute) for < 10% of analytes in a Multi-Element Scan / Multi-Parameter Scan (considered acceptable as per OMOE & CCME).



## Analysis Holding Time Compliance

This report summarizes extraction / preparation and analysis times and compares each with ALS recommended holding times, which are selected to meet known provincial and /or federal requirements. In the absence of regulatory hold times, ALS establishes recommendations based on guidelines published by organizations such as CCME, US EPA, APHA Standard Methods, ASTM, or Environment Canada (where available). Dates and holding times reported below represent the first dates of extraction or analysis. If subsequent tests or dilutions exceeded holding times, qualifiers are added (refer to COA).

If samples are identified below as having been analyzed or extracted outside of recommended holding times, measurement uncertainties may be increased, and this should be taken into consideration when interpreting results.

Where actual sampling date is not provided on the chain of custody, the date of receipt with time at 00:00 is used for calculation purposes.

Where only the sample date without time is provided on the chain of custody, the sampling date at 00:00 is used for calculation purposes.

Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 21 D.Lyons D.1	E559-L	17-Oct-2023	---	---	---		19-Oct-2023	28 days	2 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 6 B.Lyons D.1	E559-L	17-Oct-2023	---	---	---		19-Oct-2023	28 days	2 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 7 B.Lyons D.2	E559-L	17-Oct-2023	---	---	---		19-Oct-2023	28 days	2 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 8 B.Lyons D.3	E559-L	17-Oct-2023	---	---	---		19-Oct-2023	28 days	2 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 9 B.Lyons D.4	E559-L	17-Oct-2023	---	---	---		19-Oct-2023	28 days	2 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 9A B.Lyons D.5	E559-L	17-Oct-2023	---	---	---		19-Oct-2023	28 days	2 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 10 Magneson D.1	E559-L	16-Oct-2023	---	---	---		19-Oct-2023	28 days	3 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 11 Magneson D.2	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 13 Magneson D.4	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 14 Magneson D.5	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 15 Magneson D.6	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 16 Beaver County D.1	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 19 Winsnes D.1	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 1Booth D.1	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 2 Ewert D.1	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 20 Balash D.1	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 21 Balash D.2	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 22 Balash D.3	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 3 Ewert D.2	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 4 Ewert D.3	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 5 Ewert D.4	E559-L	16-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> DUP 01	E559-L	17-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Chemical Oxygen Demand by Colourimetry (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> Dup 02	E559-L	17-Oct-2023	----	----	----		19-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 21 D.Lyons D.1	E562	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 6 B.Lyons D.1	E562	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔





Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 7 B.Lyons D.2	E562	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 8 B.Lyons D.3	E562	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 9 B.Lyons D.4	E562	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 9A B.Lyons D.5	E562	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 10 Magneson D.1	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 11 Magneson D.2	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 13 Magneson D.4	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 14 Magneson D.5	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>											
<b>Amber glass total (sulfuric acid)</b> 15 Magneson D.6	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 16 Beaver County D.1	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 19 Winsnes D.1	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 1Booth D.1	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 2 Ewert D.1	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 20 Balash D.1	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 21 Balash D.2	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 22 Balash D.3	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 3 Ewert D.2	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
<b>Amber glass total (sulfuric acid)</b> 4 Ewert D.3	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
Amber glass total (sulfuric acid) 5 Ewert D.4	E562	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
Amber glass total (sulfuric acid) DUP 01	E562	17-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Aggregate Organics : Phenols (4AAP) in Water by Colorimetry</b>										
Amber glass total (sulfuric acid) Dup 02	E562	17-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 21 D.Lyons D.1	E298	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 6 B.Lyons D.1	E298	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 7 B.Lyons D.2	E298	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 8 B.Lyons D.3	E298	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 9 B.Lyons D.4	E298	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 9A B.Lyons D.5	E298	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 10 Magneson D.1	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 11 Magneson D.2	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 13 Magneson D.4	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 14 Magneson D.5	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 15 Magneson D.6	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 16 Beaver County D.1	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 19 Winsnes D.1	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 1Booth D.1	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
<b>Amber glass total (sulfuric acid)</b> 2 Ewert D.1	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 20 Balash D.1	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 21 Balash D.2	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 22 Balash D.3	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 3 Ewert D.2	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 4 Ewert D.3	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) 5 Ewert D.4	E298	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) DUP 01	E298	17-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Ammonia by Fluorescence</b>										
Amber glass total (sulfuric acid) Dup 02	E298	17-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 21 D.Lyons D.1	E235.Cl	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 6 B.Lyons D.1	E235.Cl	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 7 B.Lyons D.2	E235.Cl	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 8 B.Lyons D.3	E235.Cl	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 9 B.Lyons D.4	E235.Cl	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 9A B.Lyons D.5	E235.Cl	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 10 Magneson D.1	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 11 Magneson D.2	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 13 Magneson D.4	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Chloride in Water by IC</b>											
HDPE 14 Magneson D.5	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 15 Magneson D.6	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 16 Beaver County D.1	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 19 Winsnes D.1	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 1Booth D.1	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 2 Ewert D.1	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 20 Balash D.1	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 21 Balash D.2	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 22 Balash D.3	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 3 Ewert D.2	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 4 Ewert D.3	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE 5 Ewert D.4	E235.Cl	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE DUP 01	E235.Cl	17-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Chloride in Water by IC</b>										
HDPE Dup 02	E235.Cl	17-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Fluoride in Water by IC</b>										
HDPE 21 D.Lyons D.1	E235.F	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔
<b>Anions and Nutrients : Fluoride in Water by IC</b>										
HDPE 6 B.Lyons D.1	E235.F	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔
<b>Anions and Nutrients : Fluoride in Water by IC</b>										
HDPE 7 B.Lyons D.2	E235.F	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔
<b>Anions and Nutrients : Fluoride in Water by IC</b>										
HDPE 8 B.Lyons D.3	E235.F	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔
<b>Anions and Nutrients : Fluoride in Water by IC</b>										
HDPE 9 B.Lyons D.4	E235.F	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔





Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 9A B.Lyons D.5	E235.F	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 10 Magneson D.1	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 11 Magneson D.2	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 13 Magneson D.4	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 14 Magneson D.5	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 15 Magneson D.6	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 16 Beaver County D.1	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 19 Winsnes D.1	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 1Booth D.1	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 2 Ewert D.1	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 20 Balash D.1	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 21 Balash D.2	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 22 Balash D.3	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 3 Ewert D.2	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 4 Ewert D.3	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE 5 Ewert D.4	E235.F	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE DUP 01	E235.F	17-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Fluoride in Water by IC</b>											
HDPE Dup 02	E235.F	17-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 21 D.Lyons D.1	E235.NO3	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 6 B.Lyons D.1	E235.NO3	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 7 B.Lyons D.2	E235.NO3	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 8 B.Lyons D.3	E235.NO3	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 9 B.Lyons D.4	E235.NO3	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 9A B.Lyons D.5	E235.NO3	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 10 Magneson D.1	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 11 Magneson D.2	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 13 Magneson D.4	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 14 Magneson D.5	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 15 Magneson D.6	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 16 Beaver County D.1	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 19 Winsnes D.1	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 1Booth D.1	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 2 Ewert D.1	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 20 Balash D.1	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 21 Balash D.2	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 22 Balash D.3	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 3 Ewert D.2	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 4 Ewert D.3	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE 5 Ewert D.4	E235.NO3	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE DUP 01	E235.NO3	17-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrate in Water by IC</b>											
HDPE Dup 02	E235.NO3	17-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 21 D.Lyons D.1	E235.NO2	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 6 B.Lyons D.1	E235.NO2	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 7 B.Lyons D.2	E235.NO2	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 8 B.Lyons D.3	E235.NO2	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 9 B.Lyons D.4	E235.NO2	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 9A B.Lyons D.5	E235.NO2	17-Oct-2023	19-Oct-2023	3 days	2 days	✔	19-Oct-2023	3 days	2 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 10 Magneson D.1	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 11 Magneson D.2	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 13 Magneson D.4	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 14 Magneson D.5	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 15 Magneson D.6	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 16 Beaver County D.1	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 19 Winsnes D.1	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 1Booth D.1	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 2 Ewert D.1	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 20 Balash D.1	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 21 Balash D.2	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 22 Balash D.3	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 3 Ewert D.2	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 4 Ewert D.3	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE 5 Ewert D.4	E235.NO2	16-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE DUP 01	E235.NO2	17-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Nitrite in Water by IC</b>											
HDPE Dup 02	E235.NO2	17-Oct-2023	19-Oct-2023	3 days	3 days	✔	19-Oct-2023	3 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 21 D.Lyons D.1	E235.SO4	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 6 B.Lyons D.1	E235.SO4	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 7 B.Lyons D.2	E235.SO4	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 8 B.Lyons D.3	E235.SO4	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 9 B.Lyons D.4	E235.SO4	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 9A B.Lyons D.5	E235.SO4	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 10 Magneson D.1	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 11 Magneson D.2	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	





Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 13 Magneson D.4	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 14 Magneson D.5	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 15 Magneson D.6	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 16 Beaver County D.1	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 19 Winsnes D.1	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 1Booth D.1	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 2 Ewert D.1	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 20 Balash D.1	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 21 Balash D.2	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 22 Balash D.3	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 3 Ewert D.2	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 4 Ewert D.3	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE 5 Ewert D.4	E235.SO4	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE DUP 01	E235.SO4	17-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Sulfate in Water by IC</b>											
HDPE Dup 02	E235.SO4	17-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>											
Amber glass total (sulfuric acid) 21 D.Lyons D.1	E318	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>											
Amber glass total (sulfuric acid) 6 B.Lyons D.1	E318	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>											
Amber glass total (sulfuric acid) 7 B.Lyons D.2	E318	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 8 B.Lyons D.3	E318	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 9 B.Lyons D.4	E318	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 9A B.Lyons D.5	E318	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	2 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> DUP 01	E318	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> Dup 02	E318	17-Oct-2023	19-Oct-2023	28 days	2 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 10 Magneson D.1	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 11 Magneson D.2	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 13 Magneson D.4	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 14 Magneson D.5	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 15 Magneson D.6	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 16 Beaver County D.1	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 19 Winsnes D.1	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 1Booth D.1	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 2 Ewert D.1	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 20 Balash D.1	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 21 Balash D.2	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 22 Balash D.3	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>										
<b>Amber glass total (sulfuric acid)</b> 3 Ewert D.2	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>											
<b>Amber glass total (sulfuric acid)</b> 4 Ewert D.3	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Total Kjeldahl Nitrogen by Fluorescence (Low Level)</b>											
<b>Amber glass total (sulfuric acid)</b> 5 Ewert D.4	E318	16-Oct-2023	19-Oct-2023	28 days	3 days	✔	19-Oct-2023	28 days	3 days	✔	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>											
<b>Amber glass total (sulfuric acid)</b> 21 D.Lyons D.1	E372-S	17-Oct-2023	01-Nov-2023	28 days	15 days	✔	01-Nov-2023	28 days	15 days	✔	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>											
<b>Amber glass total (sulfuric acid)</b> 6 B.Lyons D.1	E372-S	17-Oct-2023	01-Nov-2023	28 days	15 days	✔	01-Nov-2023	28 days	15 days	✔	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>											
<b>Amber glass total (sulfuric acid)</b> 7 B.Lyons D.2	E372-S	17-Oct-2023	01-Nov-2023	28 days	15 days	✔	01-Nov-2023	28 days	15 days	✔	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>											
<b>Amber glass total (sulfuric acid)</b> 8 B.Lyons D.3	E372-S	17-Oct-2023	01-Nov-2023	28 days	15 days	✔	01-Nov-2023	28 days	15 days	✔	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>											
<b>Amber glass total (sulfuric acid)</b> 9 B.Lyons D.4	E372-S	17-Oct-2023	01-Nov-2023	28 days	15 days	✔	01-Nov-2023	28 days	15 days	✔	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>											
<b>Amber glass total (sulfuric acid)</b> 9A B.Lyons D.5	E372-S	17-Oct-2023	01-Nov-2023	28 days	15 days	✔	01-Nov-2023	28 days	15 days	✔	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>											
<b>Amber glass total (sulfuric acid)</b> DUP 01	E372-S	17-Oct-2023	01-Nov-2023	28 days	15 days	✔	01-Nov-2023	28 days	16 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> Dup 02	E372-S	17-Oct-2023	01-Nov-2023	28 days	15 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 10 Magneson D.1	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 11 Magneson D.2	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 13 Magneson D.4	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 14 Magneson D.5	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 15 Magneson D.6	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 16 Beaver County D.1	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 19 Winsnes D.1	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 1Booth D.1	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 2 Ewert D.1	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 20 Balash D.1	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 21 Balash D.2	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 22 Balash D.3	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 3 Ewert D.2	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 4 Ewert D.3	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Anions and Nutrients : Total Phosphorus by Colourimetry (0.001 mg/L)</b>										
<b>Amber glass total (sulfuric acid)</b> 5 Ewert D.4	E372-S	16-Oct-2023	01-Nov-2023	28 days	16 days	✔	01-Nov-2023	28 days	16 days	✔
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>										
<b>Glass vial dissolved (hydrochloric acid)</b> 21 D.Lyons D.1	E509	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>										
<b>Glass vial dissolved (hydrochloric acid)</b> 6 B.Lyons D.1	E509	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) 7 B.Lyons D.2	E509	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) 8 B.Lyons D.3	E509	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) 9 B.Lyons D.4	E509	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) 9A B.Lyons D.5	E509	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) DUP 01	E509	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) Dup 02	E509	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) 10 Magneson D.1	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) 11 Magneson D.2	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
Glass vial dissolved (hydrochloric acid) 13 Magneson D.4	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	





Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 14 Magneson D.5	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 15 Magneson D.6	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 16 Beaver County D.1	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 19 Winsnes D.1	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 1Booth D.1	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 2 Ewert D.1	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 20 Balash D.1	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 21 Balash D.2	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>											
<b>Glass vial dissolved (hydrochloric acid)</b> 22 Balash D.3	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>										
Glass vial dissolved (hydrochloric acid) 3 Ewert D.2	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>										
Glass vial dissolved (hydrochloric acid) 4 Ewert D.3	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Dissolved Metals : Dissolved Mercury in Water by CVAAS</b>										
Glass vial dissolved (hydrochloric acid) 5 Ewert D.4	E509	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>										
HDPE - dissolved (lab preserved) 21 D.Lyons D.1	E421	17-Oct-2023	21-Oct-2023	180 days	4 days	✔	21-Oct-2023	180 days	4 days	✔
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>										
HDPE - dissolved (lab preserved) 6 B.Lyons D.1	E421	17-Oct-2023	21-Oct-2023	180 days	4 days	✔	21-Oct-2023	180 days	4 days	✔
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>										
HDPE - dissolved (lab preserved) 7 B.Lyons D.2	E421	17-Oct-2023	21-Oct-2023	180 days	4 days	✔	21-Oct-2023	180 days	4 days	✔
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>										
HDPE - dissolved (lab preserved) 8 B.Lyons D.3	E421	17-Oct-2023	21-Oct-2023	180 days	4 days	✔	21-Oct-2023	180 days	4 days	✔
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>										
HDPE - dissolved (lab preserved) 9 B.Lyons D.4	E421	17-Oct-2023	21-Oct-2023	180 days	4 days	✔	21-Oct-2023	180 days	4 days	✔
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>										
HDPE - dissolved (lab preserved) 9A B.Lyons D.5	E421	17-Oct-2023	21-Oct-2023	180 days	4 days	✔	21-Oct-2023	180 days	4 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 10 Magneson D.1	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 11 Magneson D.2	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 13 Magneson D.4	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 14 Magneson D.5	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 15 Magneson D.6	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 16 Beaver County D.1	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 19 Winsnes D.1	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 1Booth D.1	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
<b>HDPE - dissolved (lab preserved)</b> 2 Ewert D.1	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
HDPE - dissolved (lab preserved) 20 Balash D.1	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
HDPE - dissolved (lab preserved) 21 Balash D.2	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
HDPE - dissolved (lab preserved) 22 Balash D.3	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
HDPE - dissolved (lab preserved) 3 Ewert D.2	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
HDPE - dissolved (lab preserved) 4 Ewert D.3	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
HDPE - dissolved (lab preserved) 5 Ewert D.4	E421	16-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
HDPE - dissolved (lab preserved) DUP 01	E421	17-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Dissolved Metals : Dissolved Metals in Water by CRC ICPMS</b>											
HDPE - dissolved (lab preserved) Dup 02	E421	17-Oct-2023	21-Oct-2023	180 days	5 days	✔	21-Oct-2023	180 days	5 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 21 D.Lyons D.1	E581.F1	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 6 B.Lyons D.1	E581.F1	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 7 B.Lyons D.2	E581.F1	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 8 B.Lyons D.3	E581.F1	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 9 B.Lyons D.4	E581.F1	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 9A B.Lyons D.5	E581.F1	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 10 Magneson D.1	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 11 Magneson D.2	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 13 Magneson D.4	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 14 Magneson D.5	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 15 Magneson D.6	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 16 Beaver County D.1	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 19 Winsnes D.1	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 1Booth D.1	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 2 Ewert D.1	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 20 Balash D.1	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 21 Balash D.2	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 22 Balash D.3	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 3 Ewert D.2	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 4 Ewert D.3	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) 5 Ewert D.4	E581.F1	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) DUP 01	E581.F1	17-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHC - F1 by Headspace GC-FID</b>											
Glass vial (sodium bisulfate) Dup 02	E581.F1	17-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 21 D.Lyons D.1	E601	17-Oct-2023	18-Oct-2023	14 days	1 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 6 B.Lyons D.1	E601	17-Oct-2023	18-Oct-2023	14 days	1 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 7 B.Lyons D.2	E601	17-Oct-2023	18-Oct-2023	14 days	1 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 8 B.Lyons D.3	E601	17-Oct-2023	18-Oct-2023	14 days	1 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 9 B.Lyons D.4	E601	17-Oct-2023	18-Oct-2023	14 days	1 days	✔	18-Oct-2023	40 days	0 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 9A B.Lyons D.5	E601	17-Oct-2023	18-Oct-2023	14 days	1 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) DUP 01	E601	17-Oct-2023	18-Oct-2023	14 days	1 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) Dup 02	E601	17-Oct-2023	18-Oct-2023	14 days	1 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 10 Magneson D.1	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 11 Magneson D.2	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 13 Magneson D.4	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 14 Magneson D.5	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 15 Magneson D.6	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 16 Beaver County D.1	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	





Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 19 Winsnes D.1	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 1Booth D.1	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 2 Ewert D.1	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 20 Balash D.1	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 21 Balash D.2	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 22 Balash D.3	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 3 Ewert D.2	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 4 Ewert D.3	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	
<b>Hydrocarbons : CCME PHCs - F2-F4 by GC-FID</b>											
Amber glass/Teflon lined cap (sodium bisulfate) 5 Ewert D.4	E601	16-Oct-2023	18-Oct-2023	14 days	2 days	✔	18-Oct-2023	40 days	0 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 21 D.Lyons D.1	E358-L	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 6 B.Lyons D.1	E358-L	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 7 B.Lyons D.2	E358-L	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 8 B.Lyons D.3	E358-L	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 9 B.Lyons D.4	E358-L	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 9A B.Lyons D.5	E358-L	17-Oct-2023	18-Oct-2023	28 days	1 days	✔	18-Oct-2023	28 days	1 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 10 Magneson D.1	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 11 Magneson D.2	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 13 Magneson D.4	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 14 Magneson D.5	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 15 Magneson D.6	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 16 Beaver County D.1	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 19 Winsnes D.1	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 1Booth D.1	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 2 Ewert D.1	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 20 Balash D.1	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 21 Balash D.2	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>											
<b>Amber glass dissolved (sulfuric acid)</b> 22 Balash D.3	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 3 Ewert D.2	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 4 Ewert D.3	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> 5 Ewert D.4	E358-L	16-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> DUP 01	E358-L	17-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Organic / Inorganic Carbon : Dissolved Organic Carbon by Combustion (Low Level)</b>										
<b>Amber glass dissolved (sulfuric acid)</b> Dup 02	E358-L	17-Oct-2023	18-Oct-2023	28 days	2 days	✔	18-Oct-2023	28 days	2 days	✔
<b>Physical Tests : Alkalinity Species by Titration</b>										
<b>HDPE</b> 21 D.Lyons D.1	E290	17-Oct-2023	20-Oct-2023	14 days	3 days	✔	20-Oct-2023	14 days	3 days	✔
<b>Physical Tests : Alkalinity Species by Titration</b>										
<b>HDPE</b> 6 B.Lyons D.1	E290	17-Oct-2023	20-Oct-2023	14 days	3 days	✔	20-Oct-2023	14 days	3 days	✔
<b>Physical Tests : Alkalinity Species by Titration</b>										
<b>HDPE</b> 7 B.Lyons D.2	E290	17-Oct-2023	20-Oct-2023	14 days	3 days	✔	20-Oct-2023	14 days	3 days	✔
<b>Physical Tests : Alkalinity Species by Titration</b>										
<b>HDPE</b> 8 B.Lyons D.3	E290	17-Oct-2023	20-Oct-2023	14 days	3 days	✔	20-Oct-2023	14 days	3 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 9 B.Lyons D.4	E290	17-Oct-2023	20-Oct-2023	14 days	3 days	✔	20-Oct-2023	14 days	3 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 9A B.Lyons D.5	E290	17-Oct-2023	20-Oct-2023	14 days	3 days	✔	20-Oct-2023	14 days	3 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 10 Magneson D.1	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 11 Magneson D.2	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 13 Magneson D.4	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 14 Magneson D.5	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 15 Magneson D.6	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 16 Beaver County D.1	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 19 Winsnes D.1	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 1Booth D.1	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 2 Ewert D.1	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 20 Balash D.1	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 21 Balash D.2	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 22 Balash D.3	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 3 Ewert D.2	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 4 Ewert D.3	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE 5 Ewert D.4	E290	16-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	
<b>Physical Tests : Alkalinity Species by Titration</b>											
HDPE DUP 01	E290	17-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Physical Tests : Alkalinity Species by Titration</b>										
HDPE Dup 02	E290	17-Oct-2023	20-Oct-2023	14 days	4 days	✔	20-Oct-2023	14 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 21 D.Lyons D.1	E100	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 6 B.Lyons D.1	E100	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 7 B.Lyons D.2	E100	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 8 B.Lyons D.3	E100	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 9 B.Lyons D.4	E100	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 9A B.Lyons D.5	E100	17-Oct-2023	20-Oct-2023	28 days	3 days	✔	20-Oct-2023	28 days	3 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 10 Magneson D.1	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 11 Magneson D.2	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Physical Tests : Conductivity in Water</b>										
HDPE 13 Magneson D.4	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 14 Magneson D.5	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 15 Magneson D.6	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 16 Beaver County D.1	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 19 Winsnes D.1	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 1Booth D.1	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 2 Ewert D.1	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 20 Balash D.1	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔
<b>Physical Tests : Conductivity in Water</b>										
HDPE 21 Balash D.2	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✔	20-Oct-2023	28 days	4 days	✔





Matrix: **Water** Evaluation: \* = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Physical Tests : Conductivity in Water</b>											
HDPE 22 Balash D.3	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✓	20-Oct-2023	28 days	4 days	✓	
<b>Physical Tests : Conductivity in Water</b>											
HDPE 3 Ewert D.2	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✓	20-Oct-2023	28 days	4 days	✓	
<b>Physical Tests : Conductivity in Water</b>											
HDPE 4 Ewert D.3	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✓	20-Oct-2023	28 days	4 days	✓	
<b>Physical Tests : Conductivity in Water</b>											
HDPE 5 Ewert D.4	E100	16-Oct-2023	20-Oct-2023	28 days	4 days	✓	20-Oct-2023	28 days	4 days	✓	
<b>Physical Tests : Conductivity in Water</b>											
HDPE DUP 01	E100	17-Oct-2023	20-Oct-2023	28 days	4 days	✓	20-Oct-2023	28 days	4 days	✓	
<b>Physical Tests : Conductivity in Water</b>											
HDPE Dup 02	E100	17-Oct-2023	20-Oct-2023	28 days	4 days	✓	20-Oct-2023	28 days	4 days	✓	
<b>Physical Tests : pH by Meter</b>											
HDPE 21 D.Lyons D.1	E108	17-Oct-2023	20-Oct-2023	0.25 hrs	72 hrs	* EHTR-FM	20-Oct-2023	0.25 hrs	72 hrs	* EHTR-FM	
<b>Physical Tests : pH by Meter</b>											
HDPE 9 B.Lyons D.4	E108	17-Oct-2023	20-Oct-2023	0.25 hrs	73 hrs	* EHTR-FM	20-Oct-2023	0.25 hrs	73 hrs	* EHTR-FM	
<b>Physical Tests : pH by Meter</b>											
HDPE 9A B.Lyons D.5	E108	17-Oct-2023	20-Oct-2023	0.25 hrs	73 hrs	* EHTR-FM	20-Oct-2023	0.25 hrs	73 hrs	* EHTR-FM	



Matrix: **Water** Evaluation: \* = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis					
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval		
				Rec	Actual			Rec	Actual			
<b>Physical Tests : pH by Meter</b>												
HDPE 7 B.Lyons D.2	E108	17-Oct-2023	20-Oct-2023	0.25 hrs	74 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	74 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 8 B.Lyons D.3	E108	17-Oct-2023	20-Oct-2023	0.25 hrs	74 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	74 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 6 B.Lyons D.1	E108	17-Oct-2023	20-Oct-2023	0.25 hrs	75 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	75 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE DUP 01	E108	17-Oct-2023	20-Oct-2023	0.25 hrs	85 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	85 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE Dup 02	E108	17-Oct-2023	20-Oct-2023	0.25 hrs	85 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	85 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 1Booth D.1	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	88 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	88 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 3 Ewert D.2	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	89 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	89 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 2 Ewert D.1	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	90 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	90 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 19 Winsnes D.1	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	91 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	91 hrs	*	EHTR-FM



Matrix: **Water** Evaluation: \* = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis					
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval		
				Rec	Actual			Rec	Actual			
<b>Physical Tests : pH by Meter</b>												
HDPE 5 Ewert D.4	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	92 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	92 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 4 Ewert D.3	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	93 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	93 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 16 Beaver County D.1	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	94 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	94 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 20 Balash D.1	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	94 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	94 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 21 Balash D.2	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	95 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	95 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 22 Balash D.3	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	95 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	95 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 11 Magneson D.2	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	96 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	96 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 14 Magneson D.5	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	96 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	96 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 10 Magneson D.1	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	97 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	97 hrs	*	EHTR-FM



Matrix: **Water** Evaluation: \* = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis					
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval		
				Rec	Actual			Rec	Actual			
<b>Physical Tests : pH by Meter</b>												
HDPE 15 Magneson D.6	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	97 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	97 hrs	*	EHTR-FM
<b>Physical Tests : pH by Meter</b>												
HDPE 13 Magneson D.4	E108	16-Oct-2023	20-Oct-2023	0.25 hrs	98 hrs	*	EHTR-FM	20-Oct-2023	0.25 hrs	98 hrs	*	EHTR-FM
<b>Physical Tests : TDS by Gravimetry</b>												
HDPE 10 Magneson D.1	E162	16-Oct-2023	---	---	---			20-Oct-2023	7 days	4 days	✓	
<b>Physical Tests : TDS by Gravimetry</b>												
HDPE 11 Magneson D.2	E162	16-Oct-2023	---	---	---			20-Oct-2023	7 days	4 days	✓	
<b>Physical Tests : TDS by Gravimetry</b>												
HDPE 13 Magneson D.4	E162	16-Oct-2023	---	---	---			20-Oct-2023	7 days	4 days	✓	
<b>Physical Tests : TDS by Gravimetry</b>												
HDPE 14 Magneson D.5	E162	16-Oct-2023	---	---	---			20-Oct-2023	7 days	4 days	✓	
<b>Physical Tests : TDS by Gravimetry</b>												
HDPE 1Booth D.1	E162	16-Oct-2023	---	---	---			20-Oct-2023	7 days	4 days	✓	
<b>Physical Tests : TDS by Gravimetry</b>												
HDPE 2 Ewert D.1	E162	16-Oct-2023	---	---	---			20-Oct-2023	7 days	4 days	✓	
<b>Physical Tests : TDS by Gravimetry</b>												
HDPE 3 Ewert D.2	E162	16-Oct-2023	---	---	---			20-Oct-2023	7 days	4 days	✓	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 4 Ewert D.3	E162	16-Oct-2023	----	----	----		20-Oct-2023	7 days	4 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 5 Ewert D.4	E162	16-Oct-2023	----	----	----		20-Oct-2023	7 days	4 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 21 D.Lyons D.1	E162	17-Oct-2023	----	----	----		22-Oct-2023	7 days	5 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 6 B.Lyons D.1	E162	17-Oct-2023	----	----	----		22-Oct-2023	7 days	5 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 7 B.Lyons D.2	E162	17-Oct-2023	----	----	----		22-Oct-2023	7 days	5 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 8 B.Lyons D.3	E162	17-Oct-2023	----	----	----		22-Oct-2023	7 days	5 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 9 B.Lyons D.4	E162	17-Oct-2023	----	----	----		22-Oct-2023	7 days	5 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 9A B.Lyons D.5	E162	17-Oct-2023	----	----	----		22-Oct-2023	7 days	5 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE DUP 01	E162	17-Oct-2023	----	----	----		22-Oct-2023	7 days	5 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE Dup 02	E162	17-Oct-2023	---	---	---		22-Oct-2023	7 days	5 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 15 Magneson D.6	E162	16-Oct-2023	---	---	---		22-Oct-2023	7 days	6 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 16 Beaver County D.1	E162	16-Oct-2023	---	---	---		22-Oct-2023	7 days	6 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 19 Winsnes D.1	E162	16-Oct-2023	---	---	---		22-Oct-2023	7 days	6 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 20 Balash D.1	E162	16-Oct-2023	---	---	---		22-Oct-2023	7 days	6 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 21 Balash D.2	E162	16-Oct-2023	---	---	---		22-Oct-2023	7 days	6 days	✔
<b>Physical Tests : TDS by Gravimetry</b>										
HDPE 22 Balash D.3	E162	16-Oct-2023	---	---	---		22-Oct-2023	7 days	6 days	✔
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 10 Magneson D.1	E160	16-Oct-2023	---	---	---		23-Oct-2023	7 days	7 days	✔
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 11 Magneson D.2	E160	16-Oct-2023	---	---	---		24-Oct-2023	7 days	7 days	✔



Matrix: **Water** Evaluation: \* = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 14 Magneson D.5	E160	16-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 15 Magneson D.6	E160	16-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 16 Beaver County D.1	E160	16-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 1Booth D.1	E160	16-Oct-2023	----	----	----		23-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 2 Ewert D.1	E160	16-Oct-2023	----	----	----		23-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 20 Balash D.1	E160	16-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 21 Balash D.2	E160	16-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 21 D.Lyons D.1	E160	17-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 22 Balash D.3	E160	16-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓



Matrix: **Water** Evaluation: \* = Holding time exceedance ; ✓ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 3 Ewert D.2	E160	16-Oct-2023	----	----	----		23-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 4 Ewert D.3	E160	16-Oct-2023	----	----	----		23-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 5 Ewert D.4	E160	16-Oct-2023	----	----	----		23-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 6 B.Lyons D.1	E160	17-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 7 B.Lyons D.2	E160	17-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 8 B.Lyons D.3	E160	17-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 9 B.Lyons D.4	E160	17-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 9A B.Lyons D.5	E160	17-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE DUP 01	E160	17-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✓





Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis			
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval
				Rec	Actual			Rec	Actual	
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE Dup 02	E160	17-Oct-2023	----	----	----		24-Oct-2023	7 days	7 days	✔
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 13 Magneson D.4	E160	16-Oct-2023	----	----	----		24-Oct-2023	7 days	8 days	✖ EHT
<b>Physical Tests : TSS by Gravimetry</b>										
HDPE 19 Winsnes D.1	E160	16-Oct-2023	----	----	----		24-Oct-2023	7 days	8 days	✔
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>										
Glass vial (sodium bisulfate) 21 D.Lyons D.1	E611A	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>										
Glass vial (sodium bisulfate) 6 B.Lyons D.1	E611A	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>										
Glass vial (sodium bisulfate) 7 B.Lyons D.2	E611A	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>										
Glass vial (sodium bisulfate) 8 B.Lyons D.3	E611A	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>										
Glass vial (sodium bisulfate) 9 B.Lyons D.4	E611A	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>										
Glass vial (sodium bisulfate) 9A B.Lyons D.5	E611A	17-Oct-2023	19-Oct-2023	14 days	2 days	✔	19-Oct-2023	14 days	2 days	✔



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 10 Magneson D.1	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 11 Magneson D.2	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 13 Magneson D.4	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 14 Magneson D.5	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 15 Magneson D.6	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 16 Beaver County D.1	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 19 Winsnes D.1	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 1Booth D.1	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 2 Ewert D.1	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	



Matrix: **Water** Evaluation: ✖ = Holding time exceedance ; ✔ = Within Holding Time

Analyte Group : Analytical Method Container / Client Sample ID(s)	Method	Sampling Date	Extraction / Preparation				Analysis				
			Preparation Date	Holding Times		Eval	Analysis Date	Holding Times		Eval	
				Rec	Actual			Rec	Actual		
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 20 Balash D.1	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 21 Balash D.2	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 22 Balash D.3	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 3 Ewert D.2	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 4 Ewert D.3	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) 5 Ewert D.4	E611A	16-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) DUP 01	E611A	17-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	
<b>Volatile Organic Compounds : BTEX by Headspace GC-MS</b>											
Glass vial (sodium bisulfate) Dup 02	E611A	17-Oct-2023	19-Oct-2023	14 days	3 days	✔	19-Oct-2023	14 days	3 days	✔	

**Legend & Qualifier Definitions**

EHTR-FM: Exceeded ALS recommended hold time prior to sample receipt. Field Measurement recommended  
 EHT: Exceeded ALS recommended hold time prior to analysis.  
 Rec. HT: ALS recommended hold time (see units).



## Quality Control Parameter Frequency Compliance

The following report summarizes the frequency of laboratory QC samples analyzed within the analytical batches (QC lots) in which the submitted samples were processed. The actual frequency should be greater than or equal to the expected frequency.

Matrix: **Water** Evaluation: ✖ = QC frequency outside specification; ✔ = QC frequency within specification.

Quality Control Sample Type	Method	QC Lot #	Count		Frequency (%)		
			QC	Regular	Actual	Expected	Evaluation
<b>Analytical Methods</b>							
<b>Laboratory Duplicates (DUP)</b>							
Alkalinity Species by Titration	E290	1196651	3	58	5.1	5.0	✔
Ammonia by Fluorescence	E298	1197454	2	40	5.0	5.0	✔
BTEX by Headspace GC-MS	E611A	1193705	2	40	5.0	5.0	✔
CCME PHC - F1 by Headspace GC-FID	E581.F1	1193706	2	40	5.0	5.0	✔
Chemical Oxygen Demand by Colourimetry (Low Level)	E559-L	1193619	3	60	5.0	5.0	✔
Chloride in Water by IC	E235.Cl	1194703	2	36	5.5	5.0	✔
Conductivity in Water	E100	1196650	3	60	5.0	5.0	✔
Dissolved Mercury in Water by CVAAS	E509	1191479	2	27	7.4	5.0	✔
Dissolved Metals in Water by CRC ICPMS	E421	1197253	2	34	5.8	5.0	✔
Dissolved Organic Carbon by Combustion (Low Level)	E358-L	1192634	2	33	6.0	5.0	✔
Fluoride in Water by IC	E235.F	1194700	2	36	5.5	5.0	✔
Nitrate in Water by IC	E235.NO3	1194701	2	40	5.0	5.0	✔
Nitrite in Water by IC	E235.NO2	1194702	2	40	5.0	5.0	✔
pH by Meter	E108	1196649	3	60	5.0	5.0	✔
Phenols (4AAP) in Water by Colorimetry	E562	1197246	2	40	5.0	5.0	✔
Sulfate in Water by IC	E235.SO4	1194704	2	36	5.5	5.0	✔
TDS by Gravimetry	E162	1194732	2	37	5.4	5.0	✔
Total Kjeldahl Nitrogen by Fluorescence (Low Level)	E318	1191618	2	30	6.6	5.0	✔
Total Phosphorus by Colourimetry (0.001 mg/L)	E372-S	1216788	2	40	5.0	5.0	✔
TSS by Gravimetry	E160	1199775	2	40	5.0	5.0	✔
<b>Laboratory Control Samples (LCS)</b>							
Alkalinity Species by Titration	E290	1196651	3	58	5.1	5.0	✔
Ammonia by Fluorescence	E298	1197454	2	40	5.0	5.0	✔
BTEX by Headspace GC-MS	E611A	1193705	2	40	5.0	5.0	✔
CCME PHC - F1 by Headspace GC-FID	E581.F1	1193706	2	40	5.0	5.0	✔
CCME PHCs - F2-F4 by GC-FID	E601	1191084	2	40	5.0	5.0	✔
Chemical Oxygen Demand by Colourimetry (Low Level)	E559-L	1193619	3	60	5.0	5.0	✔
Chloride in Water by IC	E235.Cl	1194703	2	36	5.5	5.0	✔
Conductivity in Water	E100	1196650	3	60	5.0	5.0	✔
Dissolved Mercury in Water by CVAAS	E509	1191479	2	27	7.4	5.0	✔
Dissolved Metals in Water by CRC ICPMS	E421	1197253	2	34	5.8	5.0	✔
Dissolved Organic Carbon by Combustion (Low Level)	E358-L	1192634	2	33	6.0	5.0	✔
Fluoride in Water by IC	E235.F	1194700	2	36	5.5	5.0	✔
Nitrate in Water by IC	E235.NO3	1194701	2	40	5.0	5.0	✔
Nitrite in Water by IC	E235.NO2	1194702	2	40	5.0	5.0	✔
pH by Meter	E108	1196649	3	60	5.0	5.0	✔



Matrix: **Water**

Evaluation: ✖ = QC frequency outside specification; ✔ = QC frequency within specification.

Quality Control Sample Type	Method	QC Lot #	Count		Frequency (%)		
			QC	Regular	Actual	Expected	Evaluation
<b>Analytical Methods</b>							
<b>Laboratory Control Samples (LCS) - Continued</b>							
Phenols (4AAP) in Water by Colorimetry	E562	1197246	2	40	5.0	5.0	✔
Sulfate in Water by IC	E235.SO4	1194704	2	36	5.5	5.0	✔
TDS by Gravimetry	E162	1194732	2	37	5.4	5.0	✔
Total Kjeldahl Nitrogen by Fluorescence (Low Level)	E318	1191618	2	30	6.6	5.0	✔
Total Phosphorus by Colourimetry (0.001 mg/L)	E372-S	1216788	2	40	5.0	5.0	✔
TSS by Gravimetry	E160	1199775	2	40	5.0	5.0	✔
<b>Method Blanks (MB)</b>							
Alkalinity Species by Titration	E290	1196651	3	58	5.1	5.0	✔
Ammonia by Fluorescence	E298	1197454	2	40	5.0	5.0	✔
BTEX by Headspace GC-MS	E611A	1193705	2	40	5.0	5.0	✔
CCME PHC - F1 by Headspace GC-FID	E581.F1	1193706	2	40	5.0	5.0	✔
CCME PHCs - F2-F4 by GC-FID	E601	1191084	2	40	5.0	5.0	✔
Chemical Oxygen Demand by Colourimetry (Low Level)	E559-L	1193619	3	60	5.0	5.0	✔
Chloride in Water by IC	E235.Cl	1194703	2	36	5.5	5.0	✔
Conductivity in Water	E100	1196650	3	60	5.0	5.0	✔
Dissolved Mercury in Water by CVAAS	E509	1191479	2	27	7.4	5.0	✔
Dissolved Metals in Water by CRC ICPMS	E421	1197253	2	34	5.8	5.0	✔
Dissolved Organic Carbon by Combustion (Low Level)	E358-L	1192634	2	33	6.0	5.0	✔
Fluoride in Water by IC	E235.F	1194700	2	36	5.5	5.0	✔
Nitrate in Water by IC	E235.NO3	1194701	2	40	5.0	5.0	✔
Nitrite in Water by IC	E235.NO2	1194702	2	40	5.0	5.0	✔
Phenols (4AAP) in Water by Colorimetry	E562	1197246	2	40	5.0	5.0	✔
Sulfate in Water by IC	E235.SO4	1194704	2	36	5.5	5.0	✔
TDS by Gravimetry	E162	1194732	2	37	5.4	5.0	✔
Total Kjeldahl Nitrogen by Fluorescence (Low Level)	E318	1191618	2	30	6.6	5.0	✔
Total Phosphorus by Colourimetry (0.001 mg/L)	E372-S	1216788	2	40	5.0	5.0	✔
TSS by Gravimetry	E160	1199775	2	40	5.0	5.0	✔
<b>Matrix Spikes (MS)</b>							
Ammonia by Fluorescence	E298	1197454	2	40	5.0	5.0	✔
BTEX by Headspace GC-MS	E611A	1193705	2	40	5.0	5.0	✔
Chemical Oxygen Demand by Colourimetry (Low Level)	E559-L	1193619	3	60	5.0	5.0	✔
Chloride in Water by IC	E235.Cl	1194703	2	36	5.5	5.0	✔
Dissolved Mercury in Water by CVAAS	E509	1191479	2	27	7.4	5.0	✔
Dissolved Metals in Water by CRC ICPMS	E421	1197253	2	34	5.8	5.0	✔
Dissolved Organic Carbon by Combustion (Low Level)	E358-L	1192634	2	33	6.0	5.0	✔
Fluoride in Water by IC	E235.F	1194700	2	36	5.5	5.0	✔
Nitrate in Water by IC	E235.NO3	1194701	2	40	5.0	5.0	✔
Nitrite in Water by IC	E235.NO2	1194702	2	40	5.0	5.0	✔
Phenols (4AAP) in Water by Colorimetry	E562	1197246	2	40	5.0	5.0	✔



Matrix: **Water** Evaluation: ✖ = QC frequency outside specification; ✔ = QC frequency within specification.

Quality Control Sample Type	Method	QC Lot #	Count		Frequency (%)		
			QC	Regular	Actual	Expected	Evaluation
<i>Analytical Methods</i>							
<b>Matrix Spikes (MS) - Continued</b>							
Sulfate in Water by IC	E235.SO4	1194704	2	36	5.5	5.0	✔
Total Kjeldahl Nitrogen by Fluorescence (Low Level)	E318	1191618	2	30	6.6	5.0	✔
Total Phosphorus by Colourimetry (0.001 mg/L)	E372-S	1216788	2	40	5.0	5.0	✔



## Methodology References and Summaries

The analytical methods used by ALS are developed using internationally recognized reference methods (where available), such as those published by US EPA, APHA Standard Methods, ASTM, ISO, Environment Canada, BC MOE, and Ontario MOE. Reference methods may incorporate modifications to improve performance (indicated by "mod").

Analytical Methods	Method / Lab	Matrix	Method Reference	Method Descriptions
Conductivity in Water	E100 ALS Environmental - Calgary	Water	APHA 2510 (mod)	Conductivity, also known as Electrical Conductivity (EC) or Specific Conductance, is measured by immersion of a conductivity cell with platinum electrodes into a water sample. Conductivity measurements are temperature-compensated to 25°C.
pH by Meter	E108 ALS Environmental - Calgary	Water	APHA 4500-H (mod)	pH is determined by potentiometric measurement with a pH electrode, and is conducted at ambient laboratory temperature (normally 20 ± 5°C). For high accuracy test results, pH should be measured in the field within the recommended 15 minute hold time.
TSS by Gravimetry	E160 ALS Environmental - Edmonton	Water	APHA 2540 D (mod)	Total Suspended Solids (TSS) are determined by filtering a sample through a glass fibre filter, following by drying of the filter at 104 ± 1°C, with gravimetric measurement of the filtered solids. Samples containing very high dissolved solid content (i.e. seawaters, brackish waters) may produce a positive bias by this method. Alternate analysis methods are available for these types of samples.
TDS by Gravimetry	E162 ALS Environmental - Edmonton	Water	APHA 2540 C (mod)	Total Dissolved Solids (TDS) are determined by filtering a sample through a glass fibre filter, with evaporation of the filtrate at 180 ± 2°C for 16 hours or to constant weight, with gravimetric measurement of the residue.
Chloride in Water by IC	E235.Cl ALS Environmental - Edmonton	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Fluoride in Water by IC	E235.F ALS Environmental - Edmonton	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Nitrite in Water by IC	E235.NO2 ALS Environmental - Edmonton	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Nitrate in Water by IC	E235.NO3 ALS Environmental - Edmonton	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.
Sulfate in Water by IC	E235.SO4 ALS Environmental - Edmonton	Water	EPA 300.1 (mod)	Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.



Analytical Methods	Method / Lab	Matrix	Method Reference	Method Descriptions
Alkalinity Species by Titration	E290 ALS Environmental - Calgary	Water	APHA 2320 B (mod)	Total alkalinity is determined by potentiometric titration to a pH 4.5 endpoint. Bicarbonate, carbonate and hydroxide alkalinity are calculated from phenolphthalein alkalinity and total alkalinity values.
Ammonia by Fluorescence	E298 ALS Environmental - Edmonton	Water	Method Fialab 100, 2018	Ammonia in water is determined by automated continuous flow analysis with membrane diffusion and fluorescence detection, after reaction with OPA (ortho-phthalaldehyde). This method is approved under US EPA 40 CFR Part 136 (May 2021)
Total Kjeldahl Nitrogen by Fluorescence (Low Level)	E318 ALS Environmental - Edmonton	Water	Method Fialab 100, 2018	TKN in water is determined by automated continuous flow analysis with membrane diffusion and fluorescence detection, after reaction with OPA (ortho-phthalaldehyde). This method is approved under US EPA 40 CFR Part 136 (May 2021).
Dissolved Organic Carbon by Combustion (Low Level)	E358-L ALS Environmental - Calgary	Water	APHA 5310 B (mod)	Dissolved Organic Carbon (Non-Purgeable), also known as NPOC (dissolved), is a direct measurement of DOC after a filtered (0.45 micron) sample has been acidified and purged to remove inorganic carbon (IC). Analysis is by high temperature combustion with infrared detection of CO <sub>2</sub> . NPOC does not include volatile organic species that are purged off with IC. For samples where the majority of DC (dissolved carbon) is comprised of IC (which is common), this method is more accurate and more reliable than the DOC by subtraction method (i.e. DC minus DIC).
Total Phosphorus by Colourimetry (0.001 mg/L)	E372-S ALS Environmental - Edmonton	Water	APHA 4500-P E (mod).	Total Phosphorus is determined colourimetrically after heated persulfate digestion of the sample.
Dissolved Metals in Water by CRC ICPMS	E421 ALS Environmental - Edmonton	Water	APHA 3030B/EPA 6020B (mod)	Water samples are filtered (0.45 um), preserved with nitric acid, and analyzed by Collision/Reaction Cell ICPMS.  Method Limitation (re: Sulfur): Sulfide and volatile sulfur species may not be recovered by this method.
Dissolved Mercury in Water by CVAAS	E509 ALS Environmental - Edmonton	Water	APHA 3030B/EPA 1631E (mod)	Water samples are filtered (0.45 um), preserved with HCl, then undergo a cold-oxidation using bromine monochloride prior to reduction with stannous chloride, and analyzed by CVAAS.
Chemical Oxygen Demand by Colourimetry (Low Level)	E559-L ALS Environmental - Edmonton	Water	APHA 5220 D (mod)	Samples are analyzed using the closed reflux colourimetric method.
Phenols (4AAP) in Water by Colorimetry	E562 ALS Environmental - Edmonton	Water	EPA 9066	This automated method is based on the distillation of phenol and subsequent reaction of the distillate with alkaline ferricyanide (K <sub>3</sub> Fe(CN) <sub>6</sub> ) and 4-amino-antipyrine (4-AAP) to form a red complex which is measured colorimetrically.





Analytical Methods	Method / Lab	Matrix	Method Reference	Method Descriptions
CCME PHC - F1 by Headspace GC-FID	E581.F1 ALS Environmental - Edmonton	Water	CCME PHC in Soil - Tier 1	CCME Fraction 1 (F1) is analyzed by static headspace GC-FID. Samples are prepared in headspace vials and are heated and agitated on the headspace autosampler, causing VOCs to partition between the aqueous phase and the headspace in accordance with Henry's law.  Analytical methods for CCME Petroleum Hydrocarbons (PHCs) are validated to comply fully with the Reference Method for the Canada-Wide Standard for PHC. Unless qualified, all required quality control criteria of the CCME PHC method have been met, including response factor and linearity requirements.
CCME PHCs - F2-F4 by GC-FID	E601 ALS Environmental - Edmonton	Water	CCME PHC in Soil - Tier 1	Sample extracts are analyzed by GC-FID for CCME hydrocarbon fractions (F2-F4).  Analytical methods for CCME Petroleum Hydrocarbons (PHCs) are validated to comply fully with the Reference Method for the Canada-Wide Standard for PHC. Unless qualified, all required quality control criteria of the CCME PHC method have been met, including response factor and linearity requirements.
BTEX by Headspace GC-MS	E611A ALS Environmental - Edmonton	Water	EPA 8260D (mod)	Volatile Organic Compounds (VOCs) are analyzed by static headspace GC-MS. Samples are prepared in headspace vials and are heated and agitated on the headspace autosampler, causing VOCs to partition between the aqueous phase and the headspace in accordance with Henry's law.
Dissolved Hardness (Calculated)	EC100 ALS Environmental - Edmonton	Water	APHA 2340B	"Hardness (as CaCO <sub>3</sub> ), dissolved" is calculated from the sum of dissolved Calcium and Magnesium concentrations, expressed in CaCO <sub>3</sub> equivalents. "Total Hardness" refers to the sum of Calcium and Magnesium Hardness. Hardness is normally or preferentially calculated from dissolved Calcium and Magnesium concentrations, because it is a property of water due to dissolved divalent cations.
Ion Balance using Dissolved Metals	EC101 ALS Environmental - Edmonton	Water	APHA 1030E	Cation Sum, Anion Sum, and Ion Balance are calculated based on guidance from APHA Standard Methods (1030E Checking Correctness of Analysis). Dissolved species are used where available. Minor ions are included where data is present.  Ion Balance cannot be calculated accurately for waters with very low electrical conductivity (EC).
TDS in Water (Calculation)	EC103 ALS Environmental - Edmonton	Water	APHA 1030E (mod)	Total Dissolved Solids is calculated based on guidance from APHA Standard Methods (1030E Checking Correctness of Analysis). Dissolved species are used where available. Minor ions are included where data is present.
Nitrate and Nitrite (as N) (Calculation)	EC235.N+N ALS Environmental - Edmonton	Water	EPA 300.0	Nitrate and Nitrite (as N) is a calculated parameter. Nitrate and Nitrite (as N) = Nitrite (as N) + Nitrate (as N).
F1-BTEX	EC580 ALS Environmental - Edmonton	Water	CCME PHC in Soil - Tier 1	F1-BTEX is calculated as follows: F1-BTEX = F1 (C6-C10) minus benzene, toluene, ethylbenzene and xylenes (BTEX).

Preparation Methods	Method / Lab	Matrix	Method Reference	Method Descriptions
---------------------	--------------	--------	------------------	---------------------



<i>Preparation Methods</i>	<i>Method / Lab</i>	<i>Matrix</i>	<i>Method Reference</i>	<i>Method Descriptions</i>
Preparation for Ammonia	EP298 ALS Environmental - Edmonton	Water		Sample preparation for Preserved Nutrients Water Quality Analysis.
Digestion for TKN in water	EP318 ALS Environmental - Edmonton	Water	APHA 4500-Norg D (mod)	Samples are digested at high temperature using Sulfuric Acid with Copper catalyst, which converts organic nitrogen sources to Ammonia, which is then quantified by the analytical method as TKN. This method is unsuitable for samples containing high levels of nitrate. If nitrate exceeds TKN concentration by ten times or more, results may be biased low.
Preparation for Dissolved Organic Carbon for Combustion	EP358 ALS Environmental - Calgary	Water	APHA 5310 B (mod)	Preparation for Dissolved Organic Carbon
Digestion for Total Phosphorus in water	EP372 ALS Environmental - Edmonton	Water	APHA 4500-P E (mod).	Samples are heated with a persulfate digestion reagent.
Dissolved Metals Water Filtration	EP421 ALS Environmental - Edmonton	Water	APHA 3030B	Water samples are filtered (0.45 um), and preserved with HNO <sub>3</sub> .
Dissolved Mercury Water Filtration	EP509 ALS Environmental - Edmonton	Water	APHA 3030B	Water samples are filtered (0.45 um), and preserved with HCl.
VOCs Preparation for Headspace Analysis	EP581 ALS Environmental - Edmonton	Water	EPA 5021A (mod)	Samples are prepared in headspace vials and are heated and agitated on the headspace autosampler. An aliquot of the headspace is then injected into the GC/MS-FID system.
PHCs and PAHs Hexane Extraction	EP601 ALS Environmental - Edmonton	Water	EPA 3511 (mod)	Petroleum Hydrocarbons (PHCs) and Polycyclic Aromatic Hydrocarbons (PAHs) are extracted using a hexane liquid-liquid extraction.

## QUALITY CONTROL REPORT

<b>Work Order</b>	<b>: EO2309502</b>	<b>Page</b>	: 1 of 26
<b>Amendment</b>	<b>: 1</b>		
<b>Client</b>	: Tetra Tech Canada Inc.	<b>Laboratory</b>	: ALS Environmental - Edmonton
<b>Contact</b>	: Brent Finnestad	<b>Account Manager</b>	: Kieran Tordoff
<b>Address</b>	: North Building 14940 123 Ave NW Edmonton AB Canada T5V 1B4	<b>Address</b>	: 9450 - 17 Avenue NW Edmonton, Alberta Canada T6N 1M9
<b>Telephone</b>	:	<b>Telephone</b>	: +1 780 413 5227
<b>Project</b>	: 704-SWM.SWOP04810-01	<b>Date Samples Received</b>	: 17-Oct-2023 15:36
<b>PO</b>	: 704-SWM.SWOP04810-01	<b>Date Analysis Commenced</b>	: 18-Oct-2023
<b>C-O-C number</b>	: ----	<b>Issue Date</b>	: 02-Nov-2023 14:52
<b>Sampler</b>	: ----                    780-718-9317		
<b>Site</b>	: ----		
<b>Quote number</b>	: EO23-EBAE100-006 (Q83988)		
<b>No. of samples received</b>	: 23		
<b>No. of samples analysed</b>	: 23		

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Quality Control Report contains the following information:

- Laboratory Duplicate (DUP) Report; Relative Percent Difference (RPD) and Data Quality Objectives
- Matrix Spike (MS) Report; Recovery and Data Quality Objectives
- Method Blank (MB) Report; Recovery and Data Quality Objectives
- Laboratory Control Sample (LCS) Report; Recovery and Data Quality Objectives

### Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is conducted in accordance with US FDA 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Laboratory Department</i>
Alex Drake	Lab Analyst	Edmonton Inorganics, Edmonton, Alberta
Alex Drake	Lab Analyst	Edmonton Metals, Edmonton, Alberta
Brayden Ginther	Laboratory Analyst	Edmonton Metals, Edmonton, Alberta
Brooke Miller	Laboratory Analyst	Edmonton Inorganics, Edmonton, Alberta
Dan Nguyen	Team Leader - Inorganics	Edmonton Inorganics, Edmonton, Alberta
Dan Nguyen	Team Leader - Inorganics	Edmonton Metals, Edmonton, Alberta
Daniel Nguyen	Lab Assistant	Edmonton Metals, Edmonton, Alberta
Elke Tabora		Calgary Inorganics, Calgary, Alberta
Fahad Husain	Analyst	Edmonton Inorganics, Edmonton, Alberta
Garrett Nodin	Lab Analyst	Edmonton Inorganics, Edmonton, Alberta
Jing Liu	Lab Assistant	Edmonton Inorganics, Edmonton, Alberta
Kari Mulroy	Lab Supervisor - Environmental	Edmonton Organics, Edmonton, Alberta
Kevin Baxter	Team Leader - Inorganics	Calgary Inorganics, Calgary, Alberta
Logan Carroll	Laboratory Analyst	Edmonton Inorganics, Edmonton, Alberta

Michelle Schroder  
Yan Zhang

Laboratory Analyst  
Lab Analyst

Edmonton Inorganics, Edmonton, Alberta  
Edmonton Organics, Edmonton, Alberta



---

## General Comments

The ALS Quality Control (QC) report is optionally provided to ALS clients upon request. ALS test methods include comprehensive QC checks with every analysis to ensure our high standards of quality are met. Each QC result has a known or expected target value, which is compared against predetermined Data Quality Objectives (DQOs) to provide confidence in the accuracy of associated test results. This report contains detailed results for all QC results applicable to this sample submission. Please refer to the ALS Quality Control Interpretation report (QCI) for applicable method references and methodology summaries.

### Key :

Anonymous = Refers to samples which are not part of this work order, but which formed part of the QC process lot.

CAS Number = Chemical Abstracts Service number is a unique identifier assigned to discrete substances.

DQO = Data Quality Objective.

LOR = Limit of Reporting (detection limit).

RPD = Relative Percent Difference

# = Indicates a QC result that did not meet the ALS DQO.

## Workorder Comments

---

Holding times are displayed as "--" if no guidance exists from CCME, Canadian provinces, or broadly recognized international references.

---



### Laboratory Duplicate (DUP) Report

A Laboratory Duplicate (DUP) is a randomly selected intralaboratory replicate sample. Laboratory Duplicates provide information regarding method precision and sample heterogeneity. ALS DQOs for Laboratory Duplicates are expressed as test-specific limits for Relative Percent Difference (RPD), or as an absolute difference limit of 2 times the LOR for low concentration duplicates within ~ 4-10 times the LOR (cut-off is test-specific).

Sub-Matrix: <b>Water</b>					Laboratory Duplicate (DUP) Report						
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
<b>Physical Tests (QC Lot: 1194732)</b>											
EO2309472-001	Anonymous	Solids, total dissolved [TDS]	----	E162	20	mg/L	854	852	0.235%	20%	----
<b>Physical Tests (QC Lot: 1196649)</b>											
EO2309464-004	Anonymous	pH	----	E108	0.10	pH units	8.96	8.96	0.00%	4%	----
<b>Physical Tests (QC Lot: 1196650)</b>											
EO2309464-004	Anonymous	Conductivity	----	E100	2.0	µS/cm	538	539	0.186%	10%	----
<b>Physical Tests (QC Lot: 1196651)</b>											
EO2309480-001	Anonymous	Alkalinity, total (as CaCO <sub>3</sub> )	----	E290	2.0	mg/L	583	582	0.154%	20%	----
<b>Physical Tests (QC Lot: 1197230)</b>											
CG2314802-001	Anonymous	pH	----	E108	0.10	pH units	8.28	8.58	3.56%	4%	----
<b>Physical Tests (QC Lot: 1197231)</b>											
CG2314802-001	Anonymous	Conductivity	----	E100	2.0	µS/cm	1540	1570	1.80%	10%	----
<b>Physical Tests (QC Lot: 1197232)</b>											
CG2314802-001	Anonymous	Alkalinity, total (as CaCO <sub>3</sub> )	----	E290	2.0	mg/L	382	386	1.09%	20%	----
<b>Physical Tests (QC Lot: 1197234)</b>											
EO2309502-014	21 Balash D.2	Alkalinity, total (as CaCO <sub>3</sub> )	----	E290	2.0	mg/L	310	323	4.04%	20%	----
<b>Physical Tests (QC Lot: 1197235)</b>											
EO2309502-014	21 Balash D.2	pH	----	E108	0.10	pH units	8.67	8.68	0.115%	4%	----
<b>Physical Tests (QC Lot: 1197236)</b>											
EO2309502-014	21 Balash D.2	Conductivity	----	E100	2.0	µS/cm	1910	1910	0.00%	10%	----
<b>Physical Tests (QC Lot: 1197463)</b>											
EO2309502-010	15 Magneson D.6	Solids, total dissolved [TDS]	----	E162	20	mg/L	1630	1650	1.31%	20%	----
<b>Physical Tests (QC Lot: 1199775)</b>											
EO2309444-004	Anonymous	Solids, total suspended [TSS]	----	E160	3.0	mg/L	15.0	16.2	1.2	Diff <2x LOR	----
<b>Physical Tests (QC Lot: 1200569)</b>											
EO2309502-007	11 Magneson D.2	Solids, total suspended [TSS]	----	E160	3.0	mg/L	86.4	85.0	1.63%	20%	----
<b>Anions and Nutrients (QC Lot: 1191618)</b>											
EO2309439-060	Anonymous	Kjeldahl nitrogen, total [TKN]	----	E318	0.200	mg/L	1.19	1.11	0.080	Diff <2x LOR	----
<b>Anions and Nutrients (QC Lot: 1191619)</b>											
EO2309502-019	8 B.Lyons D.3	Kjeldahl nitrogen, total [TKN]	----	E318	0.050	mg/L	3.15	3.40	7.64%	20%	----
<b>Anions and Nutrients (QC Lot: 1194700)</b>											



Sub-Matrix: Water					Laboratory Duplicate (DUP) Report						
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
<b>Anions and Nutrients (QC Lot: 1194700) - continued</b>											
EO2309502-016	21 D.Lyons D.1	Fluoride	16984-48-8	E235.F	0.020	mg/L	0.277	0.279	0.719%	20%	----
<b>Anions and Nutrients (QC Lot: 1194701)</b>											
EO2309502-016	21 D.Lyons D.1	Nitrate (as N)	14797-55-8	E235.NO3	0.020	mg/L	0.165	0.161	0.004	Diff <2x LOR	----
<b>Anions and Nutrients (QC Lot: 1194702)</b>											
EO2309502-016	21 D.Lyons D.1	Nitrite (as N)	14797-65-0	E235.NO2	0.010	mg/L	0.021	0.022	0.0008	Diff <2x LOR	----
<b>Anions and Nutrients (QC Lot: 1194703)</b>											
EO2309502-016	21 D.Lyons D.1	Chloride	16887-00-6	E235.Cl	0.50	mg/L	10.8	10.6	1.33%	20%	----
<b>Anions and Nutrients (QC Lot: 1194704)</b>											
EO2309502-016	21 D.Lyons D.1	Sulfate (as SO4)	14808-79-8	E235.SO4	0.30	mg/L	21.3	21.1	0.835%	20%	----
<b>Anions and Nutrients (QC Lot: 1195018)</b>											
EO2309506-008	Anonymous	Sulfate (as SO4)	14808-79-8	E235.SO4	0.30	mg/L	889	761	15.5%	20%	----
<b>Anions and Nutrients (QC Lot: 1195019)</b>											
EO2309506-008	Anonymous	Nitrate (as N)	14797-55-8	E235.NO3	0.020	mg/L	<0.020	<0.020	0	Diff <2x LOR	----
<b>Anions and Nutrients (QC Lot: 1195020)</b>											
EO2309506-008	Anonymous	Nitrite (as N)	14797-65-0	E235.NO2	0.010	mg/L	<0.010	<0.010	0	Diff <2x LOR	----
<b>Anions and Nutrients (QC Lot: 1195021)</b>											
EO2309506-008	Anonymous	Fluoride	16984-48-8	E235.F	0.020	mg/L	<0.020	<0.020	0	Diff <2x LOR	----
<b>Anions and Nutrients (QC Lot: 1195022)</b>											
EO2309506-008	Anonymous	Chloride	16887-00-6	E235.Cl	0.50	mg/L	39.1	22.4	54.2%	20%	----
<b>Anions and Nutrients (QC Lot: 1197454)</b>											
EO2309480-001	Anonymous	Ammonia, total (as N)	7664-41-7	E298	0.0500	mg/L	1.85	1.86	0.270%	20%	----
<b>Anions and Nutrients (QC Lot: 1197657)</b>											
FC2303044-001	Anonymous	Ammonia, total (as N)	7664-41-7	E298	0.0050	mg/L	0.0467	0.0477	0.0010	Diff <2x LOR	----
<b>Anions and Nutrients (QC Lot: 1216788)</b>											
EO2309502-001	1Booth D.1	Phosphorus, total	7723-14-0	E372-S	0.0010	mg/L	0.607	0.605	0.403%	20%	----
<b>Anions and Nutrients (QC Lot: 1216789)</b>											
EO2309502-021	9A B.Lyons D.5	Phosphorus, total	7723-14-0	E372-S	0.0010	mg/L	0.172	0.174	0.964%	20%	----
<b>Organic / Inorganic Carbon (QC Lot: 1192634)</b>											
EO2309502-001	1Booth D.1	Carbon, dissolved organic [DOC]	----	E358-L	0.50	mg/L	29.8	32.3	8.15%	20%	----
<b>Organic / Inorganic Carbon (QC Lot: 1192635)</b>											
EO2309502-021	9A B.Lyons D.5	Carbon, dissolved organic [DOC]	----	E358-L	0.50	mg/L	31.1	31.3	0.545%	20%	----
<b>Dissolved Metals (QC Lot: 1191479)</b>											
EO2309493-001	Anonymous	Mercury, dissolved	7439-97-6	E509	0.0000050	mg/L	<0.0000050	<0.0000050	0	Diff <2x LOR	----



Sub-Matrix: Water					Laboratory Duplicate (DUP) Report						
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
<b>Dissolved Metals (QC Lot: 1191480)</b>											
EO2309502-013	20 Balash D.1	Mercury, dissolved	7439-97-6	E509	0.0000050	mg/L	<0.0000050	<0.0000050	0	Diff <2x LOR	----
<b>Dissolved Metals (QC Lot: 1197253)</b>											
EO2309502-001	1Booth D.1	Aluminum, dissolved	7429-90-5	E421	0.0010	mg/L	0.0027	0.0032	0.0005	Diff <2x LOR	----
		Antimony, dissolved	7440-36-0	E421	0.00010	mg/L	0.00023	0.00022	0.000007	Diff <2x LOR	----
		Arsenic, dissolved	7440-38-2	E421	0.00010	mg/L	0.00647	0.00641	0.938%	20%	----
		Barium, dissolved	7440-39-3	E421	0.00010	mg/L	0.0503	0.0500	0.553%	20%	----
		Beryllium, dissolved	7440-41-7	E421	0.000020	mg/L	<0.000020	<0.000020	0	Diff <2x LOR	----
		Bismuth, dissolved	7440-69-9	E421	0.000050	mg/L	<0.000050	<0.000050	0	Diff <2x LOR	----
		Boron, dissolved	7440-42-8	E421	0.010	mg/L	0.048	0.050	0.001	Diff <2x LOR	----
		Cadmium, dissolved	7440-43-9	E421	0.0000050	mg/L	0.0000052	<0.0000050	0.0000002	Diff <2x LOR	----
		Calcium, dissolved	7440-70-2	E421	0.050	mg/L	22.6	22.3	1.34%	20%	----
		Cesium, dissolved	7440-46-2	E421	0.000010	mg/L	<0.000010	<0.000010	0	Diff <2x LOR	----
		Chromium, dissolved	7440-47-3	E421	0.00050	mg/L	<0.00050	<0.00050	0	Diff <2x LOR	----
		Cobalt, dissolved	7440-48-4	E421	0.00010	mg/L	0.00035	0.00034	0.000006	Diff <2x LOR	----
		Copper, dissolved	7440-50-8	E421	0.00020	mg/L	0.00054	0.00059	0.00005	Diff <2x LOR	----
		Iron, dissolved	7439-89-6	E421	0.010	mg/L	0.142	0.143	0.555%	20%	----
		Lead, dissolved	7439-92-1	E421	0.000050	mg/L	0.000098	0.000092	0.000006	Diff <2x LOR	----
		Lithium, dissolved	7439-93-2	E421	0.0010	mg/L	0.0384	0.0383	0.137%	20%	----
		Magnesium, dissolved	7439-95-4	E421	0.0050	mg/L	10.2	10.1	0.878%	20%	----
		Manganese, dissolved	7439-96-5	E421	0.00010	mg/L	0.00556	0.00551	0.910%	20%	----
		Molybdenum, dissolved	7439-98-7	E421	0.000050	mg/L	0.00106	0.00108	1.62%	20%	----
		Nickel, dissolved	7440-02-0	E421	0.00050	mg/L	0.00384	0.00358	0.00026	Diff <2x LOR	----
		Phosphorus, dissolved	7723-14-0	E421	0.050	mg/L	0.344	0.319	0.025	Diff <2x LOR	----
		Potassium, dissolved	7440-09-7	E421	0.050	mg/L	13.2	13.2	0.197%	20%	----
		Rubidium, dissolved	7440-17-7	E421	0.00020	mg/L	0.00131	0.00131	0.000004	Diff <2x LOR	----
		Selenium, dissolved	7782-49-2	E421	0.000050	mg/L	0.000132	0.000139	0.000007	Diff <2x LOR	----
		Silicon, dissolved	7440-21-3	E421	0.050	mg/L	1.01	1.01	0.118%	20%	----
		Silver, dissolved	7440-22-4	E421	0.000010	mg/L	<0.000010	<0.000010	0	Diff <2x LOR	----
		Sodium, dissolved	7440-23-5	E421	0.050	mg/L	140	133	4.91%	20%	----
		Strontium, dissolved	7440-24-6	E421	0.00020	mg/L	0.243	0.237	2.38%	20%	----
		Sulfur, dissolved	7704-34-9	E421	0.50	mg/L	21.0	20.8	0.651%	20%	----
		Tellurium, dissolved	13494-80-9	E421	0.00020	mg/L	<0.00020	<0.00020	0	Diff <2x LOR	----
		Thallium, dissolved	7440-28-0	E421	0.000010	mg/L	<0.000010	<0.000010	0	Diff <2x LOR	----
		Thorium, dissolved	7440-29-1	E421	0.00010	mg/L	<0.00010	<0.00010	0	Diff <2x LOR	----





Sub-Matrix: Water					Laboratory Duplicate (DUP) Report						
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
<b>Dissolved Metals (QC Lot: 1197253) - continued</b>											
EO2309502-001	1Booth D.1	Tin, dissolved	7440-31-5	E421	0.00010	mg/L	0.00030	0.00021	0.00010	Diff <2x LOR	----
		Titanium, dissolved	7440-32-6	E421	0.00030	mg/L	0.00065	0.00089	0.00024	Diff <2x LOR	----
		Tungsten, dissolved	7440-33-7	E421	0.00010	mg/L	<0.00010	<0.00010	0	Diff <2x LOR	----
		Uranium, dissolved	7440-61-1	E421	0.000010	mg/L	0.000525	0.000522	0.655%	20%	----
		Vanadium, dissolved	7440-62-2	E421	0.00050	mg/L	0.00120	0.00118	0.00002	Diff <2x LOR	----
		Zinc, dissolved	7440-66-6	E421	0.0010	mg/L	<0.0010	<0.0010	0	Diff <2x LOR	----
		Zirconium, dissolved	7440-67-7	E421	0.00020	mg/L	0.00066	0.00071	0.00005	Diff <2x LOR	----
<b>Dissolved Metals (QC Lot: 1197254)</b>											
EO2309502-021	9A B.Lyons D.5	Aluminum, dissolved	7429-90-5	E421	0.0010	mg/L	0.0068	0.0073	0.0004	Diff <2x LOR	----
		Antimony, dissolved	7440-36-0	E421	0.00010	mg/L	0.00020	0.00021	0.000007	Diff <2x LOR	----
		Arsenic, dissolved	7440-38-2	E421	0.00010	mg/L	0.00296	0.00284	4.27%	20%	----
		Barium, dissolved	7440-39-3	E421	0.00010	mg/L	0.0626	0.0632	1.07%	20%	----
		Beryllium, dissolved	7440-41-7	E421	0.000020	mg/L	<0.000020	<0.000020	0	Diff <2x LOR	----
		Bismuth, dissolved	7440-69-9	E421	0.000050	mg/L	<0.000050	<0.000050	0	Diff <2x LOR	----
		Boron, dissolved	7440-42-8	E421	0.010	mg/L	0.029	0.028	0.0006	Diff <2x LOR	----
		Cadmium, dissolved	7440-43-9	E421	0.0000050	mg/L	<0.0000050	0.0000060	0.0000010	Diff <2x LOR	----
		Calcium, dissolved	7440-70-2	E421	0.050	mg/L	24.3	24.4	0.0706%	20%	----
		Cesium, dissolved	7440-46-2	E421	0.000010	mg/L	<0.000010	<0.000010	0	Diff <2x LOR	----
		Chromium, dissolved	7440-47-3	E421	0.00050	mg/L	<0.00050	<0.00050	0	Diff <2x LOR	----
		Cobalt, dissolved	7440-48-4	E421	0.00010	mg/L	0.00043	0.00040	0.00002	Diff <2x LOR	----
		Copper, dissolved	7440-50-8	E421	0.00020	mg/L	0.00088	0.00086	0.00002	Diff <2x LOR	----
		Iron, dissolved	7439-89-6	E421	0.010	mg/L	0.241	0.234	3.09%	20%	----
		Lead, dissolved	7439-92-1	E421	0.000050	mg/L	0.000177	0.000180	0.000002	Diff <2x LOR	----
		Lithium, dissolved	7439-93-2	E421	0.0010	mg/L	0.0133	0.0132	0.966%	20%	----
		Magnesium, dissolved	7439-95-4	E421	0.0050	mg/L	11.9	12.2	2.50%	20%	----
		Manganese, dissolved	7439-96-5	E421	0.00010	mg/L	0.00360	0.00341	5.39%	20%	----
		Molybdenum, dissolved	7439-98-7	E421	0.000050	mg/L	0.00103	0.00104	1.19%	20%	----
		Nickel, dissolved	7440-02-0	E421	0.00050	mg/L	0.00500	0.00461	0.00039	Diff <2x LOR	----
		Phosphorus, dissolved	7723-14-0	E421	0.050	mg/L	0.058	<0.050	0.008	Diff <2x LOR	----
Potassium, dissolved	7440-09-7	E421	0.050	mg/L	14.4	14.4	0.596%	20%	----		
Rubidium, dissolved	7440-17-7	E421	0.00020	mg/L	0.00153	0.00172	0.00018	Diff <2x LOR	----		
Selenium, dissolved	7782-49-2	E421	0.000050	mg/L	0.000225	0.000247	0.000022	Diff <2x LOR	----		
Silicon, dissolved	7440-21-3	E421	0.050	mg/L	0.192	0.190	0.002	Diff <2x LOR	----		
Silver, dissolved	7440-22-4	E421	0.000010	mg/L	<0.000010	<0.000010	0	Diff <2x LOR	----		



Sub-Matrix: Water					Laboratory Duplicate (DUP) Report						
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
<b>Dissolved Metals (QC Lot: 1197254) - continued</b>											
EO2309502-021	9A B.Lyons D.5	Sodium, dissolved	7440-23-5	E421	0.050	mg/L	91.8	92.1	0.227%	20%	----
		Strontium, dissolved	7440-24-6	E421	0.00020	mg/L	0.185	0.182	1.78%	20%	----
		Sulfur, dissolved	7704-34-9	E421	0.50	mg/L	10.0	10.1	0.151%	20%	----
		Tellurium, dissolved	13494-80-9	E421	0.00020	mg/L	<0.00020	<0.00020	0	Diff <2x LOR	----
		Thallium, dissolved	7440-28-0	E421	0.00010	mg/L	<0.00010	<0.00010	0	Diff <2x LOR	----
		Thorium, dissolved	7440-29-1	E421	0.00010	mg/L	<0.00010	<0.00010	0	Diff <2x LOR	----
		Tin, dissolved	7440-31-5	E421	0.00010	mg/L	0.00017	<0.00010	0.00007	Diff <2x LOR	----
		Titanium, dissolved	7440-32-6	E421	0.00030	mg/L	0.00109	0.00113	0.00004	Diff <2x LOR	----
		Tungsten, dissolved	7440-33-7	E421	0.00010	mg/L	<0.00010	<0.00010	0	Diff <2x LOR	----
		Uranium, dissolved	7440-61-1	E421	0.00010	mg/L	0.000756	0.000758	0.326%	20%	----
		Vanadium, dissolved	7440-62-2	E421	0.00050	mg/L	0.00070	0.00066	0.00004	Diff <2x LOR	----
		Zinc, dissolved	7440-66-6	E421	0.0010	mg/L	0.0012	0.0010	0.0002	Diff <2x LOR	----
Zirconium, dissolved	7440-67-7	E421	0.00020	mg/L	0.00086	0.00082	0.00004	Diff <2x LOR	----		
<b>Aggregate Organics (QC Lot: 1193619)</b>											
EO2309455-019	Anonymous	Chemical oxygen demand [COD]	----	E559-L	10	mg/L	27	30	3	Diff <2x LOR	----
<b>Aggregate Organics (QC Lot: 1193858)</b>											
EO2309434-012	Anonymous	Chemical oxygen demand [COD]	----	E559-L	100	mg/L	409	514	105	Diff <2x LOR	----
<b>Aggregate Organics (QC Lot: 1195266)</b>											
EO2309502-022	DUP 01	Chemical oxygen demand [COD]	----	E559-L	10	mg/L	134	126	6.17%	20%	----
<b>Aggregate Organics (QC Lot: 1197246)</b>											
EO2309440-072	Anonymous	Phenols, total (4AAP)	----	E562	0.0010	mg/L	<0.0010	<0.0010	0	Diff <2x LOR	----
<b>Aggregate Organics (QC Lot: 1197247)</b>											
EO2309502-009	14 Magneson D.5	Phenols, total (4AAP)	----	E562	0.0010	mg/L	<0.0010	<0.0010	0	Diff <2x LOR	----
<b>Volatile Organic Compounds (QC Lot: 1193705)</b>											
EO2309460-035	Anonymous	Benzene	71-43-2	E611A	0.50	µg/L	<0.50	<0.50	0	Diff <2x LOR	----
		Ethylbenzene	100-41-4	E611A	0.50	µg/L	<0.50	<0.50	0	Diff <2x LOR	----
		Styrene	100-42-5	E611A	0.50	µg/L	<0.50	<0.50	0	Diff <2x LOR	----
		Toluene	108-88-3	E611A	0.50	µg/L	<0.50	<0.50	0	Diff <2x LOR	----
		Xylene, m+p-	179601-23-1	E611A	0.40	µg/L	<0.40	<0.40	0	Diff <2x LOR	----
		Xylene, o-	95-47-6	E611A	0.30	µg/L	<0.30	<0.30	0	Diff <2x LOR	----
<b>Volatile Organic Compounds (QC Lot: 1194589)</b>											
EO2309502-020	9 B.Lyons D.4	Benzene	71-43-2	E611A	0.50	µg/L	<0.00050 mg/L	<0.50	0	Diff <2x LOR	----
		Ethylbenzene	100-41-4	E611A	0.50	µg/L	<0.00050 mg/L	<0.50	0	Diff <2x LOR	----



Sub-Matrix: Water					Laboratory Duplicate (DUP) Report						
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	LOR	Unit	Original Result	Duplicate Result	RPD(%) or Difference	Duplicate Limits	Qualifier
<b>Volatile Organic Compounds (QC Lot: 1194589) - continued</b>											
EO2309502-020	9 B.Lyons D.4	Styrene	100-42-5	E611A	0.50	µg/L	<0.00050 mg/L	<0.50	0	Diff <2x LOR	----
		Toluene	108-88-3	E611A	0.50	µg/L	<0.00050 mg/L	<0.50	0	Diff <2x LOR	----
		Xylene, m+p-	179601-23-1	E611A	0.40	µg/L	<0.00040 mg/L	<0.40	0	Diff <2x LOR	----
		Xylene, o-	95-47-6	E611A	0.30	µg/L	<0.00030 mg/L	<0.30	0	Diff <2x LOR	----
<b>Hydrocarbons (QC Lot: 1193706)</b>											
EO2309460-035	Anonymous	F1 (C6-C10)	----	E581.F1	100	µg/L	<100	<100	0	Diff <2x LOR	----
<b>Hydrocarbons (QC Lot: 1194590)</b>											
EO2309502-020	9 B.Lyons D.4	F1 (C6-C10)	----	E581.F1	100	µg/L	<0.10 mg/L	<100	0	Diff <2x LOR	----



## Method Blank (MB) Report

A Method Blank is an analyte-free matrix that undergoes sample processing identical to that carried out for test samples. Method Blank results are used to monitor and control for potential contamination from the laboratory environment and reagents. For most tests, the DQO for Method Blanks is for the result to be < LOR.

Sub-Matrix: **Water**

Analyte	CAS Number	Method	LOR	Unit	Result	Qualifier
<b>Physical Tests (QCLot: 1194732)</b>						
Solids, total dissolved [TDS]	---	E162	10	mg/L	<10	---
<b>Physical Tests (QCLot: 1196650)</b>						
Conductivity	---	E100	1	µS/cm	<1.0	---
<b>Physical Tests (QCLot: 1196651)</b>						
Alkalinity, total (as CaCO3)	---	E290	1	mg/L	<1.0	---
<b>Physical Tests (QCLot: 1197231)</b>						
Conductivity	---	E100	1	µS/cm	<1.0	---
<b>Physical Tests (QCLot: 1197232)</b>						
Alkalinity, total (as CaCO3)	---	E290	1	mg/L	<1.0	---
<b>Physical Tests (QCLot: 1197234)</b>						
Alkalinity, total (as CaCO3)	---	E290	1	mg/L	<1.0	---
<b>Physical Tests (QCLot: 1197236)</b>						
Conductivity	---	E100	1	µS/cm	<1.0	---
<b>Physical Tests (QCLot: 1197463)</b>						
Solids, total dissolved [TDS]	---	E162	10	mg/L	<10	---
<b>Physical Tests (QCLot: 1199775)</b>						
Solids, total suspended [TSS]	---	E160	3	mg/L	<3.0	---
<b>Physical Tests (QCLot: 1200569)</b>						
Solids, total suspended [TSS]	---	E160	3	mg/L	<3.0	---
<b>Anions and Nutrients (QCLot: 1191618)</b>						
Kjeldahl nitrogen, total [TKN]	---	E318	0.05	mg/L	<0.050	---
<b>Anions and Nutrients (QCLot: 1191619)</b>						
Kjeldahl nitrogen, total [TKN]	---	E318	0.05	mg/L	<0.050	---
<b>Anions and Nutrients (QCLot: 1194700)</b>						
Fluoride	16984-48-8	E235.F	0.02	mg/L	<0.020	---
<b>Anions and Nutrients (QCLot: 1194701)</b>						
Nitrate (as N)	14797-55-8	E235.NO3	0.02	mg/L	<0.020	---
<b>Anions and Nutrients (QCLot: 1194702)</b>						
Nitrite (as N)	14797-65-0	E235.NO2	0.01	mg/L	<0.010	---
<b>Anions and Nutrients (QCLot: 1194703)</b>						
Chloride	16887-00-6	E235.Cl	0.5	mg/L	<0.50	---
<b>Anions and Nutrients (QCLot: 1194704)</b>						



Sub-Matrix: **Water**

Analyte	CAS Number	Method	LOR	Unit	Result	Qualifier
<b>Anions and Nutrients (QCLot: 1194704) - continued</b>						
Sulfate (as SO4)	14808-79-8	E235.SO4	0.3	mg/L	<0.30	----
<b>Anions and Nutrients (QCLot: 1195018)</b>						
Sulfate (as SO4)	14808-79-8	E235.SO4	0.3	mg/L	<0.30	----
<b>Anions and Nutrients (QCLot: 1195019)</b>						
Nitrate (as N)	14797-55-8	E235.NO3	0.02	mg/L	<0.020	----
<b>Anions and Nutrients (QCLot: 1195020)</b>						
Nitrite (as N)	14797-65-0	E235.NO2	0.01	mg/L	<0.010	----
<b>Anions and Nutrients (QCLot: 1195021)</b>						
Fluoride	16984-48-8	E235.F	0.02	mg/L	<0.020	----
<b>Anions and Nutrients (QCLot: 1195022)</b>						
Chloride	16887-00-6	E235.Cl	0.5	mg/L	<0.50	----
<b>Anions and Nutrients (QCLot: 1197454)</b>						
Ammonia, total (as N)	7664-41-7	E298	0.005	mg/L	<0.0050	----
<b>Anions and Nutrients (QCLot: 1197657)</b>						
Ammonia, total (as N)	7664-41-7	E298	0.005	mg/L	<0.0050	----
<b>Anions and Nutrients (QCLot: 1216788)</b>						
Phosphorus, total	7723-14-0	E372-S	0.001	mg/L	<0.0010	----
<b>Anions and Nutrients (QCLot: 1216789)</b>						
Phosphorus, total	7723-14-0	E372-S	0.001	mg/L	<0.0010	----
<b>Organic / Inorganic Carbon (QCLot: 1192634)</b>						
Carbon, dissolved organic [DOC]	----	E358-L	0.5	mg/L	<0.50	----
<b>Organic / Inorganic Carbon (QCLot: 1192635)</b>						
Carbon, dissolved organic [DOC]	----	E358-L	0.5	mg/L	<0.50	----
<b>Dissolved Metals (QCLot: 1191479)</b>						
Mercury, dissolved	7439-97-6	E509	0.000005	mg/L	<0.0000050	----
<b>Dissolved Metals (QCLot: 1191480)</b>						
Mercury, dissolved	7439-97-6	E509	0.000005	mg/L	<0.0000050	----
<b>Dissolved Metals (QCLot: 1197253)</b>						
Aluminum, dissolved	7429-90-5	E421	0.001	mg/L	<0.0010	----
Antimony, dissolved	7440-36-0	E421	0.0001	mg/L	<0.00010	----
Arsenic, dissolved	7440-38-2	E421	0.0001	mg/L	<0.00010	----
Barium, dissolved	7440-39-3	E421	0.0001	mg/L	<0.00010	----
Beryllium, dissolved	7440-41-7	E421	0.00002	mg/L	<0.000020	----
Bismuth, dissolved	7440-69-9	E421	0.00005	mg/L	<0.000050	----
Boron, dissolved	7440-42-8	E421	0.01	mg/L	<0.010	----



Sub-Matrix: **Water**

Analyte	CAS Number	Method	LOR	Unit	Result	Qualifier
<b>Dissolved Metals (QCLot: 1197253) - continued</b>						
Cadmium, dissolved	7440-43-9	E421	0.000005	mg/L	<0.0000050	----
Calcium, dissolved	7440-70-2	E421	0.05	mg/L	<0.050	----
Cesium, dissolved	7440-46-2	E421	0.00001	mg/L	<0.000010	----
Chromium, dissolved	7440-47-3	E421	0.0005	mg/L	<0.00050	----
Cobalt, dissolved	7440-48-4	E421	0.0001	mg/L	<0.00010	----
Copper, dissolved	7440-50-8	E421	0.0002	mg/L	<0.00020	----
Iron, dissolved	7439-89-6	E421	0.01	mg/L	<0.010	----
Lead, dissolved	7439-92-1	E421	0.00005	mg/L	<0.000050	----
Lithium, dissolved	7439-93-2	E421	0.001	mg/L	<0.0010	----
Magnesium, dissolved	7439-95-4	E421	0.005	mg/L	<0.0050	----
Manganese, dissolved	7439-96-5	E421	0.0001	mg/L	<0.00010	----
Molybdenum, dissolved	7439-98-7	E421	0.00005	mg/L	<0.000050	----
Nickel, dissolved	7440-02-0	E421	0.0005	mg/L	<0.00050	----
Phosphorus, dissolved	7723-14-0	E421	0.05	mg/L	<0.050	----
Potassium, dissolved	7440-09-7	E421	0.05	mg/L	<0.050	----
Rubidium, dissolved	7440-17-7	E421	0.0002	mg/L	<0.00020	----
Selenium, dissolved	7782-49-2	E421	0.00005	mg/L	<0.000050	----
Silicon, dissolved	7440-21-3	E421	0.05	mg/L	<0.050	----
Silver, dissolved	7440-22-4	E421	0.00001	mg/L	<0.000010	----
Sodium, dissolved	7440-23-5	E421	0.05	mg/L	<0.050	----
Strontium, dissolved	7440-24-6	E421	0.0002	mg/L	<0.00020	----
Sulfur, dissolved	7704-34-9	E421	0.5	mg/L	<0.50	----
Tellurium, dissolved	13494-80-9	E421	0.0002	mg/L	<0.00020	----
Thallium, dissolved	7440-28-0	E421	0.00001	mg/L	<0.000010	----
Thorium, dissolved	7440-29-1	E421	0.0001	mg/L	<0.00010	----
Tin, dissolved	7440-31-5	E421	0.0001	mg/L	<0.00010	----
Titanium, dissolved	7440-32-6	E421	0.0003	mg/L	<0.00030	----
Tungsten, dissolved	7440-33-7	E421	0.0001	mg/L	<0.00010	----
Uranium, dissolved	7440-61-1	E421	0.00001	mg/L	<0.000010	----
Vanadium, dissolved	7440-62-2	E421	0.0005	mg/L	<0.00050	----
Zinc, dissolved	7440-66-6	E421	0.001	mg/L	<0.0010	----
Zirconium, dissolved	7440-67-7	E421	0.0002	mg/L	<0.00020	----
<b>Dissolved Metals (QCLot: 1197254)</b>						
Aluminum, dissolved	7429-90-5	E421	0.001	mg/L	<0.0010	----
Antimony, dissolved	7440-36-0	E421	0.0001	mg/L	<0.00010	----



Sub-Matrix: **Water**

Analyte	CAS Number	Method	LOR	Unit	Result	Qualifier
<b>Dissolved Metals (QCLot: 1197254) - continued</b>						
Arsenic, dissolved	7440-38-2	E421	0.0001	mg/L	<0.00010	----
Barium, dissolved	7440-39-3	E421	0.0001	mg/L	<0.00010	----
Beryllium, dissolved	7440-41-7	E421	0.00002	mg/L	<0.000020	----
Bismuth, dissolved	7440-69-9	E421	0.00005	mg/L	<0.000050	----
Boron, dissolved	7440-42-8	E421	0.01	mg/L	<0.010	----
Cadmium, dissolved	7440-43-9	E421	0.000005	mg/L	<0.0000050	----
Calcium, dissolved	7440-70-2	E421	0.05	mg/L	<0.050	----
Cesium, dissolved	7440-46-2	E421	0.00001	mg/L	<0.000010	----
Chromium, dissolved	7440-47-3	E421	0.0005	mg/L	<0.00050	----
Cobalt, dissolved	7440-48-4	E421	0.0001	mg/L	<0.00010	----
Copper, dissolved	7440-50-8	E421	0.0002	mg/L	<0.00020	----
Iron, dissolved	7439-89-6	E421	0.01	mg/L	<0.010	----
Lead, dissolved	7439-92-1	E421	0.00005	mg/L	<0.000050	----
Lithium, dissolved	7439-93-2	E421	0.001	mg/L	<0.0010	----
Magnesium, dissolved	7439-95-4	E421	0.005	mg/L	<0.0050	----
Manganese, dissolved	7439-96-5	E421	0.0001	mg/L	<0.00010	----
Molybdenum, dissolved	7439-98-7	E421	0.00005	mg/L	<0.000050	----
Nickel, dissolved	7440-02-0	E421	0.0005	mg/L	<0.00050	----
Phosphorus, dissolved	7723-14-0	E421	0.05	mg/L	<0.050	----
Potassium, dissolved	7440-09-7	E421	0.05	mg/L	<0.050	----
Rubidium, dissolved	7440-17-7	E421	0.0002	mg/L	<0.00020	----
Selenium, dissolved	7782-49-2	E421	0.00005	mg/L	<0.000050	----
Silicon, dissolved	7440-21-3	E421	0.05	mg/L	<0.050	----
Silver, dissolved	7440-22-4	E421	0.00001	mg/L	<0.000010	----
Sodium, dissolved	7440-23-5	E421	0.05	mg/L	<0.050	----
Strontium, dissolved	7440-24-6	E421	0.0002	mg/L	<0.00020	----
Sulfur, dissolved	7704-34-9	E421	0.5	mg/L	<0.50	----
Tellurium, dissolved	13494-80-9	E421	0.0002	mg/L	<0.00020	----
Thallium, dissolved	7440-28-0	E421	0.00001	mg/L	<0.000010	----
Thorium, dissolved	7440-29-1	E421	0.0001	mg/L	<0.00010	----
Tin, dissolved	7440-31-5	E421	0.0001	mg/L	<0.00010	----
Titanium, dissolved	7440-32-6	E421	0.0003	mg/L	<0.00030	----
Tungsten, dissolved	7440-33-7	E421	0.0001	mg/L	<0.00010	----
Uranium, dissolved	7440-61-1	E421	0.00001	mg/L	<0.000010	----
Vanadium, dissolved	7440-62-2	E421	0.0005	mg/L	<0.00050	----



Sub-Matrix: **Water**

Analyte	CAS Number	Method	LOR	Unit	Result	Qualifier
<b>Dissolved Metals (QCLot: 1197254) - continued</b>						
Zinc, dissolved	7440-66-6	E421	0.001	mg/L	<0.0010	---
Zirconium, dissolved	7440-67-7	E421	0.0002	mg/L	<0.00020	---
<b>Aggregate Organics (QCLot: 1193619)</b>						
Chemical oxygen demand [COD]	---	E559-L	10	mg/L	<10	---
<b>Aggregate Organics (QCLot: 1193858)</b>						
Chemical oxygen demand [COD]	---	E559-L	10	mg/L	<10	---
<b>Aggregate Organics (QCLot: 1195266)</b>						
Chemical oxygen demand [COD]	---	E559-L	10	mg/L	<10	---
<b>Aggregate Organics (QCLot: 1197246)</b>						
Phenols, total (4AAP)	---	E562	0.001	mg/L	<0.0010	---
<b>Aggregate Organics (QCLot: 1197247)</b>						
Phenols, total (4AAP)	---	E562	0.001	mg/L	<0.0010	---
<b>Volatile Organic Compounds (QCLot: 1193705)</b>						
Benzene	71-43-2	E611A	0.5	µg/L	<0.50	---
Ethylbenzene	100-41-4	E611A	0.5	µg/L	<0.50	---
Styrene	100-42-5	E611A	0.5	µg/L	<0.50	---
Toluene	108-88-3	E611A	0.5	µg/L	<0.50	---
Xylene, m+p-	179601-23-1	E611A	0.4	µg/L	<0.40	---
Xylene, o-	95-47-6	E611A	0.3	µg/L	<0.30	---
<b>Volatile Organic Compounds (QCLot: 1194589)</b>						
Benzene	71-43-2	E611A	0.5	µg/L	<0.50	---
Ethylbenzene	100-41-4	E611A	0.5	µg/L	<0.50	---
Styrene	100-42-5	E611A	0.5	µg/L	<0.50	---
Toluene	108-88-3	E611A	0.5	µg/L	<0.50	---
Xylene, m+p-	179601-23-1	E611A	0.4	µg/L	<0.40	---
Xylene, o-	95-47-6	E611A	0.3	µg/L	<0.30	---
<b>Hydrocarbons (QCLot: 1191084)</b>						
F2 (C10-C16)	---	E601	100	µg/L	<100	---
<b>Hydrocarbons (QCLot: 1191215)</b>						
F2 (C10-C16)	---	E601	100	µg/L	<100	---
<b>Hydrocarbons (QCLot: 1193706)</b>						
F1 (C6-C10)	---	E581.F1	100	µg/L	<100	---
<b>Hydrocarbons (QCLot: 1194590)</b>						
F1 (C6-C10)	---	E581.F1	100	µg/L	<100	---







## Laboratory Control Sample (LCS) Report

A Laboratory Control Sample (LCS) is an analyte-free matrix that has been fortified (spiked) with test analytes at known concentration and processed in an identical manner to test samples. LCS results are expressed as percent recovery, and are used to monitor and control test method accuracy and precision, independent of test sample matrix.

Sub-Matrix: **Water**

					Laboratory Control Sample (LCS) Report				
Analyte	CAS Number	Method	LOR	Unit	Spike	Recovery (%)	Recovery Limits (%)		Qualifier
					Concentration	LCS	Low	High	
<b>Physical Tests (QCLot: 1194732)</b>									
Solids, total dissolved [TDS]	----	E162	10	mg/L	1000 mg/L	102	85.0	115	----
<b>Physical Tests (QCLot: 1196649)</b>									
pH	----	E108	----	pH units	7 pH units	100	98.0	102	----
<b>Physical Tests (QCLot: 1196650)</b>									
Conductivity	----	E100	1	µS/cm	146.9 µS/cm	106	90.0	110	----
<b>Physical Tests (QCLot: 1196651)</b>									
Alkalinity, total (as CaCO <sub>3</sub> )	----	E290	1	mg/L	500 mg/L	103	85.0	115	----
<b>Physical Tests (QCLot: 1197230)</b>									
pH	----	E108	----	pH units	7 pH units	100	98.0	102	----
<b>Physical Tests (QCLot: 1197231)</b>									
Conductivity	----	E100	1	µS/cm	146.9 µS/cm	107	90.0	110	----
<b>Physical Tests (QCLot: 1197232)</b>									
Alkalinity, total (as CaCO <sub>3</sub> )	----	E290	1	mg/L	500 mg/L	106	85.0	115	----
<b>Physical Tests (QCLot: 1197234)</b>									
Alkalinity, total (as CaCO <sub>3</sub> )	----	E290	1	mg/L	500 mg/L	107	85.0	115	----
<b>Physical Tests (QCLot: 1197235)</b>									
pH	----	E108	----	pH units	7 pH units	101	98.0	102	----
<b>Physical Tests (QCLot: 1197236)</b>									
Conductivity	----	E100	1	µS/cm	146.9 µS/cm	95.2	90.0	110	----
<b>Physical Tests (QCLot: 1197463)</b>									
Solids, total dissolved [TDS]	----	E162	10	mg/L	1000 mg/L	96.2	85.0	115	----
<b>Physical Tests (QCLot: 1199775)</b>									
Solids, total suspended [TSS]	----	E160	3	mg/L	150 mg/L	102	85.0	115	----
<b>Physical Tests (QCLot: 1200569)</b>									
Solids, total suspended [TSS]	----	E160	3	mg/L	150 mg/L	97.5	85.0	115	----
<b>Anions and Nutrients (QCLot: 1191618)</b>									
Kjeldahl nitrogen, total [TKN]	----	E318	0.05	mg/L	4 mg/L	102	75.0	125	----
<b>Anions and Nutrients (QCLot: 1191619)</b>									
Kjeldahl nitrogen, total [TKN]	----	E318	0.05	mg/L	4 mg/L	99.1	75.0	125	----
<b>Anions and Nutrients (QCLot: 1194700)</b>									
Fluoride	16984-48-8	E235.F	0.02	mg/L	1 mg/L	104	90.0	110	----



Sub-Matrix: **Water**

					Laboratory Control Sample (LCS) Report				
					Spike	Recovery (%)	Recovery Limits (%)		
Analyte	CAS Number	Method	LOR	Unit	Concentration	LCS	Low	High	Qualifier
<b>Anions and Nutrients (QCLot: 1194701)</b>									
Nitrate (as N)	14797-55-8	E235.NO3	0.02	mg/L	2.5 mg/L	103	90.0	110	----
<b>Anions and Nutrients (QCLot: 1194702)</b>									
Nitrite (as N)	14797-65-0	E235.NO2	0.01	mg/L	0.5 mg/L	96.1	90.0	110	----
<b>Anions and Nutrients (QCLot: 1194703)</b>									
Chloride	16887-00-6	E235.Cl	0.5	mg/L	100 mg/L	98.8	90.0	110	----
<b>Anions and Nutrients (QCLot: 1194704)</b>									
Sulfate (as SO4)	14808-79-8	E235.SO4	0.3	mg/L	100 mg/L	98.3	90.0	110	----
<b>Anions and Nutrients (QCLot: 1195018)</b>									
Sulfate (as SO4)	14808-79-8	E235.SO4	0.3	mg/L	100 mg/L	101	90.0	110	----
<b>Anions and Nutrients (QCLot: 1195019)</b>									
Nitrate (as N)	14797-55-8	E235.NO3	0.02	mg/L	2.5 mg/L	105	90.0	110	----
<b>Anions and Nutrients (QCLot: 1195020)</b>									
Nitrite (as N)	14797-65-0	E235.NO2	0.01	mg/L	0.5 mg/L	96.3	90.0	110	----
<b>Anions and Nutrients (QCLot: 1195021)</b>									
Fluoride	16984-48-8	E235.F	0.02	mg/L	1 mg/L	104	90.0	110	----
<b>Anions and Nutrients (QCLot: 1195022)</b>									
Chloride	16887-00-6	E235.Cl	0.5	mg/L	100 mg/L	99.7	90.0	110	----
<b>Anions and Nutrients (QCLot: 1197454)</b>									
Ammonia, total (as N)	7664-41-7	E298	0.005	mg/L	0.2 mg/L	102	85.0	115	----
<b>Anions and Nutrients (QCLot: 1197657)</b>									
Ammonia, total (as N)	7664-41-7	E298	0.005	mg/L	0.2 mg/L	102	85.0	115	----
<b>Anions and Nutrients (QCLot: 1216788)</b>									
Phosphorus, total	7723-14-0	E372-S	0.001	mg/L	0.05 mg/L	110	80.0	120	----
<b>Anions and Nutrients (QCLot: 1216789)</b>									
Phosphorus, total	7723-14-0	E372-S	0.001	mg/L	0.05 mg/L	111	80.0	120	----
<b>Organic / Inorganic Carbon (QCLot: 1192634)</b>									
Carbon, dissolved organic [DOC]	----	E358-L	0.5	mg/L	8.57 mg/L	94.0	80.0	120	----
<b>Organic / Inorganic Carbon (QCLot: 1192635)</b>									
Carbon, dissolved organic [DOC]	----	E358-L	0.5	mg/L	8.57 mg/L	85.6	80.0	120	----
Mercury, dissolved	7439-97-6	E509	0.000005	mg/L	0.0001 mg/L	107	80.0	120	----
Mercury, dissolved	7439-97-6	E509	0.000005	mg/L	0.0001 mg/L	103	80.0	120	----
<b>Dissolved Metals (QCLot: 1197253)</b>									
Aluminum, dissolved	7429-90-5	E421	0.001	mg/L	2 mg/L	113	80.0	120	----



Sub-Matrix: **Water**

					Laboratory Control Sample (LCS) Report				
					Spike	Recovery (%)	Recovery Limits (%)		
Analyte	CAS Number	Method	LOR	Unit	Concentration	LCS	Low	High	Qualifier
<b>Dissolved Metals (QCLot: 1197253) - continued</b>									
Antimony, dissolved	7440-36-0	E421	0.0001	mg/L	1 mg/L	104	80.0	120	----
Arsenic, dissolved	7440-38-2	E421	0.0001	mg/L	1 mg/L	101	80.0	120	----
Barium, dissolved	7440-39-3	E421	0.0001	mg/L	0.25 mg/L	95.6	80.0	120	----
Beryllium, dissolved	7440-41-7	E421	0.00002	mg/L	0.1 mg/L	100	80.0	120	----
Bismuth, dissolved	7440-69-9	E421	0.00005	mg/L	1 mg/L	99.8	80.0	120	----
Boron, dissolved	7440-42-8	E421	0.01	mg/L	1 mg/L	98.2	80.0	120	----
Cadmium, dissolved	7440-43-9	E421	0.000005	mg/L	0.1 mg/L	98.5	80.0	120	----
Calcium, dissolved	7440-70-2	E421	0.05	mg/L	50 mg/L	102	80.0	120	----
Cesium, dissolved	7440-46-2	E421	0.00001	mg/L	0.05 mg/L	103	80.0	120	----
Chromium, dissolved	7440-47-3	E421	0.0005	mg/L	0.25 mg/L	120	80.0	120	----
Cobalt, dissolved	7440-48-4	E421	0.0001	mg/L	0.25 mg/L	118	80.0	120	----
Copper, dissolved	7440-50-8	E421	0.0002	mg/L	0.25 mg/L	119	80.0	120	----
Iron, dissolved	7439-89-6	E421	0.01	mg/L	1 mg/L	# 121	80.0	120	MES
Lead, dissolved	7439-92-1	E421	0.00005	mg/L	0.5 mg/L	102	80.0	120	----
Lithium, dissolved	7439-93-2	E421	0.001	mg/L	0.25 mg/L	100	80.0	120	----
Magnesium, dissolved	7439-95-4	E421	0.005	mg/L	50 mg/L	113	80.0	120	----
Manganese, dissolved	7439-96-5	E421	0.0001	mg/L	0.25 mg/L	119	80.0	120	----
Molybdenum, dissolved	7439-98-7	E421	0.00005	mg/L	0.25 mg/L	100	80.0	120	----
Nickel, dissolved	7440-02-0	E421	0.0005	mg/L	0.5 mg/L	118	80.0	120	----
Phosphorus, dissolved	7723-14-0	E421	0.05	mg/L	10 mg/L	108	80.0	120	----
Potassium, dissolved	7440-09-7	E421	0.05	mg/L	50 mg/L	# 121	80.0	120	MES
Rubidium, dissolved	7440-17-7	E421	0.0002	mg/L	0.1 mg/L	103	80.0	120	----
Selenium, dissolved	7782-49-2	E421	0.00005	mg/L	1 mg/L	# 129	80.0	120	MES
Silicon, dissolved	7440-21-3	E421	0.05	mg/L	10 mg/L	97.6	80.0	120	----
Silver, dissolved	7440-22-4	E421	0.00001	mg/L	0.1 mg/L	98.3	80.0	120	----
Sodium, dissolved	7440-23-5	E421	0.05	mg/L	50 mg/L	# 122	80.0	120	MES
Strontium, dissolved	7440-24-6	E421	0.0002	mg/L	0.25 mg/L	98.3	80.0	120	----
Sulfur, dissolved	7704-34-9	E421	0.5	mg/L	50 mg/L	110	80.0	120	----
Tellurium, dissolved	13494-80-9	E421	0.0002	mg/L	0.1 mg/L	106	80.0	120	----
Thallium, dissolved	7440-28-0	E421	0.00001	mg/L	1 mg/L	103	80.0	120	----
Thorium, dissolved	7440-29-1	E421	0.0001	mg/L	0.1 mg/L	93.9	80.0	120	----
Tin, dissolved	7440-31-5	E421	0.0001	mg/L	0.5 mg/L	99.0	80.0	120	----
Titanium, dissolved	7440-32-6	E421	0.0003	mg/L	0.25 mg/L	111	80.0	120	----
Tungsten, dissolved	7440-33-7	E421	0.0001	mg/L	0.1 mg/L	103	80.0	120	----
Uranium, dissolved	7440-61-1	E421	0.00001	mg/L	0.005 mg/L	108	80.0	120	----
Vanadium, dissolved	7440-62-2	E421	0.0005	mg/L	0.5 mg/L	102	80.0	120	----



Sub-Matrix: **Water**

					Laboratory Control Sample (LCS) Report				
					Spike	Recovery (%)	Recovery Limits (%)		
Analyte	CAS Number	Method	LOR	Unit	Concentration	LCS	Low	High	Qualifier
<b>Dissolved Metals (QCLot: 1197253) - continued</b>									
Zinc, dissolved	7440-66-6	E421	0.001	mg/L	0.5 mg/L	115	80.0	120	----
Zirconium, dissolved	7440-67-7	E421	0.0002	mg/L	0.1 mg/L	97.6	80.0	120	----
<b>Dissolved Metals (QCLot: 1197254)</b>									
Aluminum, dissolved	7429-90-5	E421	0.001	mg/L	2 mg/L	111	80.0	120	----
Antimony, dissolved	7440-36-0	E421	0.0001	mg/L	1 mg/L	105	80.0	120	----
Arsenic, dissolved	7440-38-2	E421	0.0001	mg/L	1 mg/L	99.6	80.0	120	----
Barium, dissolved	7440-39-3	E421	0.0001	mg/L	0.25 mg/L	95.7	80.0	120	----
Beryllium, dissolved	7440-41-7	E421	0.00002	mg/L	0.1 mg/L	104	80.0	120	----
Bismuth, dissolved	7440-69-9	E421	0.00005	mg/L	1 mg/L	101	80.0	120	----
Boron, dissolved	7440-42-8	E421	0.01	mg/L	1 mg/L	102	80.0	120	----
Cadmium, dissolved	7440-43-9	E421	0.000005	mg/L	0.1 mg/L	97.0	80.0	120	----
Calcium, dissolved	7440-70-2	E421	0.05	mg/L	50 mg/L	101	80.0	120	----
Cesium, dissolved	7440-46-2	E421	0.00001	mg/L	0.05 mg/L	102	80.0	120	----
Chromium, dissolved	7440-47-3	E421	0.0005	mg/L	0.25 mg/L	119	80.0	120	----
Cobalt, dissolved	7440-48-4	E421	0.0001	mg/L	0.25 mg/L	117	80.0	120	----
Copper, dissolved	7440-50-8	E421	0.0002	mg/L	0.25 mg/L	117	80.0	120	----
Iron, dissolved	7439-89-6	E421	0.01	mg/L	1 mg/L	119	80.0	120	----
Lead, dissolved	7439-92-1	E421	0.00005	mg/L	0.5 mg/L	104	80.0	120	----
Lithium, dissolved	7439-93-2	E421	0.001	mg/L	0.25 mg/L	101	80.0	120	----
Magnesium, dissolved	7439-95-4	E421	0.005	mg/L	50 mg/L	113	80.0	120	----
Manganese, dissolved	7439-96-5	E421	0.0001	mg/L	0.25 mg/L	118	80.0	120	----
Molybdenum, dissolved	7439-98-7	E421	0.00005	mg/L	0.25 mg/L	102	80.0	120	----
Nickel, dissolved	7440-02-0	E421	0.0005	mg/L	0.5 mg/L	117	80.0	120	----
Phosphorus, dissolved	7723-14-0	E421	0.05	mg/L	10 mg/L	96.3	80.0	120	----
Potassium, dissolved	7440-09-7	E421	0.05	mg/L	50 mg/L	119	80.0	120	----
Rubidium, dissolved	7440-17-7	E421	0.0002	mg/L	0.1 mg/L	104	80.0	120	----
Selenium, dissolved	7782-49-2	E421	0.00005	mg/L	1 mg/L	# 130	80.0	120	MES
Silicon, dissolved	7440-21-3	E421	0.05	mg/L	10 mg/L	94.5	80.0	120	----
Silver, dissolved	7440-22-4	E421	0.00001	mg/L	0.1 mg/L	99.6	80.0	120	----
Sodium, dissolved	7440-23-5	E421	0.05	mg/L	50 mg/L	120	80.0	120	----
Strontium, dissolved	7440-24-6	E421	0.0002	mg/L	0.25 mg/L	98.9	80.0	120	----
Sulfur, dissolved	7704-34-9	E421	0.5	mg/L	50 mg/L	# 122	80.0	120	MES
Tellurium, dissolved	13494-80-9	E421	0.0002	mg/L	0.1 mg/L	108	80.0	120	----
Thallium, dissolved	7440-28-0	E421	0.00001	mg/L	1 mg/L	105	80.0	120	----
Thorium, dissolved	7440-29-1	E421	0.0001	mg/L	0.1 mg/L	99.8	80.0	120	----
Tin, dissolved	7440-31-5	E421	0.0001	mg/L	0.5 mg/L	98.8	80.0	120	----



Sub-Matrix: **Water**

					Laboratory Control Sample (LCS) Report				
					Spike	Recovery (%)	Recovery Limits (%)		
Analyte	CAS Number	Method	LOR	Unit	Concentration	LCS	Low	High	Qualifier
<b>Dissolved Metals (QCLot: 1197254) - continued</b>									
Titanium, dissolved	7440-32-6	E421	0.0003	mg/L	0.25 mg/L	114	80.0	120	----
Tungsten, dissolved	7440-33-7	E421	0.0001	mg/L	0.1 mg/L	102	80.0	120	----
Uranium, dissolved	7440-61-1	E421	0.00001	mg/L	0.005 mg/L	104	80.0	120	----
Vanadium, dissolved	7440-62-2	E421	0.0005	mg/L	0.5 mg/L	101	80.0	120	----
Zinc, dissolved	7440-66-6	E421	0.001	mg/L	0.5 mg/L	# 124	80.0	120	MES
Zirconium, dissolved	7440-67-7	E421	0.0002	mg/L	0.1 mg/L	99.5	80.0	120	----
<b>Aggregate Organics (QCLot: 1193619)</b>									
Chemical oxygen demand [COD]	----	E559-L	10	mg/L	100 mg/L	104	85.0	115	----
<b>Aggregate Organics (QCLot: 1193858)</b>									
Chemical oxygen demand [COD]	----	E559-L	10	mg/L	100 mg/L	108	85.0	115	----
<b>Aggregate Organics (QCLot: 1195266)</b>									
Chemical oxygen demand [COD]	----	E559-L	10	mg/L	100 mg/L	108	85.0	115	----
<b>Aggregate Organics (QCLot: 1197246)</b>									
Phenols, total (4AAP)	----	E562	0.001	mg/L	0.02 mg/L	97.4	85.0	115	----
<b>Aggregate Organics (QCLot: 1197247)</b>									
Phenols, total (4AAP)	----	E562	0.001	mg/L	0.02 mg/L	97.6	85.0	115	----
<b>Volatile Organic Compounds (QCLot: 1193705)</b>									
Benzene	71-43-2	E611A	0.5	µg/L	100 µg/L	80.2	70.0	130	----
Ethylbenzene	100-41-4	E611A	0.5	µg/L	100 µg/L	88.3	70.0	130	----
Styrene	100-42-5	E611A	0.5	µg/L	100 µg/L	91.6	70.0	130	----
Toluene	108-88-3	E611A	0.5	µg/L	100 µg/L	86.6	70.0	130	----
Xylene, m+p-	179601-23-1	E611A	0.4	µg/L	200 µg/L	94.7	70.0	130	----
Xylene, o-	95-47-6	E611A	0.3	µg/L	100 µg/L	98.1	70.0	130	----
<b>Volatile Organic Compounds (QCLot: 1194589)</b>									
Benzene	71-43-2	E611A	0.5	µg/L	100 µg/L	81.4	70.0	130	----
Ethylbenzene	100-41-4	E611A	0.5	µg/L	100 µg/L	85.4	70.0	130	----
Styrene	100-42-5	E611A	0.5	µg/L	100 µg/L	97.1	70.0	130	----
Toluene	108-88-3	E611A	0.5	µg/L	100 µg/L	84.1	70.0	130	----
Xylene, m+p-	179601-23-1	E611A	0.4	µg/L	200 µg/L	84.7	70.0	130	----
Xylene, o-	95-47-6	E611A	0.3	µg/L	100 µg/L	81.3	70.0	130	----
<b>Hydrocarbons (QCLot: 1191084)</b>									
F2 (C10-C16)	----	E601	100	µg/L	3820 µg/L	108	70.0	130	----
<b>Hydrocarbons (QCLot: 1191215)</b>									



Sub-Matrix: **Water**

					Laboratory Control Sample (LCS) Report				
					Spike	Recovery (%)	Recovery Limits (%)		
Analyte	CAS Number	Method	LOR	Unit	Concentration	LCS	Low	High	Qualifier
<b>Hydrocarbons (QCLot: 1191215) - continued</b>									
F2 (C10-C16)	----	E601	100	µg/L	3820 µg/L	104	70.0	130	----
<b>Hydrocarbons (QCLot: 1193706)</b>									
F1 (C6-C10)	----	E581.F1	100	µg/L	2750 µg/L	93.1	70.0	130	----
<b>Hydrocarbons (QCLot: 1194590)</b>									
F1 (C6-C10)	----	E581.F1	100	µg/L	2750 µg/L	77.8	70.0	130	----

### Qualifiers

Qualifier	Description
MES	Data Quality Objective was marginally exceeded (by < 10% absolute) for < 10% of analytes in a Multi-Element Scan / Multi-Parameter Scan (considered acceptable as per OMOE & CCME).



## Matrix Spike (MS) Report

A Matrix Spike (MS) is a randomly selected intra-laboratory replicate sample that has been fortified (spiked) with test analytes at known concentration, and processed in an identical manner to test samples. Matrix Spikes provide information regarding analyte recovery and potential matrix effects. MS DQO exceedances due to sample matrix may sometimes be unavoidable; in such cases, test results for the associated sample (or similar samples) may be subject to bias. ND – Recovery not determined, background level >= 1x spike level.

Sub-Matrix: **Water**

					Matrix Spike (MS) Report					
					Spike		Recovery (%)	Recovery Limits (%)		
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	Concentration	Target	MS	Low	High	Qualifier
<b>Anions and Nutrients (QCLot: 1191618)</b>										
EO2309480-001	Anonymous	Kjeldahl nitrogen, total [TKN]	----	E318	2.20 mg/L	2.5 mg/L	87.9	70.0	130	----
<b>Anions and Nutrients (QCLot: 1191619)</b>										
EO2309502-020	9 B.Lyons D.4	Kjeldahl nitrogen, total [TKN]	----	E318	ND mg/L	2.5 mg/L	ND	70.0	130	----
<b>Anions and Nutrients (QCLot: 1194700)</b>										
EO2309502-016	21 D.Lyons D.1	Fluoride	16984-48-8	E235.F	1.02 mg/L	1 mg/L	102	75.0	125	----
<b>Anions and Nutrients (QCLot: 1194701)</b>										
EO2309502-016	21 D.Lyons D.1	Nitrate (as N)	14797-55-8	E235.NO3	2.50 mg/L	2.5 mg/L	100	75.0	125	----
<b>Anions and Nutrients (QCLot: 1194702)</b>										
EO2309502-016	21 D.Lyons D.1	Nitrite (as N)	14797-65-0	E235.NO2	0.447 mg/L	0.5 mg/L	89.4	75.0	125	----
<b>Anions and Nutrients (QCLot: 1194703)</b>										
EO2309502-016	21 D.Lyons D.1	Chloride	16887-00-6	E235.Cl	94.4 mg/L	100 mg/L	94.4	75.0	125	----
<b>Anions and Nutrients (QCLot: 1194704)</b>										
EO2309502-016	21 D.Lyons D.1	Sulfate (as SO4)	14808-79-8	E235.SO4	94.5 mg/L	100 mg/L	94.5	75.0	125	----
<b>Anions and Nutrients (QCLot: 1195018)</b>										
EO2309506-008	Anonymous	Sulfate (as SO4)	14808-79-8	E235.SO4	ND mg/L	100 mg/L	ND	75.0	125	----
<b>Anions and Nutrients (QCLot: 1195019)</b>										
EO2309506-008	Anonymous	Nitrate (as N)	14797-55-8	E235.NO3	2.52 mg/L	2.5 mg/L	101	75.0	125	----
<b>Anions and Nutrients (QCLot: 1195020)</b>										
EO2309506-008	Anonymous	Nitrite (as N)	14797-65-0	E235.NO2	0.463 mg/L	0.5 mg/L	92.6	75.0	125	----
<b>Anions and Nutrients (QCLot: 1195021)</b>										
EO2309506-008	Anonymous	Fluoride	16984-48-8	E235.F	0.958 mg/L	1 mg/L	95.8	75.0	125	----
<b>Anions and Nutrients (QCLot: 1195022)</b>										
EO2309506-008	Anonymous	Chloride	16887-00-6	E235.Cl	78.9 mg/L	100 mg/L	78.9	75.0	125	----
<b>Anions and Nutrients (QCLot: 1197454)</b>										
EO2309480-001	Anonymous	Ammonia, total (as N)	7664-41-7	E298	ND mg/L	0.1 mg/L	ND	75.0	125	----
<b>Anions and Nutrients (QCLot: 1197657)</b>										
FC2303044-001	Anonymous	Ammonia, total (as N)	7664-41-7	E298	0.106 mg/L	0.1 mg/L	106	75.0	125	----





Sub-Matrix: Water

					Matrix Spike (MS) Report					
					Spike		Recovery (%)	Recovery Limits (%)		
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	Concentration	Target	MS	Low	High	Qualifier
<b>Anions and Nutrients (QCLot: 1216788)</b>										
EO2309502-002	2 Ewert D.1	Phosphorus, total	7723-14-0	E372-S	ND mg/L	0.067 mg/L	ND	70.0	130	----
<b>Anions and Nutrients (QCLot: 1216789)</b>										
EO2309502-022	DUP 01	Phosphorus, total	7723-14-0	E372-S	ND mg/L	0.067 mg/L	ND	70.0	130	----
<b>Organic / Inorganic Carbon (QCLot: 1192634)</b>										
EO2309502-001	1Booth D.1	Carbon, dissolved organic [DOC]	----	E358-L	ND mg/L	5 mg/L	ND	70.0	130	----
<b>Organic / Inorganic Carbon (QCLot: 1192635)</b>										
EO2309502-021	9A B.Lyons D.5	Carbon, dissolved organic [DOC]	----	E358-L	ND mg/L	5 mg/L	ND	70.0	130	----
<b>Dissolved Metals (QCLot: 1191479)</b>										
EO2309493-002	Anonymous	Mercury, dissolved	7439-97-6	E509	0.000108 mg/L	0.0001 mg/L	108	70.0	130	----
<b>Dissolved Metals (QCLot: 1191480)</b>										
EO2309502-014	21 Balash D.2	Mercury, dissolved	7439-97-6	E509	0.000107 mg/L	0.0001 mg/L	107	70.0	130	----
<b>Dissolved Metals (QCLot: 1197253)</b>										
EO2309502-002	2 Ewert D.1	Aluminum, dissolved	7429-90-5	E421	0.184 mg/L	0.2 mg/L	91.9	70.0	130	----
		Antimony, dissolved	7440-36-0	E421	0.0212 mg/L	0.02 mg/L	106	70.0	130	----
		Arsenic, dissolved	7440-38-2	E421	0.0196 mg/L	0.02 mg/L	97.8	70.0	130	----
		Barium, dissolved	7440-39-3	E421	ND mg/L	0.02 mg/L	ND	70.0	130	----
		Beryllium, dissolved	7440-41-7	E421	0.0445 mg/L	0.04 mg/L	111	70.0	130	----
		Bismuth, dissolved	7440-69-9	E421	0.00912 mg/L	0.01 mg/L	91.2	70.0	130	----
		Boron, dissolved	7440-42-8	E421	0.100 mg/L	0.1 mg/L	100	70.0	130	----
		Cadmium, dissolved	7440-43-9	E421	0.00380 mg/L	0.004 mg/L	94.9	70.0	130	----
		Calcium, dissolved	7440-70-2	E421	ND mg/L	4 mg/L	ND	70.0	130	----
		Cesium, dissolved	7440-46-2	E421	0.0103 mg/L	0.01 mg/L	103	70.0	130	----
		Chromium, dissolved	7440-47-3	E421	0.0378 mg/L	0.04 mg/L	94.4	70.0	130	----
		Cobalt, dissolved	7440-48-4	E421	0.0192 mg/L	0.02 mg/L	95.9	70.0	130	----
		Copper, dissolved	7440-50-8	E421	0.0186 mg/L	0.02 mg/L	93.2	70.0	130	----
		Iron, dissolved	7439-89-6	E421	1.99 mg/L	2 mg/L	99.5	70.0	130	----
		Lead, dissolved	7439-92-1	E421	0.0194 mg/L	0.02 mg/L	96.8	70.0	130	----
		Lithium, dissolved	7439-93-2	E421	0.104 mg/L	0.1 mg/L	104	70.0	130	----
		Magnesium, dissolved	7439-95-4	E421	ND mg/L	1 mg/L	ND	70.0	130	----
		Manganese, dissolved	7439-96-5	E421	ND mg/L	0.02 mg/L	ND	70.0	130	----
		Molybdenum, dissolved	7439-98-7	E421	0.0200 mg/L	0.02 mg/L	99.9	70.0	130	----
		Nickel, dissolved	7440-02-0	E421	0.0377 mg/L	0.04 mg/L	94.4	70.0	130	----
		Phosphorus, dissolved	7723-14-0	E421	10.0 mg/L	10 mg/L	100	70.0	130	----



Sub-Matrix: Water

					Matrix Spike (MS) Report					
					Spike		Recovery (%)	Recovery Limits (%)		
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	Concentration	Target	MS	Low	High	Qualifier
<b>Dissolved Metals (QCLot: 1197253) - continued</b>										
EO2309502-002	2 Ewert D.1	Potassium, dissolved	7440-09-7	E421	ND mg/L	4 mg/L	ND	70.0	130	----
		Rubidium, dissolved	7440-17-7	E421	0.0198 mg/L	0.02 mg/L	99.1	70.0	130	----
		Selenium, dissolved	7782-49-2	E421	0.0420 mg/L	0.04 mg/L	105	70.0	130	----
		Silicon, dissolved	7440-21-3	E421	9.46 mg/L	10 mg/L	94.6	70.0	130	----
		Silver, dissolved	7440-22-4	E421	0.00300 mg/L	0.004 mg/L	74.9	70.0	130	----
		Sodium, dissolved	7440-23-5	E421	ND mg/L	2 mg/L	ND	70.0	130	----
		Strontium, dissolved	7440-24-6	E421	ND mg/L	0.02 mg/L	ND	70.0	130	----
		Sulfur, dissolved	7704-34-9	E421	ND mg/L	20 mg/L	ND	70.0	130	----
		Tellurium, dissolved	13494-80-9	E421	0.0434 mg/L	0.04 mg/L	108	70.0	130	----
		Thallium, dissolved	7440-28-0	E421	0.00389 mg/L	0.004 mg/L	97.2	70.0	130	----
		Thorium, dissolved	7440-29-1	E421	0.0199 mg/L	0.02 mg/L	99.5	70.0	130	----
		Tin, dissolved	7440-31-5	E421	0.0196 mg/L	0.02 mg/L	97.8	70.0	130	----
		Titanium, dissolved	7440-32-6	E421	0.0393 mg/L	0.04 mg/L	98.3	70.0	130	----
		Tungsten, dissolved	7440-33-7	E421	0.0203 mg/L	0.02 mg/L	102	70.0	130	----
		Uranium, dissolved	7440-61-1	E421	0.00403 mg/L	0.004 mg/L	101	70.0	130	----
		Vanadium, dissolved	7440-62-2	E421	0.102 mg/L	0.1 mg/L	102	70.0	130	----
		Zinc, dissolved	7440-66-6	E421	0.370 mg/L	0.4 mg/L	92.6	70.0	130	----
		Zirconium, dissolved	7440-67-7	E421	0.0408 mg/L	0.04 mg/L	102	70.0	130	----
<b>Dissolved Metals (QCLot: 1197254)</b>										
EO2309502-022	DUP 01	Aluminum, dissolved	7429-90-5	E421	ND mg/L	0.2 mg/L	ND	70.0	130	----
		Antimony, dissolved	7440-36-0	E421	0.0205 mg/L	0.02 mg/L	102	70.0	130	----
		Arsenic, dissolved	7440-38-2	E421	0.0203 mg/L	0.02 mg/L	102	70.0	130	----
		Barium, dissolved	7440-39-3	E421	ND mg/L	0.02 mg/L	ND	70.0	130	----
		Beryllium, dissolved	7440-41-7	E421	0.0408 mg/L	0.04 mg/L	102	70.0	130	----
		Bismuth, dissolved	7440-69-9	E421	0.00902 mg/L	0.01 mg/L	90.2	70.0	130	----
		Boron, dissolved	7440-42-8	E421	0.100 mg/L	0.1 mg/L	100	70.0	130	----
		Cadmium, dissolved	7440-43-9	E421	0.00391 mg/L	0.004 mg/L	97.7	70.0	130	----
		Calcium, dissolved	7440-70-2	E421	ND mg/L	4 mg/L	ND	70.0	130	----
		Cesium, dissolved	7440-46-2	E421	0.00993 mg/L	0.01 mg/L	99.3	70.0	130	----
		Chromium, dissolved	7440-47-3	E421	0.0388 mg/L	0.04 mg/L	97.0	70.0	130	----
		Cobalt, dissolved	7440-48-4	E421	0.0196 mg/L	0.02 mg/L	98.0	70.0	130	----
		Copper, dissolved	7440-50-8	E421	0.0186 mg/L	0.02 mg/L	93.2	70.0	130	----
		Iron, dissolved	7439-89-6	E421	ND mg/L	2 mg/L	ND	70.0	130	----
		Lead, dissolved	7439-92-1	E421	0.0190 mg/L	0.02 mg/L	94.8	70.0	130	----
		Lithium, dissolved	7439-93-2	E421	0.0980 mg/L	0.1 mg/L	98.0	70.0	130	----



Sub-Matrix: Water

					Matrix Spike (MS) Report					
					Spike		Recovery (%)	Recovery Limits (%)		
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	Concentration	Target	MS	Low	High	Qualifier
<b>Dissolved Metals (QCLot: 1197254) - continued</b>										
EO2309502-022	DUP 01	Magnesium, dissolved	7439-95-4	E421	ND mg/L	1 mg/L	ND	70.0	130	----
		Manganese, dissolved	7439-96-5	E421	ND mg/L	0.02 mg/L	ND	70.0	130	----
		Molybdenum, dissolved	7439-98-7	E421	0.0189 mg/L	0.02 mg/L	94.7	70.0	130	----
		Nickel, dissolved	7440-02-0	E421	0.0380 mg/L	0.04 mg/L	95.0	70.0	130	----
		Phosphorus, dissolved	7723-14-0	E421	10.2 mg/L	10 mg/L	102	70.0	130	----
		Potassium, dissolved	7440-09-7	E421	ND mg/L	4 mg/L	ND	70.0	130	----
		Rubidium, dissolved	7440-17-7	E421	0.0202 mg/L	0.02 mg/L	101	70.0	130	----
		Selenium, dissolved	7782-49-2	E421	0.0412 mg/L	0.04 mg/L	103	70.0	130	----
		Silicon, dissolved	7440-21-3	E421	10.1 mg/L	10 mg/L	101	70.0	130	----
		Silver, dissolved	7440-22-4	E421	0.00388 mg/L	0.004 mg/L	96.9	70.0	130	----
		Sodium, dissolved	7440-23-5	E421	ND mg/L	2 mg/L	ND	70.0	130	----
		Strontium, dissolved	7440-24-6	E421	ND mg/L	0.02 mg/L	ND	70.0	130	----
		Sulfur, dissolved	7704-34-9	E421	20.4 mg/L	20 mg/L	102	70.0	130	----
		Tellurium, dissolved	13494-80-9	E421	0.0411 mg/L	0.04 mg/L	103	70.0	130	----
		Thallium, dissolved	7440-28-0	E421	0.00381 mg/L	0.004 mg/L	95.4	70.0	130	----
		Thorium, dissolved	7440-29-1	E421	0.0211 mg/L	0.02 mg/L	106	70.0	130	----
		Tin, dissolved	7440-31-5	E421	0.0194 mg/L	0.02 mg/L	97.0	70.0	130	----
		Titanium, dissolved	7440-32-6	E421	0.0485 mg/L	0.04 mg/L	121	70.0	130	----
		Tungsten, dissolved	7440-33-7	E421	0.0187 mg/L	0.02 mg/L	93.7	70.0	130	----
		Uranium, dissolved	7440-61-1	E421	0.00391 mg/L	0.004 mg/L	97.7	70.0	130	----
		Vanadium, dissolved	7440-62-2	E421	0.100 mg/L	0.1 mg/L	100	70.0	130	----
		Zinc, dissolved	7440-66-6	E421	0.378 mg/L	0.4 mg/L	94.6	70.0	130	----
		Zirconium, dissolved	7440-67-7	E421	0.0406 mg/L	0.04 mg/L	102	70.0	130	----
<b>Aggregate Organics (QCLot: 1193619)</b>										
EO2309455-020	Anonymous	Chemical oxygen demand [COD]	----	E559-L	112 mg/L	100 mg/L	112	75.0	125	----
<b>Aggregate Organics (QCLot: 1193858)</b>										
EO2309434-013	Anonymous	Chemical oxygen demand [COD]	----	E559-L	ND mg/L	100 mg/L	ND	75.0	125	----
<b>Aggregate Organics (QCLot: 1195266)</b>										
EO2309502-023	Dup 02	Chemical oxygen demand [COD]	----	E559-L	98 mg/L	100 mg/L	97.6	75.0	125	----
<b>Aggregate Organics (QCLot: 1197246)</b>										
EO2309440-073	Anonymous	Phenols, total (4AAP)	----	E562	0.0196 mg/L	0.02 mg/L	97.8	75.0	125	----
<b>Aggregate Organics (QCLot: 1197247)</b>										
EO2309502-010	15 Magneson D.6	Phenols, total (4AAP)	----	E562	0.0195 mg/L	0.02 mg/L	97.6	75.0	125	----



Sub-Matrix: **Water**

					Matrix Spike (MS) Report					
					Spike		Recovery (%)	Recovery Limits (%)		Qualifier
Laboratory sample ID	Client sample ID	Analyte	CAS Number	Method	Concentration	Target	MS	Low	High	
<b>Volatile Organic Compounds (QCLot: 1193705)</b>										
EO2309502-001	1Booth D.1	Benzene	71-43-2	E611A	83.6 µg/L	100 µg/L	83.6	50.0	140	----
		Ethylbenzene	100-41-4	E611A	92.3 µg/L	100 µg/L	92.3	50.0	140	----
		Styrene	100-42-5	E611A	94.6 µg/L	100 µg/L	94.6	50.0	140	----
		Toluene	108-88-3	E611A	85.0 µg/L	100 µg/L	85.0	50.0	140	----
		Xylene, m+p-	179601-23-1	E611A	181 µg/L	200 µg/L	90.5	50.0	140	----
		Xylene, o-	95-47-6	E611A	95.8 µg/L	100 µg/L	95.8	50.0	140	----
<b>Volatile Organic Compounds (QCLot: 1194589)</b>										
EO2309502-021	9A B.Lyons D.5	Benzene	71-43-2	E611A	83.7 µg/L	100 µg/L	83.7	50.0	140	----
		Ethylbenzene	100-41-4	E611A	84.0 µg/L	100 µg/L	84.0	50.0	140	----
		Styrene	100-42-5	E611A	89.8 µg/L	100 µg/L	89.8	50.0	140	----
		Toluene	108-88-3	E611A	80.8 µg/L	100 µg/L	80.8	50.0	140	----
		Xylene, m+p-	179601-23-1	E611A	161 µg/L	200 µg/L	80.6	50.0	140	----
		Xylene, o-	95-47-6	E611A	84.4 µg/L	100 µg/L	84.4	50.0	140	----

<b>Report To</b> Contact and company name below will appear on the final report		<b>Reports / Recipients</b>			<b>Turnaround Time (TAT) Requested</b>												
Company:	Tetra Tech	Select Report Format:	<input checked="" type="checkbox"/> PDF <input checked="" type="checkbox"/> EXCEL <input type="checkbox"/> EDD (DIGITAL) <i>ESDA</i> <input type="checkbox"/> Merge QC/QCI Reports with COA <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> N/A		<input checked="" type="checkbox"/> Routine [R] if received by 3pm M-F - no surcharges apply <input type="checkbox"/> 4 day [P4] if received by 3pm M-F - 20% rush surcharge n <input type="checkbox"/> 3 day [P3] if received by 3pm M-F - 25% rush surcharge n <input type="checkbox"/> 2 day [P2] if received by 3pm M-F - 50% rush surcharge n <input type="checkbox"/> 1 day [E] if received by 3pm M-F - 100% rush surcharge n <input type="checkbox"/> Same day [E2] if received by 10am M-S - 200% rush surch												
Contact:	Brent Finnestad	<input checked="" type="checkbox"/> Compare Results to Criteria on Report - provide details below if box checked Select Distribution: <input checked="" type="checkbox"/> EMAIL <input type="checkbox"/> MAIL <input type="checkbox"/> FAX			Additional fees may apply to rush requests on week <b>Date and Time Required for all E&amp;P TATs:</b>												
Phone:	780-718-9317	Email 1 or Fax Brent.Finnestad@TetraTech.com Email 2 Fahim.Nazari@TetraTech.com Email 3 Eba.Labdata@TetraTech.com			For all tests with rush TATs requested, please												
Company address below will appear on the final report		<b>Invoice Recipients</b>			<b>Analysis</b>												
Street:	14940 123 ave	Select Invoice Distribution:	<input checked="" type="checkbox"/> EMAIL <input type="checkbox"/> MAIL <input type="checkbox"/> FAX		Indicate Filtered (F), Preserved (P) or Filtered												
City/Province:	Edmonton Alberta	Email 1 or Fax Brent.Finnestad@TetraTech.com Email 2 Fahim.Nazari@TetraTech.com Email 3 Eba.Labdata@TetraTech.com			For all tests with rush TATs requested, please												
Postal Code:		<b>Project Information</b>			NUMBER OF CONTAINERS												
<b>Invoice To</b>	Same as Report To <input type="checkbox"/> YES <input type="checkbox"/> NO	Copy of Invoice with Report <input type="checkbox"/> YES <input type="checkbox"/> NO			Oil and Gas Required Fields (client use)												
Company:		ALS Account # / Quote #: 79533			AFE/Cost Center: PO#												
Contact:		Job #: 704-SWM.SWOP04810-01			Major/Minor Code: Routing Code:												
Project Information ALS Account # / Quote #: 79533 Job #: 704-SWM.SWOP04810-01 PO / AFE: 704-SWM.SWOP04810-01 LSD:		ALS Lab Work Order # (ALS use only): <i>E02309502</i>			Requisitioner: Location:												
ALS Lab Work Order # (ALS use only): <i>E02309502</i>		ALS Contact:			Sampler:												
ALS Sample # (ALS use only)	Sample Identification and/or Coordinates (This description will appear on the report)	Date (dd-mmm-yy)	Time (hh:mm)	Sample Type	Routine	BTEX F1 - F2	Dissolved Metals (including Mercury)	Total Dissolved Solids	Total Suspended Solids	Dissolved Organic Carbon	Nutrients	Chemical Oxygen Demand	Phenols	SAMPLES ON HOLD	EXTENDED STORAGE REQUIR	SUSPECTED HAZARD (see not	
	1 Booth D.1	16-Oct-23	1745	Surface	10	✓	✓	✓	✓	✓	✓	✓	✓				
	2 Ewert D.1		1620	Water													
	3 Ewert D.2		1645														
	4 Ewert D.3		1600														
	5 Ewert D.4		1700														
	10 Magneson D.1		1230														
	11 Magneson D.2		1330														
	13 Magneson D.4		1100														
	14 Magneson D.5		1300														
	15 Magneson D.6		1150														
	16 Beaver County D.1		1530														
	19 Winsnes D.1		1815														
<b>Drinking Water (DW) Samples<sup>1</sup> (client use)</b> Are samples taken from a Regulated DW System? <input type="checkbox"/> YES <input type="checkbox"/> NO Are samples for human consumption/ use? <input type="checkbox"/> YES <input type="checkbox"/> NO		Notes / Specify Limits for result evaluation by selecting from drop-down below (Excel COC only) <i>ESDAT format, Dissolved Metals is filtered but Not Preserved. Mercury -&gt; F/P.</i>			<b>SAMPLE RECEIPT DETAILS (ALS use only)</b> Cooling Method: <input type="checkbox"/> NONE <input type="checkbox"/> ICE <input checked="" type="checkbox"/> ICE PACKS <input type="checkbox"/> FROZEN <input type="checkbox"/> COOLING INITIATED Submission Comments identified on Sample Receipt Notification: <input type="checkbox"/> YES <input type="checkbox"/> NO Cooler Custody Seals Intact: <input type="checkbox"/> YES <input type="checkbox"/> N/A Sample Custody Seals Intact: <input type="checkbox"/> YES <input type="checkbox"/> N/A INITIAL COOLER TEMPERATURES °C: 58 6.2 78 5.9 FINAL COOLER TEMPERATURES °C:												
<b>SHIPMENT RELEASE (client use)</b> Released by: <i>Fahim Nazari</i> Date: <i>Oct-17-2023</i> Time: <i>15h</i>		<b>INITIAL SHIPMENT RECEPTION (ALS use only)</b> Received by: <i>VA</i> Date: <i>17-Oct-2023</i> Time: <i>3:36pm</i>			<b>FINAL SHIPMENT RECEPTION (ALS use only)</b> Received by: Date: Time:												

Environmental Division  
Edmonton  
Work Order Reference  
**E02309502**



Telephone : +1 780 413 5227

<b>Report To</b> Contact and company name below will appear on the final report		<b>Reports / Recipients</b>			<b>Turnaround Time (TAT) Requested</b>				<b>AFFIX ALS BARCODE LABEL HERE (ALS use only)</b>																																																																																																																																																																																																													
Company:	Tetra Tech	Select Report Format: <input checked="" type="checkbox"/> PDF <input checked="" type="checkbox"/> EXCEL <input type="checkbox"/> EDD (DIGITAL)			<input checked="" type="checkbox"/> Routine [R] if received by 3pm M-F - no surcharges apply <input type="checkbox"/> 4 day [P4] if received by 3pm M-F - 20% rush surcharge minimum <input type="checkbox"/> 3 day [P3] if received by 3pm M-F - 25% rush surcharge minimum <input type="checkbox"/> 2 day [P2] if received by 3pm M-F - 50% rush surcharge minimum <input type="checkbox"/> 1 day [E] if received by 3pm M-F - 100% rush surcharge minimum <input type="checkbox"/> Same day [E2] if received by 10am M-S - 200% rush surcharge.																																																																																																																																																																																																																	
Contact:	Brent Finnestad	Merge QC/QCI Reports with COA <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> N/A			Additional fees may apply to rush requests on weekends, statutory holidays and for non-routine tests.																																																																																																																																																																																																																	
Phone:	780-718-9317	<input checked="" type="checkbox"/> Compare Results to Criteria on Report - provide details below if box checked			Date and Time Required for all E&P TATs: _____																																																																																																																																																																																																																	
Company address below will appear on the final report		Select Distribution: <input checked="" type="checkbox"/> EMAIL <input type="checkbox"/> MAIL <input type="checkbox"/> FAX			For all tests with rush TATs requested, please contact your AM to confirm availability.																																																																																																																																																																																																																	
Street:	14940 123 ave	Email 1 or Fax Brent.Finnestad@TetraTech.com			<b>Analysis Request</b>																																																																																																																																																																																																																	
City/Province:	Edmonton Alberta	Email 2 Fahim.Nazari@TetraTech.com			Indicate Filtered (F), Preserved (P) or Filtered and Preserved (F/P) below																																																																																																																																																																																																																	
Postal Code:		Email 3 Eba.Labdata@TetraTech.com			<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th rowspan="2" style="writing-mode: vertical-rl; transform: rotate(180deg);">NUMBER OF CONTAINERS</th> <th colspan="7"></th> <th rowspan="2" style="writing-mode: vertical-rl; transform: rotate(180deg);">SAMPLES ON HOLD</th> <th rowspan="2" style="writing-mode: vertical-rl; transform: rotate(180deg);">EXTENDED STORAGE REQUIRED</th> <th rowspan="2" style="writing-mode: vertical-rl; transform: rotate(180deg);">SUSPECTED HAZARD (see notes)</th> </tr> <tr> <th>Routine</th> <th>BTEX F1 - F2</th> <th>Dissolved Metals (including Mercury)</th> <th>Total Dissolved Solids</th> <th>Total Suspended Solids</th> <th>Dissolved Organic Carbon</th> <th>Nutrients</th> <th>Chemical Oxygen Demand</th> <th>Phenols</th> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">X</td> <td></td> <td style="text-align: center;">F/P</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>							NUMBER OF CONTAINERS								SAMPLES ON HOLD	EXTENDED STORAGE REQUIRED	SUSPECTED HAZARD (see notes)	Routine	BTEX F1 - F2	Dissolved Metals (including Mercury)	Total Dissolved Solids	Total Suspended Solids	Dissolved Organic Carbon	Nutrients	Chemical Oxygen Demand	Phenols			X		F/P																																																																																																																																																																																		
NUMBER OF CONTAINERS								SAMPLES ON HOLD	EXTENDED STORAGE REQUIRED	SUSPECTED HAZARD (see notes)																																																																																																																																																																																																												
	Routine	BTEX F1 - F2	Dissolved Metals (including Mercury)	Total Dissolved Solids	Total Suspended Solids	Dissolved Organic Carbon	Nutrients				Chemical Oxygen Demand	Phenols																																																																																																																																																																																																										
		X		F/P																																																																																																																																																																																																																		
<b>Invoice To</b>		<b>Invoice Recipients</b>																																																																																																																																																																																																																				
Same as Report To <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO		Select Invoice Distribution: <input checked="" type="checkbox"/> EMAIL <input type="checkbox"/> MAIL <input type="checkbox"/> FAX																																																																																																																																																																																																																				
Copy of Invoice with Report <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO		Email 1 or Fax Brent.Finnestad@TetraTech.com																																																																																																																																																																																																																				
Company:		Email 2																																																																																																																																																																																																																				
Contact:		Email 3																																																																																																																																																																																																																				
<b>Project Information</b>				<b>Oil and Gas Required Fields (client use)</b>																																																																																																																																																																																																																		
ALS Account # / Quote #: 79533		AFE/Cost Center:		PO#																																																																																																																																																																																																																		
Job #: 704-SWM.SWOP04810-01		Major/Minor Code:		Routing Code:																																																																																																																																																																																																																		
PO / AFE: 704-SWM.SWOP04810-01		Requisitioner:																																																																																																																																																																																																																				
LSD:		Location:																																																																																																																																																																																																																				
ALS Lab Work Order # (ALS use only):				ALS Contact:		Sampler:																																																																																																																																																																																																																
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;">ALS Sample # (ALS use only)</th> <th style="width: 30%;">Sample Identification and/or Coordinates (This description will appear on the report)</th> <th style="width: 10%;">Date (dd-mmm-yy)</th> <th style="width: 10%;">Time (hh:mm)</th> <th style="width: 10%;">Sample Type</th> <th style="width: 10%;">Routine</th> <th style="width: 10%;">BTEX F1 - F2</th> <th style="width: 10%;">Dissolved Metals (including Mercury)</th> <th style="width: 10%;">Total Dissolved Solids</th> <th style="width: 10%;">Total Suspended Solids</th> <th style="width: 10%;">Dissolved Organic Carbon</th> <th style="width: 10%;">Nutrients</th> <th style="width: 10%;">Chemical Oxygen Demand</th> <th style="width: 10%;">Phenols</th> <th style="width: 10%;">SAMPLES ON HOLD</th> <th style="width: 10%;">EXTENDED STORAGE REQUIRED</th> <th style="width: 10%;">SUSPECTED HAZARD (see notes)</th> </tr> </thead> <tbody> <tr> <td></td> <td>20 Balash D.1</td> <td>16-oct-23</td> <td>1500</td> <td>Surface</td> <td>10</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>21 Balash D.2</td> <td>↓</td> <td>1415</td> <td>water</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>22 Balash D.3</td> <td>↓</td> <td>1430</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>23 D. Lyons D.1</td> <td>17-oct-23</td> <td>1245</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>6 B. Lyons D.1</td> <td>↓</td> <td>1030</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>7 B. Lyons D.2</td> <td>↓</td> <td>1045</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>8 B. Lyons D.3</td> <td>↓</td> <td>1115</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>9 B. Lyons D.4</td> <td>↓</td> <td>1140</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>9A B. Lyons D.5</td> <td>↓</td> <td>1200</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>DUP 01</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>DUP 02</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>											ALS Sample # (ALS use only)	Sample Identification and/or Coordinates (This description will appear on the report)	Date (dd-mmm-yy)	Time (hh:mm)	Sample Type	Routine	BTEX F1 - F2	Dissolved Metals (including Mercury)	Total Dissolved Solids	Total Suspended Solids	Dissolved Organic Carbon	Nutrients	Chemical Oxygen Demand	Phenols	SAMPLES ON HOLD	EXTENDED STORAGE REQUIRED	SUSPECTED HAZARD (see notes)		20 Balash D.1	16-oct-23	1500	Surface	10	✓	✓	✓	✓	✓	✓	✓	✓					21 Balash D.2	↓	1415	water														22 Balash D.3	↓	1430															23 D. Lyons D.1	17-oct-23	1245															6 B. Lyons D.1	↓	1030															7 B. Lyons D.2	↓	1045															8 B. Lyons D.3	↓	1115															9 B. Lyons D.4	↓	1140															9A B. Lyons D.5	↓	1200															DUP 01																	DUP 02															
ALS Sample # (ALS use only)	Sample Identification and/or Coordinates (This description will appear on the report)	Date (dd-mmm-yy)	Time (hh:mm)	Sample Type	Routine	BTEX F1 - F2	Dissolved Metals (including Mercury)	Total Dissolved Solids	Total Suspended Solids	Dissolved Organic Carbon	Nutrients	Chemical Oxygen Demand	Phenols	SAMPLES ON HOLD	EXTENDED STORAGE REQUIRED	SUSPECTED HAZARD (see notes)																																																																																																																																																																																																						
	20 Balash D.1	16-oct-23	1500	Surface	10	✓	✓	✓	✓	✓	✓	✓	✓																																																																																																																																																																																																									
	21 Balash D.2	↓	1415	water																																																																																																																																																																																																																		
	22 Balash D.3	↓	1430																																																																																																																																																																																																																			
	23 D. Lyons D.1	17-oct-23	1245																																																																																																																																																																																																																			
	6 B. Lyons D.1	↓	1030																																																																																																																																																																																																																			
	7 B. Lyons D.2	↓	1045																																																																																																																																																																																																																			
	8 B. Lyons D.3	↓	1115																																																																																																																																																																																																																			
	9 B. Lyons D.4	↓	1140																																																																																																																																																																																																																			
	9A B. Lyons D.5	↓	1200																																																																																																																																																																																																																			
	DUP 01																																																																																																																																																																																																																					
	DUP 02																																																																																																																																																																																																																					
<b>Drinking Water (DW) Samples<sup>1</sup> (client use)</b>				<b>Notes / Specify Limits for result evaluation by selecting from drop-down below (Excel COC only)</b>				<b>SAMPLE RECEIPT DETAILS (ALS use only)</b>																																																																																																																																																																																																														
Are samples taken from a Regulated DW System? <input type="checkbox"/> YES <input type="checkbox"/> NO				* Dissolved Metals is filtered but <u>Not</u> Preserved. Mercury → Filtered and preserved.				Cooling Method: <input type="checkbox"/> NONE <input type="checkbox"/> ICE <input type="checkbox"/> ICE PACKS <input type="checkbox"/> FROZEN <input type="checkbox"/> COOLING INITIATED																																																																																																																																																																																																														
Are samples for human consumption/ use? <input type="checkbox"/> YES <input type="checkbox"/> NO								Submission Comments identified on Sample Receipt Notification: <input type="checkbox"/> YES <input type="checkbox"/> NO																																																																																																																																																																																																														
								Cooler Custody Seals Intact: <input type="checkbox"/> YES <input type="checkbox"/> N/A Sample Custody Seals Intact: <input type="checkbox"/> YES <input type="checkbox"/> N/A																																																																																																																																																																																																														
								INITIAL COOLER TEMPERATURES °C		FINAL COOLER TEMPERATURES °C																																																																																																																																																																																																												
<b>SHIPMENT RELEASE (client use)</b>				<b>INITIAL SHIPMENT RECEPTION (ALS use only)</b>				<b>FINAL SHIPMENT RECEPTION (ALS use only)</b>																																																																																																																																																																																																														
Released by: Fahim Nazari		Date: Oct-17-2023		Time: 1510		Received by: LA		Date:		Time:		Received by:		Date:		Time:																																																																																																																																																																																																						

## APPENDIX D

### HISTORICAL DUGOUT CHEMICAL ANALYTICAL RESULTS

Table D.1: Chemical Analytical Results

Sample ID:		Booth D.1																										
Site Number:		1																										
Date Sampled:	Units	15-Oct-1996	3-Oct-1997	8-Oct-1998	20-Oct-1999	11-Oct-2000	24-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	70	40	50	70	50	40	60	50	40	55	61	50	69	65.5	59.4	75	92	78	71	219	68	77	98	84			
Ammonia-N	mg/L	<0.05	<0.05	<0.05	0.06	0.58	0.16	<0.05	<0.05	<0.05	<0.05	0.12	<0.05	<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	0.79	1.21	<0.050	0.565	<0.050			
Total Kjeldahl Nitrogen	mg/L	<0.2	0.6	1.6	1.8	1.5	2.4	1.8	1.7	1.8	1.8	1.8	1.7	2.5	1.84	2.1	2.89	2.55	2.76	2.76	7.02	3.09	2.58	4.70	2.51			
Total Organic Carbon	mg/L	16	15	19	17	17	16	22	17	21	21	21	19	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit												18	22.5	22.2	29.4	26.8	29.0	22.7	59.9	21.4	77	29.9	22.9			
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	0.0019	0.0075		
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F2 (>C10-C16)	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.10	<0.13	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>																												
Aluminium	mg/L	Not required under previous permit												<0.01	0.01	<0.010	<0.010	<0.010	0.013	<0.01	0.0035	0.0016	0.0031	0.0056	0.0021			
Antimony	mg/L	0.0007	0.0005	0.0009	0.0005	0.0007	0.0006	0.0009	0.0012	0.0024	0.0007	0.0009	0.0019	0.0005	<0.00040	<0.00040	<0.00040	<0.00040	0.00043	<0.0004	0.00077	0.0002	0.00024	0.00029	0.00020			
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.00703	0.00484
Barium	mg/L	0.033	0.025	0.03	0.032	0.051	0.049	0.025	0.039	0.018	0.033	0.079	0.075	0.073	0.0655	0.0731	0.0674	0.0518	0.0600	0.0673	0.0421	0.0883	0.0594	0.0714	0.0614			
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0020	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Boron	mg/L	Not required under previous permit												<0.05	<0.050	0.054	<0.050	<0.050	<0.050	<0.05	<0.020	0.064	0.045	0.049	0.047			
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050			
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Cobalt	mg/L	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.00092	0.00023	0.00034	0.00045			
Copper	mg/L	0.022	0.007	0.011	0.012	0.014	0.025	0.016	0.016	0.005	<0.001	0.001	<0.001	<0.001	<0.0010	0.0046	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	0.00040	0.00045	0.00054	0.00049	0.00053		
Iron	mg/L	0.120	0.328	0.445	0.572	0.403	0.126	0.181	0.577	0.081	0.077	0.212	0.175	0.022	0.02	0.018	0.029	<0.010	0.025	0.07	0.021	0.021	0.033	0.028	0.121			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	0.00011	<0.00010	<0.000050	0.000077	<0.000050	0.000072			
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0446	0.0327	
Manganese	mg/L	Not required under previous permit												0.003	0.005	<0.0020	<0.0020	<0.0020	0.0025	0.0024	0.154	0.00071	0.00744	0.00864	0.00250			
Mercury	mg/L	0.0007	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	0.000095	<0.000050	<0.000050	<0.000050			
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00244	0.00125	0.00111	0.000989	0.000853			
Nickel	mg/L	<0.002	<0.002	0.003	0.005	0.005	0.003	0.004	0.006	<0.002	<0.002	0.004	0.003	0.003	0.0035	0.0038	0.0047	0.0036	0.0035	0.0041	0.0060	0.0043	0.0034	0.00279	0.00353			
Selenium	mg/L	Not required under previous permit												<0.0004	<0.00080	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00045	0.000114	0.000115	0.000143	0.000115			
Silver	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.000020	<0.000010	<0.000010	<0.000010	<0.000010			
Thallium	mg/L	Not required under previous permit												0.0002	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.00010	<0.000020	<0.000010	<0.000010	<0.000010	<0.000010			
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00020	<0.00010	<0.00010	<0.00010	<0.00010			
Titanium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	0.0013	<0.001	<0.00060	<0.00030	<0.00032	<0.00049	0.00059			
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.000784	0.000578	
Vanadium	mg/L	Not required under previous permit												0.001	<0.0010	<0.0010	<0.0010	0.0017	0.0026	0.0015	0.0053	0.00087	0.00112	0.00135	0.00076			
Zinc	mg/L	0.293	0.256	0.106	0.055	0.117	0.099	0.011	0.026	0.054	0.002	0.005	0.011	0.008	<0.0020	<0.0020	<0.0020	0.0035	<0.0020	0.0119	0.0021	<0.0010	0.0021	<0.0010	<0.0010			
<b>Routine Water</b>																												
Ion Balance	%	100	108	101	101	102	102	98.5	104	102	104	101	99.2	98.8	95	109	88	91.9	104	110	96.7	107	95.5	107	103			
Bicarbonate	mg/L	299	283	324	302	330	345	210	164	215	299	311	342	340	291	334	425	383	333	342	552	357	396	345	328			
Chloride	mg/L	15.8	16.1	18.1	20.0	31.0	54.0	62	43	55	52	72	65	73	76	83.2	85.6	96.9	97.1	78.4	80.3	61.7	59.7	54.6	46.3			
Carbonate	mg/L	<5	<5	<5	<5	<5	<5	76	37	45	<5	<5	<5	12	29.3	15	11.7	28.7	36.1	11.2	24.6	<5.0	10.7	7.6	<5.0			
Conductivity (EC)	uS/cm	1080	986	903	956	1070	1260	1500	998	1150	898	951	944	987	1010	1100	1130	1180	1100	989	1560	885	893	845	714			
Calcium	mg/L	25.5	20.5	18.1	15.5	26.2	28.6	13.2	14.2	14.6	23	31.2	30.1	21.7	14.8	33.3	28	13.1	14.7	19.6	33.6	29	14.8	14.7	21.5			
Potassium	mg/L	7.6	7.2	7.8	7.8	11	10.5	12.3	9.6	9.3	9.7	12.3	10.6	10.9	12.2	11.7	9.26	11.8	12.9	12.2	17.9	13.9	12.3	15.1	12.5			
Magnesium	mg/L	14.0	10.8	11.3	10.4	14.3	17.1	18	11.7	12.7	11.4	12.9	12.3	14														



Table D.2: Chemical Analytical Results

Sample ID:		Ewert D.1																											
Site Number:		2																											
Date Sampled:	Units	16-Oct-1996	7-Oct-1997	9-Oct-1998	20-Oct-1999	11-Oct-2000	4-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	13-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019				
Chem. O <sub>2</sub> Demand	mg/L	40	50	100	90	50	90	90	80	40	85	55	68	70	103	67	81	81	80	79	131	83	122	53	79				
Ammonia-N	mg/L	1.65	0.36	0.8	<0.05	<0.05	0.28	<0.05	<0.05	<0.05	<0.05	1.64	<0.05	<0.05	0.207	<0.050	<0.050	0.198	<0.050	0.082	0.304	0.052	1.11	3.79	<0.050				
Total Kjeldahl Nitrogen	mg/L	3.3	2.7	3	2.5	1.7	0.9	3.9	4.8	2.7	2.2	3.9	2.3	2.4	5.8	3.52	2.66	3.15	3.13	2.95	6.65	3.06	7.29	5.64	2.70				
Total Organic Carbon	mg/L	17	24	23	19	19	31	37	29	23	31	20	24	-	-	-	-	-	-	-	-	-	-	-	-				
Dissolved Organic Carbon	mg/L	Not required under previous permit												18	29.1	31.7	20	24.8	24.9	23.4	37.2	24.3	122	21.6	22.2				
Phenols	mg/L	-																											
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																													
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Toluene	mg/L	-												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Ethylbenzene	mg/L	-												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Xylenes (m & p)	mg/L	-												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	-												-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	-												-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C <sub>7</sub> -C <sub>10</sub> )	mg/L	-												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C <sub>7</sub> -C <sub>10</sub> ) - BTEX	mg/L	-												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	-												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.10	<0.13	<0.10	<0.10	<0.10		
<b>Dissolved Metals</b>																													
Aluminium	mg/L	Not required under previous permit												<0.01	0.026	0.022	<0.010	<0.010	<0.010	<0.01	0.0167	0.0025	0.0151	0.0303	0.0349				
Antimony	mg/L	<0.0004	<0.0002	0.0005	<0.0004	0.0005	0.0009	0.0015	0.0015	0.0016	0.0015	0.0012	0.002	0.0005	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.0004	0.00043	0.00013	0.0003	0.00010	0.00025				
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.00165	0.0137
Barium	mg/L	0.051	0.075	0.064	0.111	0.078	0.075	0.131	0.155	0.155	0.041	0.088	0.071	0.057	0.048	0.0581	0.044	0.0789	0.0584	0.0826	0.0506	0.0699	0.0642	0.118	0.0449				
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	-												0.05	0.052	0.057	0.058	0.057	0.052	0.061	0.059	0.073	0.053	0.046	0.040				
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	0.0000099	0.0000059	0.0000083	<0.000050	0.0000070				
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.01	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00013	<0.00010	<0.00010	0.00011	<0.00010				
Cobalt	mg/L	<0.002	0.005	0.018	<0.002	<0.002	0.002	0.003	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.00060	0.00025	0.00064	0.00065	0.00062				
Copper	mg/L	0.132	0.008	0.014	0.016	0.011	0.028	0.021	0.027	0.007	0.004	0.003	0.005	0.001	0.0019	0.0037	<0.0010	<0.0010	<0.0010	<0.0010	0.00180	0.00360	0.00193	0.00081	0.00271				
Iron	mg/L	0.277	0.754	0.595	1.400	0.770	2.920	4.33	7.07	0.616	0.454	1.67	1.19	0.032	0.087	0.055	<0.030	0.027	0.098	0.031	0.062	0.012	0.052	0.166	0.077				
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	0.00018	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	0.000176	<0.000050	0.000098	0.000113	0.000076				
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.0263	0.0222	
Manganese	mg/L	-												0.002	0.0075	0.0096	<0.0050	<0.0020	0.0046	<0.002	0.00448	0.00161	0.0116	0.192	0.138				
Mercury	mg/L	<0.0002	<0.0004	0.0005	<0.0002	<0.0002	0.0009	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	0.0000052	0.0000081	<0.000050	<0.000050	<0.000050				
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	0.006	0.007	0.006	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00252	0.00142	0.000884	0.00136	0.00198				
Nickel	mg/L	<0.002	<0.002	0.018	0.01	0.004	0.004	0.01	0.013	<0.002	0.004	0.006	0.006	0.005	0.0047	0.0043	0.0026	0.0046	0.0027	0.0037	0.00581	0.00424	0.00243	0.00389	0.00321				
Selenium	mg/L	-												0.0005	0.00058	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.000347	0.000248	0.00025	0.000169	0.000258				
Silver	mg/L	-												<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010			
Thallium	mg/L	-												<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010			
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00010	<0.00010	<0.00010	<0.00011	<0.00010	<0.00010			
Titanium	mg/L	-												<0.001	0.0026	0.0027	<0.0010	<0.0010	<0.0010	<0.001	0.00118	<0.00030	0.00044	0.0029	0.00517				
Uranium	mg/L	-												-	-	-	-	-	-	-	-	-	-	-	-	-	0.00123	0.00138	
Vanadium	mg/L	-												<0.001	0.002	0.0012	<0.0010	<0.0010	<0.0010	<0.001	0.00286	<0.00050	0.00228	0.00067	0.00299				
Zinc	mg/L	<0.051	0.038	0.078	0.018	0.009	0.085	0.02	0.043	0.037	0.003	0.006	0.007	0.009	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.0074	0.0026	<0.0010	0.0057	<0.0010	0.0011				
<b>Routine Water</b>																													
Ion Balance	%	93	108	99	99	101	92.3	101	103	99.5	103	103	98.9	103	106	108	95.5	92.4	107	109	102	111	88.7	102	100				
Bicarbonate	mg/L	401	368	422	421	349	282	499	280	315	211	554	297	307	277	298	350	392	272	310	285	354	456	319	304				
Chloride	mg/L	11.5	12.7	10.7	15.0	13.0	18.0	27	26	13	12	13	13	16	14.8	13	20.8	20.4	32.0	23.7	27.2	31.5	31.3	30.8	32.9				
Carbonate	mg/L	<5	13	<5	<5	<5	41	41	111	<5	36	<5	12	20	32.6	18	21.2	10.3	18.6	14.3	15.8	6.6	12.7	8.2	38.3				
Conductivity (EC)	uS/cm	718	889	828	1050	1140	1170	1680	1410	656	519	554	653	734	662	662	692	727	597	648	622	759	851	758	675				
Calcium	mg/L	15.6	27.6	32.2	32.5	27.5	17.1	23.3	17.5	17.4	16	18.8	16.7	17.1	12.8	15.3	15.3	16.8	11.8	17.3	10.6	24.8	13.3	26.0	21.5				
Potassium	mg/L	15	17.4	17.6	17	19.5	13.8	22.5	14.8	13.9	9.6	14.1	12.2	13.4	13.8	13.6	14.6	15.5	17.7	17.8	14.4	19.2	18.5	19.9	16.0				
Magnesium	mg/L	8.5	14.4	12.9	14.8	14.5	9.7	18.1	11	8.7	7.0	9.4	8	9.9	7.34	8.72	10.6	9.01	10.8	10.3	5.81	12.9	12	12.8	10.2				
Sodium	mg/L	122	175	145	172	203																							

Table D.3: Chemical Analytical Results

Sample ID:		Ewert D.2																											
Site Number:		3																											
Date Sampled:	Units	16-Oct-1996	7-Oct-1997	9-Oct-1998	20-Oct-1999	11-Oct-2000	4-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	13-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019				
Chem. O <sub>2</sub> Demand	mg/L	40	50	70	90	50	60	70	30	30	49	53	67	65	54.7	55.2	62	77	53	61	158	61	88	127	92				
Ammonia-N	mg/L	0.69	<0.05	0.06	0.05	0.05	0.15	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.613	<0.050	<0.050	0.174	<0.050	<0.05	0.127	<0.05	<0.05	0.113	0.254				
Total Kjeldahl Nitrogen	mg/L	3.1	2.1	2.7	2.8	1.8	3.6	3.5	1.3	1.9	1.6	1.8	1.7	2.3	2.95	2.12	1.9	2.44	1.60	1.8	2.62	1.94	3.09	5.07	3.01				
Total Organic Carbon	mg/L	19	27	31	22	21	21	32	11	21	16	23	19	-	-	-	-	-	-	-	-	-	-	-	-				
Dissolved Organic Carbon	mg/L	Not required under previous permit													18	19.2	22.4	18	22.9	31.7	18.2	23.4	21	88	44.0	28.2			
Phenols	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	0.0018	0.0068		
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																													
Benzene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Ethylbenzene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Xylene (o)	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Xylenes	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071		
Styrene	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	-	
F1 (C6-C10)	mg/L	Not required under previous permit													<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit													<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 - (C10-C16)	mg/L	Not required under previous permit													<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.10	<0.13	<0.10	<0.10	
<b>Dissolved Metals</b>																													
Aluminum	mg/L	Not required under previous permit													0.01	0.02	<0.010	0.01	0.055	<0.010	<0.01	0.0055	0.0011	0.0045	0.0317	0.0334			
Antimony	mg/L	0.0004	<0.0002	0.0008	<0.0004	0.0005	0.0007	0.002	0.0011	0.0013	0.001	0.0010	0.0025	0.0004	<0.00040	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.0021	0.00015	0.00017	0.00038	0.00020			
Arsenic	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	0.00803	0.00619
Barium	mg/L	0.106	0.065	0.056	0.083	0.059	0.093	0.046	0.077	0.018	0.034	0.069	0.052	0.042	0.0452	0.0454	0.0361	0.0532	0.0540	0.0482	0.0511	0.041	0.0501	0.0439	0.0364				
Beryllium	mg/L	Not required under previous permit													<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	Not required under previous permit													<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	0.038	0.05	0.039	0.039	0.034			
Cadmium	mg/L	<0.001	<0.001	0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050				
Chromium	mg/L	0.005	<0.005	<0.005	<0.005	<0.005	0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050				
Cobalt	mg/L	0.003	0.005	0.022	<0.002	<0.002	0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.00036	0.00014	0.00053	0.00063	0.00061				
Copper	mg/L	0.008	<0.001	0.01	0.004	0.006	0.011	0.012	0.009	0.004	0.001	0.003	0.001	0.001	0.0014	0.0036	<0.0010	0.0016	<0.0010	<0.001	0.00063	0.00797	0.00111	0.00234	0.00127				
Iron	mg/L	7.200	1.060	1.510	1.980	1.280	4.770	1.28	3.04	0.216	0.452	1.13	0.734	0.046	0.043	0.085	0.073	0.098	0.046	0.032	0.083	0.045	0.056	0.054	0.256				
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	0.00072	<0.00050	<0.00050	0.00010	0.000164				
Lithium	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	0.0323	0.0261	
Manganese	mg/L	Not required under previous permit													0.003	<0.0020	<0.0020	<0.0050	0.0021	0.0067	<0.002	0.00205	0.00125	0.107	0.0131	0.00377			
Mercury	mg/L	<0.0002	<0.0004	0.0008	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.000050	0.000066	<0.000050	<0.000050				
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00108	0.00744	0.00491	0.0010	0.00761				
Nickel	mg/L	0.009	0.004	0.019	0.009	0.008	0.004	0.008	0.009	<0.002	0.004	0.007	0.006	0.005	0.0047	0.0065	0.0048	0.0053	0.0048	0.0034	0.0042	0.00457	0.00417	0.00423	0.00630				
Selenium	mg/L	Not required under previous permit													0.0005	0.00052	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.000243	0.000245	0.000184	0.000319	0.000366			
Silver	mg/L	Not required under previous permit													<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Thallium	mg/L	Not required under previous permit													<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Tin	mg/L	Not required under previous permit													<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	
Titanium	mg/L	Not required under previous permit													0.001	0.0013	<0.0010	<0.0010	0.003	<0.0010	<0.001	0.00034	<0.0003	0.00062	0.00375	0.00694			
Uranium	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	0.00159	0.000775
Vanadium	mg/L	Not required under previous permit													0.001	0.0019	<0.0010	<0.0010	0.0012	<0.0010	<0.001	0.00096	0.00072	0.00136	0.00513	0.00218			
Zinc	mg/L	0.028	0.025	0.027	0.019	0.014	0.039	0.011	0.016	0.066	0.002	0.006	0.008	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.006	0.0010	0.0020	0.0085	<0.0010	<0.0010				
<b>Routine Water</b>																													
Ion Balance	%	103	109	103	100	103	92.9	101	102	99.9	103	105	99.4	103	104	109	88.3	97.3	105	109	97.5	100	96.1	107	105				
Bicarbonate	mg/L	380	369	394	338	327	341	445	261	130	175	242	255	251	260	238	272	341	306	281	312	355	496	433	407				
Chloride	mg/L	12.5	14.3	11.8	13.0	10.0	14.0	22	9	15	10	12	13	16	21.4	10.5	10.3	13.7	15.5	13.2	18.0	31.3	36.3	35.7	33.3				
Carbonate	mg/L	<5	25	13	17	<5	14	51	17	111	15	<5	<5	19	9.4	7.9	8.7	7.5	8.8	11	8.2	5	15.8	11.9	<5.0				
Conductivity (EC)	uS/cm	845	926	869	900	941	1080	1610	852	1170	430	529	639	702	602	546	571	661	580	568	614	723	964	885	844				
Calcium	mg/L	15.9	19.2	29.8	16.6	29.8	27.9	16.2	17.4	13.9	17.7	22.5	21.5	17.1	13.8	20.9	15.3	12.9	21.5	19.1	16.0	28.2	28.6	17.1	25.8				
Potassium	mg/L	15.1	15.5	15.8	13.4	17	16.5	23.4	13.5	12	9.8	14.1	13.9	13.2	13	12.8	10.4	12.9	15.3	14.5	15.7	15.5	21.4	20.5	19.0				
Magnesium	mg/L	8.5	9.7	9.4	9.6	12.4	15.8	18.5	9.7	8.6	6.4	8.2	8.7	8.6	6.97	7.76	6.78	6.99	8.89	8.08	8.00	11.90	14.00	11.2	13.4				
Sodium	mg/L	174	201	182	16																								

Table D.4: Chemical Analytical Results

Sample ID:		Ewert D.3																										
Site Number:		4																										
Date Sampled:	Units	16-Oct-1996	7-Oct-1997	9-Oct-1998	20-Oct-1999	11-Oct-2000	4-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	13-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	50	60	50	70	60	80	70	50	40	43	48	82	83	77	62.5	81	72	53	30	117	74	51	78	106			
Ammonia-N	mg/L	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.845	<0.050	<0.050	2.15	<0.050	<0.05	0.785	0.641	<0.050	0.655	<0.050			
Total Kjeldahl Nitrogen	mg/L	2.7	1.8	2.1	2	1.8	3.9	4.6	3.9	3.1	1.5	1.5	2.3	2.9	3.38	2.08	2.66	4.3	2.04	1.88	5.40	3.84	2.55	3.31	3.22			
Total Organic Carbon	mg/L	19	21	21	18	23	26	29	17	24	15	19	25	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit													20	26.6	22.9	21	27.8	23.5	19.3	28.4	27.2	51	38.0	28.3		
Phenols	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	0.0018	0.0058	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	
Xylene (o)	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	
Xylenes	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	
F1 (C <sub>7</sub> -C <sub>10</sub> )	mg/L	Not required under previous permit													<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required under previous permit													<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required under previous permit													<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.10	<0.13	<0.10	
<b>Dissolved Metals</b>																												
Aluminum	mg/L	Not required under previous permit													<0.01	0.069	<0.010	<0.010	0.113	<0.010	<0.01	0.0024	0.0473	0.0052	0.0673	0.0107		
Antimony	mg/L	<0.0004	<0.0002	0.0007	<0.0004	0.0005	0.0005	0.001	0.0009	0.0014	0.0006	0.0014	0.0018	<0.0004	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.0018	0.0001	0.0001	0.0016	0.00016			
Arsenic	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	
Barium	mg/L	0.059	0.057	0.046	0.064	0.05	0.064	0.076	0.046	0.024	0.026	0.045	0.052	0.028	0.0629	0.0431	0.0261	0.0631	0.0330	0.0302	0.0300	0.0433	0.0288	0.0656	0.0418			
Beryllium	mg/L	Not required under previous permit													<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	Not required under previous permit													<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	0.029	0.044	0.018	0.035	0.039		
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.0010	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050			
Chromium	mg/L	<0.005	<0.005	n/a	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0010	0.0014	<0.0010	0.00017			
Cobalt	mg/L	<0.002	0.004	0.025	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.00039	0.00024	0.00046	0.00095	0.00036			
Copper	mg/L	0.002	<0.001	0.011	0.003	0.002	0.006	0.009	0.004	0.002	<0.001	<0.001	0.002	<0.001	<0.0010	0.0023	<0.0010	0.0012	<0.0010	<0.001	<0.00020	0.00661	0.0013	0.00163	0.00163			
Iron	mg/L	0.951	0.987	0.462	1.770	0.671	1.870	3.11	0.793	0.666	0.328	0.561	1.82	0.181	0.455	0.05	0.194	0.236	0.037	0.247	0.089	1.79	0.659	0.848	1.01			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	0.00019	<0.00010	<0.00010	<0.00050	<0.00010	<0.0001	<0.000050	0.000132	0.000168	0.000389	0.000211			
Lithium	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	
Manganese	mg/L	Not required under previous permit													0.008	0.0812	<0.0020	<0.0050	0.082	0.0027	<0.002	0.0025	0.00451	0.0477	0.194	0.00879		
Mercury	mg/L	<0.0002	0.0012	0.0007	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.000050	0.000069	<0.000050	<0.000050	<0.000050			
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.000746	0.000389	0.00046	0.000489				
Nickel	mg/L	<0.002	0.003	0.016	0.006	0.004	<0.002	0.006	0.005	<0.002	0.003	0.003	0.004	0.002	0.0039	0.0043	0.0025	0.0047	0.0024	<0.002	0.00122	0.00222	0.00281	0.00396	0.00281			
Selenium	mg/L	Not required under previous permit													<0.0004	<0.00080	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.000135	0.000153	0.000151	0.000192	0.000188		
Silver	mg/L	Not required under previous permit													<0.0001	<0.00010	<0.00010	<0.00010	<0.00050	<0.00010	<0.0001	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010		
Thallium	mg/L	Not required under previous permit													0.0001	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.0001	<0.000010	<0.000010	<0.000010	<0.000032	<0.000010		
Tin	mg/L	Not required under previous permit													<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Titanium	mg/L	Not required under previous permit													<0.001	0.0031	<0.0010	<0.0010	0.004	<0.0010	<0.001	<0.00030	0.00264	0.00083	0.00499	0.00168		
Uranium	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	-	
Vanadium	mg/L	Not required under previous permit													<0.001	<0.0010	<0.0010	<0.0010	0.0013	<0.0010	<0.001	0.00099	0.00102	0.00102	0.00193	0.00144		
Zinc	mg/L	0.011	0.02	0.019	0.007	0.002	0.043	0.017	0.007	0.036	0.002	0.004	0.007	0.015	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.0089	<0.0010	0.0024	0.0151	<0.0010			
<b>Routine Water</b>																												
Ion Balance	%	106	108	107	98	102	96.1	101	103	99.6	103	104	99	96.9	114	104	93.9	94.1	104	106	98.3	106	95.1	105	103			
Bicarbonate	mg/L	250	232	244	232	255	265	381	234	272	153	179	207	232	289	241	259	298	245	200	205	247	326	308	290			
Chloride	mg/L	9.7	15.2	9.8	13.0	12.0	13.0	20	7	11	14	21	25	30	33.3	25.4	52.2	63.1	51.5	32.9	65.3	51	55.8	64.6	56.2			
Carbonate	mg/L	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	12	<5.0	7.2	<5.0	<5.0	<5.0	<5	<5.0	<5.0	<5.0	<5.0				
Conductivity (EC)	uS/cm	462	480	476	488	523	543	860	403	545	277	363	460	488	577	506	608	682	547	448	568	549	679	708	622			
Calcium	mg/L	17.3	19.4	19.9	15.8	20.7	17.3	18.5	21.4	16.6	16.9	17.8	19.4	19.6	20.9	20.2	23.2	19.4	22.2	18.8	15.0	25.7	21.5	23.4	22.5			
Potassium	mg/L	16.2	13.4	15	12.9	16.3	15	18.6	13.1	12.9	9.8	13.0	12.9	13.1	14.9	14	12.7	15.7	16.4	15.8	17.1	15	14.9	22.0	14.2			
Magnesium	mg/L	6.8	8.1	8.6	7.7	8.9	9.5	10.7	7.6	6.9	5.8	7.2	7.8	8.7	9.31	7.68	9.81	9.67	10.3	7.96	8.28	10.5	9.48	10.9	10.7			
Sodium	mg/L	70	77	75	69	74	73	186	64	89	37	46	62	71	109	78.6	76.2	96.1	79.4	57.1								

Table D.5: Chemical Analytical Results

Sample ID:		Ewert D.4																										
Site Number:		5																										
Date Sampled:	Units	16-Oct-1996	7-Oct-1997	9-Oct-1998	20-Oct-1999	11-Oct-2000	4-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	30	40	50	80	60	60	60	50	40	103	123	82	78	98.5	69.6	66	95	67	79	109	30	102	86	92			
Ammonia-N	mg/L	<0.05	<0.05	0.042	<0.05	<0.05	0.06	0.06	<0.05	<0.05	<0.05	<0.05	<0.05	0.12	0.124	<0.050	0.055	0.103	0.098	<0.05	0.059	<0.050	<0.050	0.120	<0.050			
Total Kjeldahl Nitrogen	mg/L	1.5	1.2	2.7	2.3	1.7	3.1	3.4	2.1	3.1	4	5	6	2.9	4.74	3.2	2.8	3.17	2.82	2.25	3.33	2.88	3.48	2.91	3.61			
Total Organic Carbon	mg/L	16	17	21	19	18	23	31	20	23	35	48	26	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit												22	31.2	28	27.2	30.6	26.6	23	31.9	29.4	102	38.0	22.7			
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0015	0.0076	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071		
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10		
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.10	<0.13	<0.10	<0.10	0.77
<b>Dissolved Metals</b>																												
Aluminium	mg/L	Not required under previous permit												0.02	0.033	0.053	0.011	<0.010	<0.010	<0.01	0.0238	0.0013	0.0062	0.0194	0.0015			
Antimony	mg/L	<0.0004	<0.0002	0.0009	0.0004	0.0005	0.0006	0.0011	0.0011	0.0019	0.0011	0.002	0.003	0.0005	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00031	0.00018	0.00022	0.00025	0.00015			
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.0114	0.00313
Barium	mg/L	0.054	0.058	0.058	0.135	0.083	0.056	0.203	0.069	0.054	0.126	0.1	0.1	0.127	0.0772	0.0843	0.0335	0.0722	0.148	0.0639	0.0651	0.0524	0.0903	0.0588	0.0528			
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010		
Boron	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	0.035	0.046	0.04	0.050	0.042			
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.0010	<0.000050	<0.00005	<0.000050	<0.000050	<0.000050	0.0000196	<0.000050			
Chromium	mg/L	<0.005	<0.005	<0.005	0.007	<0.005	<0.005	0.008	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	<0.0010	<0.00010	<0.00010	<0.00010	<0.00010			
Cobalt	mg/L	<0.002	0.003	0.021	0.002	<0.002	<0.002	0.003	<0.002	<0.002	0.003	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.002	0.0010	0.00035	0.00051	0.00094	0.00043			
Copper	mg/L	0.003	<0.001	0.01	0.005	0.004	0.006	0.011	0.005	0.002	0.004	0.002	0.002	0.001	0.0017	0.0042	<0.0010	0.0017	0.0011	<0.001	0.00139	0.00084	0.00095	0.00102	0.00054			
Iron	mg/L	1.310	1.180	1.100	4.150	2.190	0.964	9.66	1.32	0.463	2.31	3.8	1.92	0.058	0.083	0.171	0.044	0.152	0.044	0.043	0.111	0.04	0.12	0.087	0.026			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00010	0.00019	<0.00010	<0.00050	<0.00010	<0.0001	0.000119	<0.000050	0.000096	0.00010	<0.00050			
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0247	0.016	
Manganese	mg/L	Not required under previous permit												0.004	0.0021	0.007	<0.0020	0.0024	<0.0020	<0.002	0.0038	0.00066	0.00532	0.00626	0.00080			
Mercury	mg/L	<0.0002	0.0009	0.0009	0.0003	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.000050	0.0000108	<0.000050	<0.000050	<0.000050			
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.007	<0.005	<0.005	<0.005	<0.005	<0.005	0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	0.00329	0.00216	0.00196	0.0019	0.00118			
Nickel	mg/L	0.003	<0.002	0.014	0.01	0.008	0.004	0.013	0.009	0.003	0.011	0.01	0.008	0.009	0.0066	0.0063	0.0056	0.0066	0.0079	0.0052	0.00487	0.00606	0.00687	0.00569	0.00406			
Selenium	mg/L	Not required under previous permit												0.0006	0.00056	0.00046	<0.00040	<0.00080	<0.00040	<0.0004	0.000372	0.000302	0.000271	0.000299	0.000217			
Silver	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.00050	<0.00010	<0.0001	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010			
Thallium	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.0001	<0.000010	<0.000010	<0.000010	0.000015	<0.000010			
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010			
Titanium	mg/L	Not required under previous permit												0.001	0.002	0.0037	<0.0010	0.0025	<0.0010	<0.001	0.00345	<0.00030	<0.00069	0.000219	<0.00030			
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.001	0.00602	
Vanadium	mg/L	Not required under previous permit												<0.001	0.001	0.0013	<0.0010	0.0014	<0.0010	<0.001	0.00294	<0.00050	<0.00050	0.00251	<0.00050			
Zinc	mg/L	0.007	0.018	0.023	0.012	0.007	0.052	0.023	0.004	0.05	0.02	0.005	0.009	0.003	<0.0020	<0.0020	<0.0020	0.002	<0.0020	0.0087	<0.0010	0.001	<0.0031	<0.0010	<0.0010			
<b>Routine Water</b>																												
Ion Balance	%	109	109	100	99	103	93.5	99.1	97	97	102	102	97.4	99.2	99.1	106	92	93.1	106	108	96.2	114	92.9	115	102			
Bicarbonate	mg/L	286	294	338	360	352	342	485	289	274	317	407	348	357	337	313	336	369	357	303	280	324	442	398	356			
Chloride	mg/L	4.2	4.3	3.4	6.0	6.0	9.0	14	12	16	18	28	20	23	21.7	19.7	15.2	19.4	21.4	15.2	18.5	17.5	19.4	21.7	18			
Carbonate	mg/L	25	17	<5	24	7	42	46	56	65	30	<5	<5	10	21.8	14.9	7	13.9	10.0	12.2	38.0	<5.0	7.2	<5.0	6.6			
Conductivity (EC)	uS/cm	645	601	565	682	658	735	974	735	711	598	700	602	637	627	606	613	666	668	587	627	599	742	713	624			
Calcium	mg/L	14	12.8	14.3	18.1	16.4	10.7	13.7	14.5	10.5	18.7	21.4	18.7	19.5	11.8	15.4	15.9	12.8	27.7	19.4	10.7	21.9	22	19.1	23.9			
Potassium	mg/L	6.7	5.6	7	7.2	7.6	7.2	8.1	6.4	9.7	11.2	17.6	12.8	11.4	10.4	9.43	10.2	10.1	14.3	12.8	13.4	13.3	15.5	14.8	14.5			
Magnesium	mg/L	6.8	7.5	7.4	9.0	9.0	10.0	11.9	7.6	8.5	10.4	12.5	10.2	10.8	9.7	8.85	10	7.97	13.1	11.1	9.75	12	13.4	13.3	13.3			
Sodium	mg/L	133	130	109	126	117	131	259	149</																			

Table D.6: Chemical Analytical Results

Sample ID:		Lyons D.1																									
Site Number:		6																									
Date Sampled:	Units	15-Oct-1996	3-Oct-1997	8-Oct-1998	20-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	13-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019		
Chem. O <sub>2</sub> Demand	mg/L	50	50	80	90	80	80	160	60	60	56	61	84	71	91.1	59.8	63	83	75	71	101	71	70	78	89		
Ammonia-N	mg/L	<0.05	<0.05	<0.05	0.08	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.0021	<0.05	<0.05	<0.050	0.155	0.202	0.252	<0.050	<0.05	0.053	1.35	<0.050	0.063	0.575		
Total Kjeldahl Nitrogen	mg/L	1.2	2	3.7	2.9	2.9	3.5	5.8	1.7	3.2	2	1.7	3.8	2.4	4.73	2.91	2.19	2.81	1.95	1.95	3.63	3.62	2.55	2.89	3.01		
Total Organic Carbon	mg/L	19	20	26	24	27	31	40	22	26	21	20	36	-	-	-	-	-	-	-	-	-	-	-	-		
Dissolved Organic Carbon	mg/L	Not required under previous permit												21	27.4	22.9	28.6	28.8	27.1	19.8	26.8	25	70	28.0	24.7		
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	0.0013	0.0087	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																											
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F2 (C10-C16)	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.13	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>																											
Aluminium	mg/L	Not required under previous permit												<0.01	0.012	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	0.0040	0.0962	0.0097	0.015	0.0306	
Antimony	mg/L	<0.0004	0.0006	0.0006	<0.0004	0.0006	0.0006	0.0008	0.001	0.0012	0.0012	0.0021	0.0012	<0.0004	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00025	0.00013	0.00014	0.00022	0.00017		
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.00522	0.00531
Barium	mg/L	0.052	0.058	0.066	0.085	0.078	0.082	0.105	0.015	0.046	0.023	0.044	0.075	0.053	0.0369	0.0554	0.0296	0.033	0.0623	0.0417	0.0472	0.0448	0.032	0.0495	0.0421		
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010
Boron	mg/L	Not required under previous permit												0.05	0.056	<0.050	<0.050	0.078	0.065	0.055	0.052	0.042	0.04	0.050	0.029		
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.0010	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	0.0000172	<0.000050		
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	<0.0010	0.0002	<0.0010	0.00011	0.0002		
Cobalt	mg/L	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.002	0.00050	0.0003	0.0004	0.00063	0.00038		
Copper	mg/L	0.002	<0.001	<0.001	0.003	0.002	0.004	0.009	0.023	0.002	0.002	0.001	0.003	<0.001	<0.0010	0.0073	0.0011	0.0013	<0.0010	<0.001	0.00065	0.00066	0.0006	0.00071	0.00063		
Iron	mg/L	<0.005	0.377	0.854	1.910	1.640	1.020	2.28	0.642	0.418	0.145	0.141	2.57	0.026	0.071	0.015	0.089	0.03	0.094	0.024	0.040	0.629	0.121	0.136	0.958		
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	0.000189	0.000056	0.000112	0.000229		
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	0.0136	0.0074	
Manganese	mg/L	Not required under previous permit												0.002	0.033	<0.0020	<0.0050	0.0023	0.0127	<0.002	0.00338	0.00586	0.0135	0.00866			
Mercury	mg/L	0.0003	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050		
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	0.000878	0.000596	0.000817	0.00112	0.00076		
Nickel	mg/L	0.002	<0.002	0.01	0.009	0.012	0.007	0.007	0.005	<0.002	0.003	0.005	0.009	0.006	0.004	0.0035	0.0035	0.0035	0.0038	0.0029	0.00278	0.00337	0.00397	0.00414	0.00361		
Selenium	mg/L	Not required under previous permit												0.0004	0.00042	<0.00040	<0.00040	<0.00080	<0.00040	<0.00040	<0.00040	<0.00040	0.000202	0.000194	0.000194	0.000273	0.000212
Silver	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Thallium	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Titanium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	0.0012	<0.001	0.00047	0.00568	0.00088	0.00113	0.00329		
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	0.000909	0.000234	
Vanadium	mg/L	Not required under previous permit												0.001	0.0018	<0.0010	0.0016	0.0026	0.0023	0.0011	0.00334	0.00241	0.0021	0.00256	0.0025	0.00205	
Zinc	mg/L	0.007	0.038	0.028	0.01	0.017	0.038	0.008	0.006	0.053	0.001	0.005	0.012	0.002	<0.0020	<0.0020	0.0027	<0.0020	<0.0020	0.0052	<0.0010	0.0012	0.0021	<0.0010	0.0016		
<b>Routine Water</b>																											
Ion Balance	%	98	106	108	100	109	106	99.9	106	103	105	103	104	104	91.6	103	96.2	94.4	97.3	106	96.3	104	94.3	110	101		
Bicarbonate	mg/L	334	314	361	359	338	427	510	281	452	211	259	207	271	287	257	304	291	311	224	213	277	281	270	217		
Chloride	mg/L	7.5	8.3	11.5	12.0	12.0	17.0	24	14	35	23	15	19	19	25.1	21.3	19.9	18.4	29.2	22.1	20.9	19.4	17.7	20.6	12.9		
Carbonate	mg/L	<5	<5	<5	5	5	17	25	48	8	<5	<5	<5	<5	5.4	5.7	5.1	5.4	7.9	6.7	22.2	<5.0	<5.0	<5.0	<5.0		
Conductivity (EC)	uS/cm	844	734	735	900	887	1110	1980	1450	1680	504	612	455	594	612	591	649	605	595	490	526	523	510	519	405		
Calcium	mg/L	33.8	29.3	30.1	29	29.8	47.8	33.3	44.6	44.9	28.3	29	18.8	27.1	18.6	22.1	22.5	17.5	23.4	22.4	16.7	21.2	20.1	22.3	18.6		
Potassium	mg/L	11.6	12.5	16.1	14.6	17.8	20.9	24.1	19.3	23.6	15.5	17.1	18	17.3	16.3	15.5	16.2	16	17.3	14.6	15.3	19.3	17.5	21.7	17.1		
Magnesium	mg/L	13.5	11.3	12.5	13.4	14.0	20.3	30.2	26.3	24.5	9.4	10.9	7.4	10.4	9.16	9.15	8.76	8.54	1								

Table D.7: Chemical Analytical Results

Sample ID:		Lyons D.2																										
Site Number:		7																										
Date Sampled:	Units	15-Oct-1996	3-Oct-1997	8-Oct-1998	20-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	13-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	60	70	80	110	70	90	100	60	60	56	95	80	72	75	55.6	77	71	71	84	103	80	64	70	83			
Ammonia-N	mg/L	<0.05	0.48	0.16	0.15	<0.05	<0.05	<0.05	0.51	0.24	<0.05	<0.05	<0.05	<0.05	0.267	<0.050	0.663	<0.050	<0.050	<0.05	0.051	0.685	<0.050	1.17	0.414			
Total Kjeldahl Nitrogen	mg/L	2.5	2.8	2.8	3.8	2.7	4.9	5.2	3.5	4.2	2	2.9	3.4	2.7	3.27	2.53	3.15	2.66	3.83	2.62	3.75	3.69	2.45	4.37	2.58			
Total Organic Carbon	mg/L	24	23	25	24	23	26	30	25	35	23	29	30	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit												20	25.9	20.5	30.4	25	25.2	21.5	27.4	26.9	64	25.0	23.4			
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0018	0.0075	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes (mg/L)	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 (C10-C16)	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.13	<0.10	<0.10	<0.10	
<b>Dissolved Metals</b>																												
Aluminum	mg/L	Not required under previous permit												<0.01	<0.010	<0.010	0.027	<0.010	0.015	<0.01	0.0070	0.0058	0.0096	0.0643	0.0613			
Antimony	mg/L	<0.0004	<0.0004	0.0037	<0.0004	0.0005	0.0005	0.0013	0.0013	0.0014	0.0017	0.0013	0.002	<0.0004	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00023	0.00013	0.00015	0.00021	0.00012			
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.00407	0.00497
Barium	mg/L	0.057	0.073	0.049	0.095	0.071	0.08	0.068	0.069	0.047	0.031	0.039	0.045	0.044	0.0588	0.041	0.0504	0.0469	0.0291	0.0503	0.0403	0.0263	0.0364	0.0655	0.0649			
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	0.056	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	0.053	0.026	0.037	0.044	0.022
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.0010	<0.000050	<0.000050	<0.000050	<0.000050	0.0000098	<0.000050	<0.000050			
Chromium	mg/L	<0.005	<0.005	<0.005	0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.00010	0.00017	<0.00010	0.00028	0.00018			
Cobalt	mg/L	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.00026	0.00029	0.00048	0.00079	0.00049			
Copper	mg/L	0.004	0.004	0.003	0.009	0.004	0.008	0.013	0.035	0.004	0.003	0.002	0.001	0.001	0.0018	0.0034	<0.0010	0.0013	0.0012	<0.001	0.00071	0.00073	0.00091	0.00116	0.00083			
Iron	mg/L	<0.005	0.837	0.680	2.430	0.680	1.480	1.64	0.601	0.113	0.122	0.215	0.547	0.056	0.044	0.023	0.839	0.016	0.028	0.036	0.013	0.268	0.083	0.275	1.51			
Lead	mg/L	<0.005	<0.005	<0.005	0.95	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00010	<0.00010	0.00032	<0.0050	<0.00010	<0.0001	<0.000050	<0.000050	0.00015	0.000218	0.000281			
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0137	0.0071	
Manganese	mg/L	Not required under previous permit												0.02	0.0318	<0.0020	0.0075	0.0055	0.0028	0.0026	0.0031	0.00297	0.0198	0.122	0.0361			
Mercury	mg/L	0.0003	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	0.000007	<0.000050	<0.000050	<0.000050			
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.000755	0.000696	0.000893	0.00102	0.00063			
Nickel	mg/L	0.003	<0.002	0.007	0.007	0.005	0.005	0.006	0.006	<0.002	0.004	0.005	0.004	0.004	0.0042	0.0038	0.0043	0.0034	0.0030	0.0027	0.00433	0.00433	0.00483	0.00453	0.00341			
Selenium	mg/L	Not required under previous permit												0.0005	0.00041	<0.00040	<0.00040	<0.00080	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	
Silver	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.0050	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Thallium	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	
Titanium	mg/L	Not required under previous permit												0.001	<0.0010	<0.0010	0.0028	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	0.00052	0.000545	0.00488	
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.000787	0.000266
Vanadium	mg/L	Not required under previous permit												0.002	0.0027	0.0022	0.0022	0.0022	0.002	0.0022	0.001	0.00394	0.00253	0.00196	0.0023	0.0026		
Zinc	mg/L	0.012	0.033	0.03	0.007	0.009	0.068	0.009	0.017	0.046	0.002	0.007	0.006	0.014	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.0054	<0.0010	0.0026	0.0122	<0.0010	0.0018		
<b>Routine Water</b>																												
Ion Balance	%	107	104	107	99	104	96.7	99.9	106	101	103	103	95.9	102	104	106	96.6	98.5	108	106	96.6	101	94.1	109	97.4			
Bicarbonate	mg/L	300	318	351	326	348	372	406	386	346	308	288	250	289	318	257	254	354	300	270	279	222	296	278	232			
Chloride	mg/L	9.9	11.7	15.3	15.0	15.0	20.0	23	24	30	27	28	19	24	23.7	25	14.1	24.3	32.8	26.9	28.6	11.8	20	21.4	15.6			
Carbonate	mg/L	<5	<5	<5	7	7	35	48	38	58	5	13	<5	13	21.5	33.7	<5.0	12.3	10.9	13.8	14.6	<5.0	<5.0	<5.0	<5.0			
Conductivity (EC)	uS/cm	600	650	643	721	791	963	1120	1120	1300	772	738	478	657	759	799	505	737	653	590	604	408	525	536	435			
Calcium	mg/L	25.6	25.7	25.6	23.8	30.5	43.6	25.4	30.4	28.6	29	25.9	19	28.4	32.7	26.1	20.6	25.6	28.1	19.1	22.2	15.5	19.3	22.5	17.4			
Potassium	mg/L	20	18.5	23.1	20.5	23.1	26.3	29.9	28.2	26	22.1	22.3	19.7	20.7	23.4	22.7	14.1	21.5	18.6	17	19.0	15.2	18.9	21.8	18.5			
Magnesium	mg/L	8.3																										

Table D.8: Chemical Analytical Results

Sample ID:		Lyons D.3																										
Site Number:		8																										
Date Sampled:	Units	15-Oct-1996	3-Oct-1997	8-Oct-1998	20-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	13-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	40	100	70	100	90	110	230	80	60	66	92	78	105	110	64.1	86	108	67	127	150	149	232	171	105			
Ammonia-N	mg/L	0.05	0.74	<0.05	<0.05	0.31	<0.05	0.11	<0.05	<0.05	<0.05	<0.05	0.14	<0.05	<0.050	0.133	0.264	0.434	<0.050	0.08	0.256	0.099	0.082	0.186	<0.050			
Total Kjeldahl Nitrogen	mg/L	2.7	4.7	2.7	3	3.2	6.5	22.2	2.8	2.7	2.4	2.9	3.5	3.9	5.64	2.98	3.48	4.78	2.39	5.93	5.61	6.45	9.34	8.83	3.66			
Total Organic Carbon	mg/L	19	36	27	30	34	42	151	27	29	26	32	33	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit													31	41.8	24.5	30.4	34.9	29.5	27.6	47.3	35.8	232	41.4	30.9		
Phenols	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	0.0021	0.0137
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Xylenes (m & p)	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylene (o)	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit													<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C <sub>9</sub> -C <sub>10</sub> )	mg/L	Not required under previous permit													<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C <sub>9</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required under previous permit													<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required under previous permit													<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.10	<0.13	<0.10	<0.10
<b>Dissolved Metals</b>																												
Aluminium	mg/L	Not required under previous permit													0.82	0.104	<0.010	0.471	0.095	0.036	0.014	0.0507	0.0166	0.0196	0.0563	0.0192		
Antimony	mg/L	0.0006	0.0006	0.0008	<0.0004	0.0006	0.0006	0.0021	0.0011	0.0014	0.001	0.0014	0.0033	0.0007	0.00046	<0.00040	<0.00040	<0.00080	<0.00040	0.00052	0.00076	0.00043	0.00054	0.00096	0.0003			
Arsenic	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	0.00277	0.00261
Barium	mg/L	0.117	0.136	<0.003	0.095	0.116	0.159	0.26	0.091	0.077	0.085	0.111	0.146	0.058	0.0835	0.0733	0.0607	0.105	0.0416	0.0408	0.119	0.0567	0.0797	0.108	0.0461			
Beryllium	mg/L	Not required under previous permit													<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	Not required under previous permit													<0.05	<0.050	0.055	<0.050	<0.050	<0.050	0.061	0.052	0.068	0.079	0.035	0.027		
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.00010	<0.000050	<0.000050	0.000062	0.0000078	0.0000064	0.000031	0.000068			
Chromium	mg/L	0.012	0.006	<0.005	<0.005	<0.005	0.017	<0.005	<0.005	<0.005	<0.005	<0.005	0.011	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	<0.00010	0.00015	<0.00010	0.00058	0.00010			
Cobalt	mg/L	0.003	<0.002	<0.002	<0.002	0.003	0.003	0.01	<0.002	<0.002	<0.002	<0.002	0.004	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.0023	0.00100	0.00123	0.00182	0.00183	0.00161			
Copper	mg/L	0.008	0.004	0.001	0.004	0.004	0.009	0.032	0.016	0.004	0.004	0.004	0.01	0.003	0.0031	0.0062	0.0033	0.0033	0.0028	0.0031	0.00334	0.0046	0.00427	0.00582	0.00484			
Iron	mg/L	8.390	8.430	0.006	1.530	3.600	4.340	15.9	1.56	1.46	2.32	1.6	9.23	0.653	0.194	0.057	0.537	0.114	0.032	0.039	0.030	0.025	0.021	0.046	0.064			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.006	<0.005	<0.005	<0.005	<0.005	<0.005	0.0004	0.00015	<0.00010	0.00029	<0.00050	<0.00010	<0.0001	<0.000050	<0.0000050	<0.000050	0.000076	0.000051			
Lithium	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	0.028	0.0166
Manganese	mg/L	Not required under previous permit													0.035	0.0062	0.0089	0.0088	0.0195	0.0021	0.0174	0.00259	0.00127	0.00254	0.00185	0.00279		
Mercury	mg/L	0.0002	0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.0000050	0.0000051	<0.0000050	<0.0000050	<0.0000050			
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	0.007	0.023	<0.005	<0.005	<0.005	<0.005	0.006	0.006	<0.0050	<0.0050	<0.0050	0.0087	0.0062	0.007	0.0116	0.00669	0.00966	0.0144	0.00452			
Nickel	mg/L	0.01	0.012	<0.002	0.01	0.015	0.017	0.04	0.013	0.004	0.008	0.011	0.021	0.012	0.0093	0.0106	0.0093	0.0128	0.0089	0.0128	0.0135	0.0135	0.0133	0.0151	0.0112			
Selenium	mg/L	Not required under previous permit													0.0012	0.00117	0.00072	0.00067	0.00085	0.00067	0.00084	0.000916	0.00106	0.00113	0.000684			
Silver	mg/L	Not required under previous permit													<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Thallium	mg/L	Not required under previous permit													<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Tin	mg/L	Not required under previous permit													<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Titanium	mg/L	Not required under previous permit													0.032	0.0065	<0.0010	0.0168	0.0057	0.0022	0.0019	0.00143	0.00098	0.00045	0.0040	0.00244		
Uranium	mg/L	Not required under previous permit													-	-	-	-	-	-	-	-	-	-	-	-	0.01	0.00318
Vanadium	mg/L	Not required under previous permit													0.003	0.0035	<0.0010	0.0034	<0.0010	0.0018	0.0028	0.00110	0.0016	0.00149	0.00126	0.00110		
Zinc	mg/L	0.037	0.036	0.005	0.006	0.034	0.098	0.049	0.013	0.061	0.007	0.007	0.032	0.017	<0.0020	<0.0020	0.0024	<0.0020	<0.0020	0.0069	<0.0010	<0.0010	<0.0010	<0.0010	0.0017			
<b>Routine Water</b>																												
Ion Balance	%	99	106	110	101	104	109	101	103	98.4	106	103	102	94.6	98.4	108	95	96.9	102	110	95.3	112	95.2	113	103			
Bicarbonate	mg/L	335	383	391	405	446	503	872	387	329	339	314	357	393	386	329	380	389	376	339	474	353	516	409	413			
Chloride	mg/L	11.7	22.5	14.0	16.0	19.0	32.0	120	29	21	17	23	23	29	25.1	27.4	20.8	37.8	21.5	20.4	34.0	25.7	34.7	48.4	22.3			
Carbonate	mg/L	<5	<5	<5	19	<5	27	196	13	17	<5	<5	<5	13	32.3	17.2	7.4	7.8	20.4	25.8	13.5	7.7	24.6	12.7	14.5			
Conductivity (EC)	uS/cm	810	689	717	897	998	1440	2980	913	760	628	693	673	781	782	807	733	948	815	937	1210	855	1230	1420	978			
Calcium	mg/L	17.7	22.5	20.8	19.6	30.1	30.6	12.8	32.3	18.3	20.8	25.4	26	24.4	17.6	42.4	24.2	17	28.6	33.2	24.4	42.4	33.3	37.6	41.3			
Potassium	mg/L	7.3	20.6	11	10.8	16.1	18.9	21.1	19.1	18	15.3	17.9	18.8	16.8	17.5	22.7	15.8	17	21.2	22	20.9	27.6	30.2	29.2	22.2			
Magnesium	mg/L	8.9	10.9	10.0	11.2	15.4	22.8	30.2	16.8	13.1	13.8	14	15.7	15.7	14.5	18.3	13.6	12.4	18.2	18.5	14.6	21.2	25.8	23.1	24.6			
Sodium	mg/L	146	122	166	169	180	290	752	168	122	110	107	116	123	140	115												

Table D.9: Chemical Analytical Results

Sample ID:		Lyons D.4																												
Site Number:		9																												
Date Sampled:	Units	15-Oct-1996	3-Oct-1997	8-Oct-1998	20-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	15-Oct-2003	15-Oct-2004	20-Oct-2005	13-Oct-2007	3-Oct-2007	16-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019					
Chem. O <sub>2</sub> Demand	mg/L	60	50	190	730	250	290	E M P T Y	90	90	126	112	130	132	131	84.4	165	149	95	132	155	120	202	221	137					
Ammonia-N	mg/L	<0.05	<0.05	0.06	1.59	0.89	5.69		0.16	0.73	0.42	0.68	<0.05	<0.05	0.065	<0.050	0.143	0.491	<0.050	0.055	0.137	0.111	3.04	1.82	0.397					
Total Kjeldahl Nitrogen	mg/L	3.9	2.5	5	19.6	2.6	20.2		3.8	3.8	5.1	7.3	5.9	5.1	6.39	4.36	6.18	4.78	3.71	4.04	6.38	6.87	11.1	10.3	4.26					
Total Organic Carbon	mg/L	33	20	47	184	156	26		33	33	47	48	51	-	-	-	-	-	-	-	-	-	-	-	-					
Dissolved Organic Carbon	mg/L	Not required by previous permit							Not required by previous permit							35	54	33.6	69.2	56.5	37.8	42	47.7	49.2	202	74.0	42.9			
Phenols	mg/L	Not required by previous permit							Not required by previous permit							-	-	-	-	-	-	-	-	-	-	-	0.0019	0.0088		
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																														
Benzene	mg/L	Not required by previous permit							Not required by previous permit							<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required by previous permit							Not required by previous permit							<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	Not required by previous permit							Not required by previous permit							<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Xylenes (m & p)	mg/L	Not required by previous permit							Not required by previous permit							-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050		
Xylene (o)	mg/L	Not required by previous permit							Not required by previous permit							-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylenes	mg/L	Not required by previous permit							Not required by previous permit							<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required by previous permit							Not required by previous permit							-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	Not required by previous permit							Not required by previous permit							<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required by previous permit							Not required by previous permit							<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required by previous permit							Not required by previous permit							<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.13	<0.10	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>																														
Aluminum	mg/L	Not required by previous permit							Not required by previous permit							0.23	0.129	0.069	0.03	0.045	0.066	0.032	0.0313	0.0755	0.0785	0.0911	0.0764			
Antimony	mg/L	0.0009	0.0009	0.003	<0.0004	0.0021	0.0011	E M P T Y	0.0014	0.0021	0.0012	0.0016	0.0012	0.0006	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00069	0.00024	0.00047	0.00058	0.00024					
Arsenic	mg/L	Not required by previous permit							Not required by previous permit							-	-	-	-	-	-	-	-	-	-	0.00685	0.00314			
Barium	mg/L	0.097	0.106	0.143	0.677	0.388	0.399		0.181	0.245	0.136	0.297	0.133	0.057	0.0671	0.0785	0.0171	0.0556	0.0851	0.0658	0.124	0.0338	0.0643	0.0935	0.0406					
Beryllium	mg/L	Not required by previous permit							Not required by previous permit							<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010		
Boron	mg/L	Not required by previous permit							Not required by previous permit							<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001		<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.00050	<0.00050	<0.00050	<0.0010	<0.00050	<0.00050	0.0000103	0.0000097	0.0000079	0.0000297	0.0000099				
Chromium	mg/L	0.008	<0.005	0.007	0.032	0.028	0.017		0.01	0.016	0.008	0.025	0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00011	0.00042	0.00025	0.00033	0.00031					
Cobalt	mg/L	<0.002	<0.002	<0.002	0.011	0.011	0.011		0.005	0.006	0.004	0.010	0.003	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.00133	0.00063	0.00197	0.0022	0.00060					
Copper	mg/L	0.004	0.004	0.007	0.024	0.027	0.02		0.055	0.015	0.008	0.02	0.006	0.004	0.002	0.004	<0.0010	0.0013	0.0012	0.0015	0.00181	0.00152	0.00243	0.00383	0.00123					
Iron	mg/L	1.830	4.620	7.320	27.800	15.300	27.400		8.99	13.9	7.47	20.6	4.71	0.142	0.3	2.12	0.998	0.268	0.067	1.18	0.216	0.995	0.108	0.168	0.922					
Lead	mg/L	<0.005	<0.005	<0.005	0.016	0.016	0.01	0.006	0.008	<0.005	0.012	<0.005	0.0001	0.0003	0.00065	<0.00010	<0.00050	<0.00010	0.00054	0.000267	0.00028	0.00059	0.000125	0.000283						
Lithium	mg/L	Not required by previous permit							Not required by previous permit							-	-	-	-	-	-	-	-	-	-	0.0339	0.016			
Manganese	mg/L	Not required by previous permit							Not required by previous permit							0.001	0.004	0.03	0.0484	0.0031	0.0022	0.0062	0.00197	0.00355	0.147	0.0927	0.00266			
Mercury	mg/L	0.0004	<0.0002	<0.0002	<0.0002	0.0005	<0.0005	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050					
Molybdenum	mg/L	<0.005	<0.005	0.007	<0.005	0.008	0.01	0.007	0.008	<0.005	0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00953	0.00113	0.00311	0.00662	0.00184						
Nickel	mg/L	0.003	0.003	0.014	0.039	0.056	0.039	0.021	0.023	0.013	0.030	0.013	0.008	0.0079	0.0057	<0.0020	0.0092	0.0072	0.0062	0.0126	0.00526	0.00965	0.0132	0.00455						
Selenium	mg/L	Not required by previous permit							Not required by previous permit							0.0007	0.00095	<0.00040	<0.00040	<0.00080	<0.00040	<0.00040	0.000626	0.000393	0.000497	0.000795	0.000262			
Silver	mg/L	Not required by previous permit							Not required by previous permit							<0.0001	<0.00010	<0.00010	<0.00010	<0.00050	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Thallium	mg/L	Not required by previous permit							Not required by previous permit							<0.0001	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Tin	mg/L	Not required by previous permit							Not required by previous permit							<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050		
Titanium	mg/L	Not required by previous permit							Not required by previous permit							0.01	0.008	0.0092	0.0024	0.0083	0.0026	0.0109	0.00518	0.00061	0.00269	0.0104	0.00661			
Uranium	mg/L	Not required by previous permit							Not required by previous permit							-	-	-	-	-	-	-	-	-	-	-	-	0.00446	0.00924	
Vanadium	mg/L	Not required by previous permit							Not required by previous permit							0.006	0.0025	0.003	0.0014	0.0051	0.0018	0.0022	0.00199	0.00334	0.00415	0.00393	0.00222			
Zinc	mg/L	0.038	0.025	0.058	0.029	0.605	0.088	0.032	0.143	0.063	0.079	0.021	0.012	<0.0020	<0.0020	<0.0020	<0.0020	0.0035	<0.0020	0.0066	<0.0010	0.0027	0.0017	<0.0010	0.0024					
<b>Routine Water</b>																														
Ion Balance	%	98	108	100	99	114	105	E M P T Y	104	103	105	102	98.1	98.6	99.9	109	92.8	94.8	110	104	98.9	110	97.7	112	101					
Bicarbonate	mg/L	385	331	459	705	650	636		402	411	429	459	428	343	405	318	470	599	425	297	413	356	619	564	442					
Chloride	mg/L	18.2	10.2	21.9	181.0	120.0	173.0		40	41	37	45	38	38	31.2	13.6	33.7	48.4	19.1	16.1	32.3	29.8	47.5	48.6	22.9					
Carbonate	mg/L	<5	<5	<5	<5	<5	<5		9	<5	<5	<5	<5	<5	42	17.4	6.4	<5.0	17.3	7.5	9.8	10.6	<5	<5.0	<5.0					
Conductivity (EC)	uS/cm	742	713	745	1740	1390	1840		887	891	730	879	760	774	758	553	921	1090	730	559	834	675	1050	1050	734					
Calcium	mg/L	23.1	20.5	21.9	39.5	45.9	56.6		39.1	29.5	27	28.2	24.4	22.7	20.5	27.7	29.4	31.9	36.6	25.3	28.7	23.5	28.8	28.6	22.2					
Potassium	mg/L	12.5	9.2	20.9	93.4	75.8	54.1		28.9	28.9	32.8	34.9	32.8	23.5	25.6	21.5	38.7	39.3	35.4	28.5	36.0	35.6	45.2	43.5	26.8					
Magnesium	mg/L	10.1	9.5	11.4	21.1	22.3	29.8		16.9	14																				



Table D.10: Chemical Analytical Results

Sample ID:		Magneson D.1																										
Site Number:		10																										
Date Sampled:	Units	17-Oct-1996	3-Oct-1997	8-Oct-1998	19-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	21-Oct-2003	15-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	50	70	110	90	130	80	140	120	120	88	126	244	186	96.3	134	280	211	149	257	197	320	323	268	339			
Ammonia-N	mg/L	<0.05	0.27	0.85	1.6	1.42	0.36	0.53	0.21	0.79	0.13	0.13	0.13	<0.05	<0.050	0.167	0.134	0.138	0.086	0.157	0.215	0.571	0.200	0.123	0.104			
Total Kjeldahl Nitrogen	mg/L	2.5	2.8	4.7	5.2	5.5	8.6	6.2	4.2	4.8	3.7	4.5	7.6	6.7	5.59	10.2	9.14	7.93	3.88	8.78	8.94	12.3	11.7	10.4	11.0			
Total Organic Carbon	mg/L	20	24	38	32	44	53	55	43	43	37	45	54	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit												55	34.7	72.3	85.5	64	77.4	58.1	93.9	106	323	91.0	102			
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0017	0.0084	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes (total)	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C <sub>7</sub> -C <sub>10</sub> )	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C <sub>7</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required under previous permit												<0.2	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	
<b>Dissolved Metals</b>																												
Aluminium	mg/L	Not required under previous permit												2.43	0.075	0.866	0.59	1.63	1.84	<0.01	0.326	0.168	0.0146	0.302	0.039			
Antimony	mg/L	0.0005	0.001	0.0012	<0.0004	0.0008	0.0008	0.0012	0.0013	0.0013	0.001	0.0010	0.002	0.0009	<0.00040	0.00067	<0.00040	<0.00080	0.00049	<0.0004	0.00044	0.00045	0.00057	0.00059	0.0005			
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.0181	0.0175
Barium	mg/L	0.03	0.036	0.042	0.052	0.06	0.055	0.041	0.038	0.045	0.058	0.06	0.104	0.062	0.0618	0.0474	0.031	0.0645	0.0712	0.0308	0.0376	0.0623	0.0562	0.0720	0.0701			
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	Not required under previous permit												0.11	<0.050	0.115	0.072	0.086	0.085	0.087	0.087	0.087	0.107	0.091	0.091	0.091	0.091	
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0003	<0.00050	0.000055	0.000055	<0.0010	0.000074	<0.00005	0.000043	0.00005	0.000038	0.000056	0.00005			
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.01	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00104	0.00114	0.00096	0.00115	0.00092			
Cobalt	mg/L	<0.002	<0.002	0.021	0.002	0.003	0.002	<0.002	<0.002	<0.002	0.002	0.005	0.005	<0.002	<0.0020	0.0026	0.0033	0.0044	0.0042	<0.002	0.00336	0.00442	0.00637	0.00608	0.0051			
Copper	mg/L	0.004	0.002	0.011	0.006	0.014	0.009	0.012	0.005	0.005	0.096	0.226	0.162	0.139	0.0014	0.0922	0.169	0.198	0.107	0.484	0.309	0.094	0.0532	0.0521	0.0255			
Iron	mg/L	<0.005	0.549	1.100	1.680	1.560	1.500	0.37	0.455	0.53	3.65	6.6	1.93	0.309	0.861	0.864	1.37	2.09	0.42	0.784	1.41	0.822	1.41	1.08	1.08			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.0014	0.00032	0.00083	0.0006	<0.0050	0.00284	0.00039	0.00053	0.00134	0.00076	0.00118	0.00105			
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0639	0.0537	
Manganese	mg/L	Not required under previous permit												0.029	0.0223	0.079	0.0699	0.232	0.440	0.0279	0.280	0.179	0.451	0.333	0.587			
Mercury	mg/L	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	0.0004	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	0.000205	<0.000050	<0.000050	<0.000050	0.000086			
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	0.0054	<0.0050	0.005	<0.0050	<0.0050	0.00595	0.00523	0.00447	0.00457	0.00327			
Nickel	mg/L	0.007	0.01	0.016	0.012	0.014	0.011	0.013	0.013	0.01	0.015	0.02	0.022	0.022	0.0058	0.0239	0.0214	0.0316	0.0283	0.0226	0.0261	0.0287	0.0288	0.0293	0.0243			
Selenium	mg/L	Not required under previous permit												0.0021	<0.00040	<0.0020	0.00069	0.00084	0.00067	0.00051	0.00076	0.00077	0.00096	0.00099	0.00099	0.00099	0.00080	
Silver	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Thallium	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050		
Titanium	mg/L	0.119	0.006	0.0546	0.0342	0.0754	0.0836	0.0031	0.0226	0.0135	0.00819	0.0552	0.00886															
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.00196	0.00185	
Vanadium	mg/L	Not required under previous permit												0.016	0.0034	0.0121	0.0106	0.0246	0.0201	0.0108	0.0139	0.0152	0.0155	0.0154	0.0131			
Zinc	mg/L	0.023	0.017	0.014	0.01	0.021	0.062	0.008	0.008	0.049	0.08	0.021	0.051	0.015	<0.0020	0.0065	0.0103	0.0143	0.0174	0.0304	0.0055	0.0123	0.0091	0.0071	0.0076			
<b>Routine Water</b>																												
Ion Balance	%	102	102	94	103	108	105	103	106	102	105	96.5	100	101	105	94.5	91.6	97.4	106	109	102	108	91.7	103	102			
Bicarbonate	mg/L	346	328	465	360	646	590	675	746	717	434	483	471	516	251	481	440	482	453	434	474	540	688	617	609			
Chloride	mg/L	73.1	70.5	96.1	97.0	110.0	159.0	161	149	158	94	101	123	157	12.2	149	126	142	136	151	147	174	200	197	202			
Carbonate	mg/L	19	16	<5	48	<5	64	86	60	90	16	30	10	19	53.6	28.4	7.9	15.5	14.0	19.7	12.5	15	<5.0	17.9	16.1			
Conductivity (EC)	uS/cm	1490	1150	1200	1420	1900	2160	2370	2500	2430	1410	1580	1430	1850	569	1930	1590	1750	1680	1830	1870	2030	2190	2150	2150			
Calcium	mg/L	28.4	27	28.6	28.3	40.7	40.3	40.6	44.4	48.9	32.3	35.0	38.2	45.5	19.8	44.3	32.8	40.3	45.7	42.9	43.1	48.8	46.1	51.1	51.7			
Potassium	mg/L	22.9	33.4	46.2	45.7	49.1	55.8	88	61.8	62.7	48.5	62.6	76.7	79.4	15.7	80.2	82.7	99.4	96.0	113	111	131	132	127	135			
Magnesium	mg/L	13.0	11.5	11.2	12.3	20.5	22.0	26.1	24.7	25.5	16.0	17.5	18.9	23.2	7.6	20.2	14.3	19.7	19.9	19.3	18.9	25.1	24	2				

Table D.11: Chemical Analytical Results

Sample ID:		Magneson D.2																								
Site Number:		11																								
Date Sampled:	Units	17-Oct-1996	3-Oct-1997	8-Oct-1998	19-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	15-Oct-2003	15-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019	
Chem. O <sub>2</sub> Demand	mg/L	250	220	370	590	260	550	EMPTY	340	160	395	165	349	231	EMPTY	124	185	EMPTY	298	215	267	126	188	160	114	
Ammonia-N	mg/L	4.6	2.09	4.98	4.83	5	2.31		6.22	10.5	6.03	2.71	0.19	6.04		0.605	0.82		0.187	0.094	0.241	0.076	0.749	0.137	0.063	
Total Kjeldahl Nitrogen	mg/L	20.5	18.8	23.3	19.4	3.6	30.1		31.8	17.2	22	12.0	16.7	23.7		16.7	11.5		4.11	8.76	13.6	4.64	8.26	6.13	3.46	
Total Organic Carbon	mg/L	96	88	183	154	100	144		170	66	114	61	125	-		-	-		-	-	-	-	-	-	-	-
Dissolved Organic Carbon	mg/L	Not required under previous permit							Not required under previous permit							117	51.2	77	51.9	39.3	35.6	41.3	188	60.0	33.5	
Phenols	mg/L	-																								
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																										
Benzene	mg/L	Not required under previous permit							Not required under previous permit							<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required under previous permit							Not required under previous permit							<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	Not required under previous permit							Not required under previous permit							<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit							Not required under previous permit							<0.0005	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	Not required under previous permit							Not required under previous permit							<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required under previous permit							Not required under previous permit							<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required under previous permit							Not required under previous permit							<0.2	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25
<b>Dissolved Metals</b>																										
Aluminium	mg/L	Not required under previous permit							Not required under previous permit							0.33	0.021	0.095	0.016	0.018	0.0069	0.132	0.0858	0.217	0.168	
Antimony	mg/L	0.0005	0.0007	0.0014	0.0004	0.0008	0.0007	0.0026	0.0021	0.0013	0.0020	0.0015	0.0011	0.0044	0.00047	<0.00040	<0.0004	0.00040	0.00021	0.00034	0.00024	0.00018				
Arsenic	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	0.0137	0.00332	
Barium	mg/L	0.726	1.28	0.967	1.3	1.03	1.04	1.9	0.343	0.967	0.394	1.08	0.147	0.0544	0.0685	0.124	0.0733	0.0963	0.0276	0.0547	0.0136	0.0524				
Beryllium	mg/L	Not required under previous permit							Not required under previous permit							<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010		
Boron	mg/L	Not required under previous permit							Not required under previous permit							0.07	0.058	<0.050	0.038	0.028	0.036	0.024				
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.000050	0.0000095	0.0000108	0.0000207	0.0000249	0.0000153				
Chromium	mg/L	0.019	0.052	0.047	0.085	0.07	0.096	0.147	0.022	0.059	0.033	0.075	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	0.00013	0.00034	0.00027	0.00053	0.00034				
Cobalt	mg/L	0.008	<0.002	0.044	0.018	0.016	0.031	0.042	0.008	0.019	0.011	0.021	0.003	0.002	<0.0020	0.0024	0.0028	0.00197	0.00079	0.00164	0.00070	0.00057				
Copper	mg/L	0.015	0.04	0.037	0.031	0.033	0.052	0.102	0.016	0.035	0.026	0.045	0.01	0.0091	0.0044	<0.0010	<0.001	0.00078	0.00204	0.00454	0.00276	0.00211				
Iron	mg/L	22.7	67.4	56.8	76.8	56.6	120	130	18.2	65.4	30.3	71.7	0.24	0.11	0.159	0.725	0.987	0.592	0.7	0.134	0.197	1.43				
Lead	mg/L	0.017	0.009	<0.005	0.031	0.032	0.054	0.07	0.011	0.043	0.019	0.045	0.0002	<0.00010	0.00014	0.00014	0.00034	0.000141	0.000212	0.000154	0.000151	0.000582				
Lithium	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	0.0124	0.0104		
Manganese	mg/L	Not required under previous permit							Not required under previous permit							0.197	0.0342	0.0063	0.424	0.344	0.384	0.00264	0.0402	0.0111	0.00213	
Mercury	mg/L	0.0002	0.0002	<0.0002	<0.0002	0.0002	<0.0002	<0.0002	0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	0.000005			
Molybdenum	mg/L	<0.005	<0.005	0.005	<0.005	<0.005	0.007	0.01	0.018	0.007	0.009	<0.005	0.021	<0.0050	<0.0050	0.0129	<0.005	0.0162	0.00198	0.00451	0.00352	0.00111				
Nickel	mg/L	0.022	0.086	0.07	0.052	0.077	0.079	0.111	0.028	0.049	0.033	0.055	0.019	0.0149	0.014	0.0118	0.0104	0.0129	0.00687	0.0105	0.00544	0.00512				
Selenium	mg/L	Not required under previous permit							Not required under previous permit							0.002	<0.0020	0.00074	0.00051	<0.0004	0.000899	0.000297	0.000603	0.000474	0.000263	
Silver	mg/L	Not required under previous permit							Not required under previous permit							<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Thallium	mg/L	Not required under previous permit							Not required under previous permit							<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	0.000018	<0.00010			
Tin	mg/L	Not required under previous permit							Not required under previous permit							<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050		
Titanium	mg/L	Not required under previous permit							Not required under previous permit							0.025	0.0027	0.0065	0.0019	0.0018	<0.00171	0.0056	0.00306	0.0158	0.0141	
Uranium	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	0.00188	0.000954	
Vanadium	mg/L	Not required under previous permit							Not required under previous permit							0.008	0.0074	0.0069	0.0075	0.0019	0.00533	0.00443	0.0038	0.0122	0.00364	
Zinc	mg/L	0.068	0.232	0.188	0.109	0.381	0.274	0.384	0.126	0.198	0.125	0.192	0.01	<0.0020	0.0024	<0.0020	0.0065	0.0013	0.0019	0.0037	<0.0010	0.0015				
<b>Routine Water</b>																										
Ion Balance	%	101	97	105	107	112	107	101	104	102	100	98.7	96	110	91.3	102	107	97	114	92.1	107	102				
Bicarbonate	mg/L	597	520	514	562	541	521	847	495	598	318	592	745	335	501	457	297	409	241	527	332	296				
Chloride	mg/L	94.2	64.0	71.3	97.0	71.0	145.0	187	109	102	80	72	168	56.9	42.7	41.8	25.6	63.5	22.4	54.4	48.5	19.2				
Carbonate	mg/L	<5	<5	<5	<5	<5	<5	<5	<5	6	<5	7	<5	9.9	11.5	14.5	11.8	6.0	<5	<5.0	12.7	<5.0				
Conductivity (EC)	uS/cm	1310	998	922	1190	1070	1350	1600	1350	1160	904	1120	1780	832	946	853	590	904	499	967	760	516				
Calcium	mg/L	27.1	31.9	34.2	47.8	88.6	84.5	84.5	55.7	47.1	24.4	37.5	54.6	38.1	30.7	44.8	34.4	40.5	22.8	26.1	19.9	20.8				
Potassium	mg/L	75	68.8	58.1	66.3	73.6	94.8	101	69.4	74.6	48.9	71.2	79.8	47.8	45.3	57.6	38.3	51.5	34	45.8	39.1	32.9				
Magnesium	mg/L	19.0	12.7	13.5	15.5	23.4	38.7	33.1	19.8	19.9	10.3	17.8	24.6	15.8	12.2	16.9	12.6	13.7	9.57	12.2	8.43	9.31				
Sodium	mg/L	187	148	172	199	166	231	251	185	173	128	169	262	110	121	98.3	61.5	99.8	58.6	143	128	69.1				
Sulfate	mg/L	53	26	35.5	27.5	23	74	62.7	157	32.4	73.3	28.1	116	45.2	3.76	3.38	0.8	16.6	2.91	14.1	21.6	5.44				
Phosphorus	mg/L	Not required under previous permit							Not required under previous permit							4.56	2.48	1.69	2.42	1.35	1.93	0.622	2.28	1.21		
pH in H <sub>2</sub> O	pH	8.2	8.0	7.5	8.2	7.7	8.0	8.3	8.3	8.4	7.9	8.3	8.2	8.49	8.5	8.53	8.64	8.40	8.28	8.26	8.68	8.19				
TDS (Calculated)	mg/L	765	602	636	716	650	603	1140	841	752	525	702	1070	491	514	502	331	494	270	559	442	303				
Nitrate	mg/L	Not required under previous permit							Not required under previous permit							0.2	0.574	0.06	<0.050	<0.05	<0.020	0.248	0.176	<0.020	0.253	
Nitrite	mg/L	Not required under previous permit							Not required under previous permit							-	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050		
Nitrate and Nitrite (as N)	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	<0.022	0.253	
Hardness as CaCO <sub>3</sub>	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	84.4	90.	

Table D.12: Chemical Analytical Results

Sample ID:		Magneson D.3																															
Site Number:		12																															
Date Sampled:	Units	17-Oct-1996	Oct. 3, 97	8-Oct-1998	19-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	15-Oct-2003	15-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	19-Oct-2010	12-Oct-2011	15-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019								
Chem. O <sub>2</sub> Demand	mg/L	10	30	30	50	40	40	30	30	30	40	39	49	53	57.2	45.1	42	49	37	59	49	37	57		119								
Ammonia-N	mg/L	0.06	<0.05	0.05	<0.05	<0.05	<0.05	0.12	<0.05	0.38	<0.05	<0.05	0.1	<0.05	<0.050	<0.050	<0.050	0.116	<0.050	<0.05	0.252	<0.050	<0.050		<0.050								
Total Kjeldahl Nitrogen	mg/L	1.3	<0.2	1.1	1	0.9	2.9	1.1	1.3	1.5	1	0.9	1.2	1.5	1.86	1.65	1.22	1.77	1.44	1.48	1.97	1.29	1.79		3.49								
Total Organic Carbon	mg/L	9	12	13	13	12	13	14	12	16	14	14	17	-	-	-	-	-	-	-	-	-	-		-								
Dissolved Organic Carbon	mg/L	Not required under previous permit														18	20.1	15.1	17.8	19.1	19.5	15.5	17.6	17.3	57		17.9						
Phenols	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		0.0136								
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																																	
Benzene	mg/L	Not required under previous permit														<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Toluene	mg/L	Not required under previous permit														<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Ethylbenzene	mg/L	Not required under previous permit														<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Xylenes (m & p)	mg/L	Not required under previous permit														-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.00050	
Xylene (o)	mg/L	Not required under previous permit														-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.00050
Xylenes	mg/L	Not required under previous permit														<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit														-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit														<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F1 - BTEX	mg/L	Not required under previous permit														<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 - (>C10-C16)	mg/L	Not required under previous permit														<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25
<b>Dissolved Metals</b>																																	
Antimony	mg/L	0.0004	0.0008	0.0012	<0.0004	0.0006	0.0005	0.0011	0.0011	0.0012	0.0014	0.0011	0.0018	0.0005	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00054	0.00031	0.00027		0.00029								
Arsenic	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		0.00194							
Barium	mg/L	0.039	0.041	0.039	0.069	0.053	0.058	0.082	0.058	0.079	0.047	0.047	0.071	0.066	0.0646	0.0455	0.0687	0.0798	0.0262	0.0425	0.0968	0.0264	0.0913		0.0773								
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.0010	<0.000050	<0.00005	0.000084	0.0000249	0.0000585		0.0000188								
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	<0.00010	<0.00010	<0.00010		0.00016								
Cobalt	mg/L	0.002	0.002	0.02	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.002	0.00024	0.00018	0.00039		0.00052								
Copper	mg/L	0.006	0.002	0.009	0.002	0.004	0.004	0.007	0.005	0.007	0.003	0.003	0.002	0.002	0.0022	0.0087	0.0011	0.0015	0.0016	0.0014	0.00136	0.0013	0.00283		0.00242								
Iron	mg/L	<0.005	0.982	0.603	0.977	0.266	0.810	2.36	1.48	3.32	0.437	1.07	0.872	0.032	0.071	0.014	0.102	0.047	0.036	<0.01	0.018	<0.010	0.019		0.015								
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00010	<0.00010	<0.00010	<0.00050	<0.00010	<0.0001	<0.000050	<0.000050	0.000087		<0.000050								
Lithium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		0.0409								
Molybdenum	mg/L	0.008	<0.005	0.007	0.006	<0.005	0.006	0.007	0.008	0.007	0.006	0.006	<0.005	0.007	0.0072	0.0217	0.0146	0.0169	0.0225	0.0212	0.0302	0.0302	0.0206		0.0254								
Nickel	mg/L	0.013	0.009	0.015	0.008	0.01	0.008	0.011	0.009	0.012	0.007	0.007	0.007	0.007	0.0081	0.0105	0.0113	0.0116	0.0127	0.013	0.0191	0.0172	0.0121		0.0203								
Zinc	mg/L	0.016	0.015	0.031	0.009	<0.001	0.032	0.01	0.009	0.066	0.004	0.009	0.009	0.009	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.0079	0.0021	0.0015	0.0057		0.0028								
Mercury	mg/L	<0.0002	<0.0002	<0.0002	0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.000050	<0.000050	<0.000050		<0.000050								
Aluminum	mg/L	Not required under previous permit														0.02	0.082	0.011	0.012	0.031	0.039	<0.01	0.0233	0.0023	0.0149		0.0033						
Beryllium	mg/L	Not required under previous permit														<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010		<0.00010				
Boron	mg/L	Not required under previous permit														<0.05	<0.050	<0.050	0.058	0.055	0.055	0.053	0.065	0.061	0.071		0.060						
Manganese	mg/L	Not required under previous permit														0.002	0.0026	<0.0020	<0.0020	<0.0020	0.0020	<0.002	0.0009	0.00027	0.0211		0.00123						
Silver	mg/L	Not required under previous permit														<0.0001	<0.00010	<0.00010	<0.00010	<0.00050	<0.00010	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010		<0.000010					
Tin	mg/L	Not required under previous permit														<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00010	<0.00010	0.00033		<0.00010						
Selenium	mg/L	Not required under previous permit														0.0007	0.00054	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.000412	0.000322	0.000233		0.000304						
Titanium	mg/L	Not required under previous permit														0.001	0.0037	<0.0010	<0.0010	0.0023	<0.0010	0.0025	<0.0010	0.00114	<0.00030	0.00144		<0.00030					
Thallium	mg/L	Not required under previous permit														0.0002	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.0001	<0.000010	<0.000010	<0.000010		<0.000010						
Uranium	mg/L	Not required under previous permit														-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.00247			
Vanadium	mg/L	Not required under previous permit														0.001	<0.0010	0.0015	0.0034	0.005	0.0127	0.0096	0.00866	0.0164	0.00285		0.00262						
<b>Routine Water</b>																																	
Ion Balance	%	103	106	109	103	105	108	97.6	104	102	109	104	103	99.5	92.3	95.7	93.6	94.2	104	104	94.5	99.8	94.8		102								
Bicarbonate	mg/L	237	198	227	222	222	246	247	200	261	225	224	256	268	228	189	267	290	253	230	251	256	334		268								
Chloride	mg/L	4.4	3.9	4.4	5.0	4.0	6.0	7	6	8	6	7	6	12	10.6	24	19.2	24.5	24.4	21.3	20.9	18.2	18.3		14.7								
Carbonate	mg/L	<5	<5	<5	5	<5	<5	13	9	<5	<5	<5	<5	14	7.1	<5.0	7.1	6	6.7	8.4	<5.0	<5.0	6.4		<5.0								
Conductivity (EC)	uS/cm	876	603	632	745	789	918	1050	909	1110	779	790	683	831	918	989	928	1060	993	957	987	943	1020		960								
Calcium	mg/L	21.8	24.9	21.1	23	24.3	28.7	22.8	21.6	35.6	37.5	26.3	27.5	25.7	19	25.5	34.4	27.4	26.4	24.4	31.3	27.9	29.1		49.1								
Potassium	mg/L	6.9	6.6	7.3	7.3	7.8	8.4	9.5	7.1	7.7	7.1	8.4	8.5	8.6	8.39	8.8	8.06	10.9	11.6	10.7	11.5	10.4	11.1		13.6								
Magnesium	mg/L	8.0	6.4	7.9	8.8	10.2	12.0	13	10	11.0	10.6	10.4	9.9	12.4	12.4	13.1																	

Table D.13: Chemical Analytical Results

Sample ID:		Magneson D.4																											
Site Number:		13																											
Date Sampled:	Units	7-Oct-1997	8-Oct-1998	19-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	15-Oct-2003	14-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019					
Chem. O <sub>2</sub> Demand	mg/L	350	1430	680	1450	5260	E M P T Y	1270	E M P T Y	259	1120	1070	1440	E M P T Y	4810	1220	1550	1560	1580	1190	1300	1930	960	1370					
Ammonia-N	mg/L	9.72	2.35	2.41	14.6	1.73		0.77		0.26	1.48	1.37	0.67		5.11	4.39	2.04	2.24	0.828	1.37	3.13	1.37	0.409	2.85					
Total Kjeldahl Nitrogen	mg/L	27.8	86.2	30.7	<3	91.2		58.2		11.9	45.1	44.4	71		128	44.6	63.8	49.7	54.7	52.8	56.1	62	39.4	43.7					
Total Organic Carbon	mg/L	168	714	187	813	1690		356		105	271	251	-		-	-	-	-	-	-	-	-	-	-	-				
Dissolved Organic Carbon	mg/L	Not required under previous permit						ired under previo		Not required under previous permit					527	1430	554	392	756	609	531	507	1930	329	415				
Phenols	mg/L	Not required under previous permit					ired under previo	Not required under previous permit					-	-	-	-	-	-	-	-	-	-	-	<0.01	0.0116				
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																													
Benzene	mg/L	Not required under previous permit					E M P T Y	ired under previo	E M P T Y	Not required under previous permit	E M P T Y	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005				
Toluene	mg/L	Not required under previous permit										<0.0005	0.00318	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	
Ethylbenzene	mg/L	Not required under previous permit										<0.0005	0.00107	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	
Xylenes (m & p)	mg/L	Not required under previous permit										-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Xylene (o)	mg/L	Not required under previous permit										-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Xylenes	mg/L	Not required under previous permit										<0.0005	0.00825	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit										-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	Not required under previous permit										<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required under previous permit										<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required under previous permit										<0.2	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25
<b>Dissolved Metals</b>																													
Aluminium	mg/L	Not required under previous permit					E M P T Y	ired under previo	E M P T Y	Not required under previous permit	E M P T Y	<0.2	0.23	0.617	1.09	0.45	0.075	5.79	0.273	0.149	0.145	0.080							
Antimony	mg/L	<0.0002	0.003	<0.0004	0.0034	0.0021						0.0007	0.0019	<0.0004	0.0012	<0.008	<0.0080	<0.00080	0.00121	<0.01	<0.001	0.0013	0.00082	0.00088	0.00082	0.00064			
Arsenic	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					-	-	-	-	-	-	-	-	0.0327	0.0275		
Barium	mg/L	0.383	1.09	0.208	1.29	0.998						0.137	0.083	0.03	0.736	<0.06	0.317	0.0722	0.305	0.113	0.137	0.330	0.188	0.236	0.383	0.166			
Beryllium	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					<0.02	<0.010	<0.0020	<0.0010	<0.050	<0.001	<0.0010	<0.00050	<0.00050	<0.00050		
Boron	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					<1	0.48	<0.10	0.318	<1.0	0.28	0.270	0.289	0.302	0.267	0.204	
Cadmium	mg/L	<0.001	<0.001	<0.001	0.002	<0.001						<0.001	<0.001	<0.001	<0.001	<0.002	<0.0010	<0.00010	<0.0010	<0.0010	0.00017	0.000114	0.000094	0.000061	0.000064	0.000079			
Chromium	mg/L	0.039	0.079	0.026	0.114	0.055						0.018	0.005	<0.005	0.07	<0.1	<0.0080	<0.010	0.0057	<0.010	<0.005	0.0119	0.00483	0.00492	0.00482	0.00285			
Cobalt	mg/L	0.024	0.063	0.011	0.069	0.061						0.008	0.006	0.003	0.036	<0.04	0.0218	<0.0040	0.013	0.014	0.0144	0.0154	0.0128	0.0108	0.00594	0.00794			
Copper	mg/L	0.017	0.084	0.017	0.136	0.188						0.018	0.0011	0.008	0.078	0.02	0.016	0.0031	0.0283	0.024	0.0335	0.0263	0.0138	0.0093	0.0069	0.0093			
Iron	mg/L	29.100	80.000	14.900	93.800	98.300						113	5.19	5.76	62.7	0.43	4.93	5.83	6.3	2.3	3.64	9.88	3.92	2.86	3.26	1.99			
Lead	mg/L	0.011	0.009	0.005	0.048	0.043						0.007	<0.005	<0.005	0.033	<0.002	0.003	0.00103	<0.0050	<0.0050	0.0044	0.00689	0.00385	0.00305	0.00422	0.00304			
Lithium	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					-	-	-	-	-	-	-	-	0.128	0.0902		
Manganese	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					0.3	1.83	1.18	1.18	0.649	0.615	1.15	0.945	1.06	1.39	0.748	
Mercury	mg/L	0.0009	<0.0002	<0.0002	0.0008	<0.0002						<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	0.000184	<0.00050	<0.00050	<0.00050	<0.00050			
Molybdenum	mg/L	0.006	0.019	0.006	0.036	0.017						0.005	0.021	<0.005	0.005	0.03	<0.0050	<0.010	0.0189	0.0409	0.0078	0.0179	0.00911	0.00492	0.00333	0.00193			
Nickel	mg/L	0.059	0.18	0.047	0.212	0.201						0.029	0.024	0.011	0.099	0.07	0.0998	0.0122	0.0658	0.085	0.0507	0.0553	0.0497	0.045	0.0350	0.0350			
Selenium	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					0.014	<0.040	<0.00080	0.00225	<0.010	0.0016	0.00339	0.00192	0.00218	0.00159	0.00142	
Silver	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					<0.002	<0.0020	<0.00020	<0.0050	<0.0010	<0.0001	0.00014	0.000092	0.000075	0.00009	<0.00050	
Thallium	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					<0.002	<0.0010	<0.00020	<0.050	<0.0050	<0.0001	<0.00010	<0.000050	<0.000050	<0.000050	<0.000050	
Tin	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					<1	<0.050	<0.10	<0.050	<0.050	<0.05	<0.0010	<0.00050	<0.00050	<0.00050	<0.00050	
Titanium	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					<0.02	0.128	0.0338	0.0989	0.083	0.0437	0.334	0.0677	0.0592	0.0716	0.0444	
Uranium	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					-	-	-	-	-	-	-	-	-	0.00295	0.00214	
Vanadium	mg/L	Not required under previous permit										ired under previo	Not required under previous permit					0.06	0.0793	0.0072	0.0345	0.055	0.033	0.0481	0.0336	0.0351	0.0277	0.0286	
Zinc	mg/L	0.149	0.424	0.027	0.505	1.92	0.067	0.073	0.015	0.261	<0.04	0.094	0.0106	0.0284	<0.10	0.053	0.047	0.0421	0.0297	0.0247	0.032								
<b>Routine Water</b>																													
Ion Balance	%	104	102	105	107	107	E M P T Y	103	E M P T Y	102	111	98.1	95	E M P T Y	115	91.8	96.1	96.8	101	97.9	114	98.6	101	110					
Bicarbonate	mg/L	1240	1650	1450	2200	2500		1890		883	1570	1470	2830		2220	1320	2350	3210	1490	1540	1080	1830	1580	1310					
Chloride	mg/L	505	868	674	1420	2530		1640		424	921	605	2040		1190	480	1030	1930	807	744	615	932	894	603					
Carbonate	mg/L	29	70	95	<5	189		81		53	57	75	359		73	49.9	140	341	138	88.6	65.1	94.1	87.5	47.6					
Conductivity (EC)	uS/cm	3620	4920	4510	7690	11700		8430		3000	6190	3980	11500		7840	4020	7490	11,800	5830	5640	4620	6910	6470	4570					
Calcium	mg/L	86.3	113	74.1	205	212		244		113	144	108	61.9		177	86.6	165	119	93.5	113	89.2	105	118	84.2					
Potassium	mg/L	322	492	359	1090	1310		1120		329	678	545	1260		1290	481	976	1550	788	728	610	870	717	634					
Magnesium	mg/L	61.4	95.8	84.0	142.0	198.0		246		67.0	112	56	177		112	44.9	90.6	148	60.8	59.2	60.3	90	84.4	71.6					
Sodium	mg/L	517	870	709	1220	2450		1540		432	838	515	1760		915	365	898	1700	680	591	560	881	844	596					
Sulfate	mg/L	140	418	126	555	713		2150		448	751	174	826		341	141	521	856	343	308	659	637	361						
Phosphorus	mg/L	Not required under previous permit						ired under previo		Not required under previous permit					-	44	30	44.5	48.1	41.6	34.4	34.8	44.7	31.3	26.9				
pH in H <sub>2</sub> O	pH	8.5	8.4	8.7	8.2	8.7		8.5		8.6	8.5	8.7	8.8		8.54	8.													

Table D.14: Chemical Analytical Results

Sample ID:		Magneson D.5																									
Site Number:		14																									
Date Sampled:	Units	7-Oct-1997	8-Oct-1998	19-Oct-1999	10-Oct-2000	5-Oct-2001	8-Oct-2002	15-Oct-2003	15-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	90	120	130	120	280	440	240	130	156	117	153	191	181	98.2	156	178	146	100	146	184	268	243	370			
Ammonia-N	mg/L	0.05	0.32	0.1	0.08	<0.05	0.13	0.05	1.15	<0.05	1.04	0.52	0.95	0.432	0.087	0.135	0.084	<0.050	0.704	1.38	0.138	2.42	0.455	0.600			
Total Kjeldahl Nitrogen	mg/L	3.7	5.1	5.2	4.6	14.2	21.5	8.2	7	5.9	7.5	6.6	8.6	9.67	8.29	5.73	7.03	4.24	4.16	6.24	6.84	11.6	10.0	13.9			
Total Organic Carbon	mg/L	34	45	49	47	76	201	49	52	63	46	56	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit											60	68.7	61.6	57.5	60.5	49.1	36.8	55.1	62.4	268	88.0	100			
Phenols	mg/L	Not required under previous permit											-	-	-	-	-	-	-	-	-	-	-	-	0.0025	0.0071	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																											
Benzene	mg/L	Not required under previous permit											<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required under previous permit											<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Ethylbenzene	mg/L	Not required under previous permit											<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Xylenes (m & p)	mg/L	Not required under previous permit											-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit											-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit											<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071		
Styrene	mg/L	Not required under previous permit											-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit											<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit											<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10		
F2 - (C10-C16)	mg/L	Not required under previous permit											<0.2	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.10	<0.13	<0.10	<0.10		
<b>Dissolved Metals</b>																											
Aluminium	mg/L	Not required under previous permit											1.16	0.057	0.031	0.035	0.106	0.203	<0.01	0.0288	0.0636	0.297	0.0245	0.0182			
Antimony	mg/L	<0.0002	0.001	0.0009	0.0009	0.001	0.0022	0.0023	0.0021	0.0012	0.0022	0.0015	0.003	0.00138	0.00082	0.00072	0.00099	0.00104	0.00047	0.00055	0.00049	0.00045	0.00101	0.00073			
Arsenic	mg/L	Not required under previous permit											-	-	-	-	-	-	-	-	-	-	-	-	-	0.019	0.0155
Barium	mg/L	0.068	0.081	0.092	0.063	0.121	0.188	0.191	0.197	0.057	0.327	0.083	0.09	0.0835	0.0459	0.0428	0.0737	0.0697	0.0402	0.0616	0.0324	0.0255	0.0764	0.0337			
Beryllium	mg/L	Not required under previous permit											<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.00020	<0.00020	<0.00020	<0.00020	<0.00020			
Boron	mg/L	Not required under previous permit											<0.05	<0.050	0.056	<0.050	<0.050	<0.050	<0.050	0.032	0.038	<0.020	<0.020	0.048			
Cadmium	mg/L	0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	0.00005	<0.000050	<0.000050	<0.0010	<0.000050	<0.00005	<0.00010	<0.00010	<0.00010	0.000019	0.000012			
Chromium	mg/L	<0.005	<0.005	0.007	<0.005	<0.005	<0.005	0.024	0.019	<0.005	0.047	0.008	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	<0.00020	0.00043	0.00068	0.00025	0.00025	0.00055			
Cobalt	mg/L	0.005	0.022	0.004	0.003	0.003	0.008	0.014	0.01	0.004	0.015	0.005	0.004	0.0034	0.0035	0.0034	<0.0020	<0.0020	0.003	0.00218	0.00169	0.00234	0.00364	0.00428			
Copper	mg/L	<0.001	0.014	0.009	0.007	0.008	0.032	0.028	0.016	0.005	0.031	0.008	0.008	0.0055	0.0118	0.0063	0.0035	0.0031	0.0023	0.00201	0.00214	0.00112	0.0052	0.00527			
Iron	mg/L	2.770	3.470	3.220	1.510	4.460	6.480	15.2	13.1	0.725	32.2	3.34	0.726	0.059	0.064	0.05	0.098	0.143	<0.01	<0.020	0.322	0.223	0.070	0.277			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	0.006	0.01	0.009	<0.005	0.025	<0.005	0.0086	<0.00010	<0.00010	<0.00010	<0.0050	0.00020	<0.0001	<0.00010	0.00024	0.00021	0.00011	0.00037			
Lithium	mg/L	Not required under previous permit											-	-	-	-	-	-	-	-	-	-	-	0.0576	0.0533		
Manganese	mg/L	Not required under previous permit											0.066	<0.0020	0.0384	0.0024	0.0033	0.0047	0.0375	0.00208	0.0381	0.633	0.00515	0.220			
Mercury	mg/L	<0.0004	<0.0004	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.000050	0.0000118	<0.000050	<0.000050	0.0000063			
Molybdenum	mg/L	<0.005	0.005	0.007	0.007	0.012	0.065	0.014	0.019	0.016	0.015	0.008	0.04	0.0326	0.0122	0.0191	0.0458	0.0444	0.0131	0.0218	0.00595	0.00653	0.0110	0.00592			
Nickel	mg/L	0.011	0.024	0.02	0.019	0.019	0.071	0.056	0.042	0.025	0.055	0.025	0.033	0.0319	0.0283	0.0314	0.0408	0.0253	0.0204	0.0236	0.0165	0.0168	0.0232	0.0225			
Selenium	mg/L	Not required under previous permit											0.0018	0.002	<0.0020	0.00121	0.00091	0.00072	0.00063	0.00087	0.00067	0.00062	0.00078	0.00088			
Silver	mg/L	Not required under previous permit											<0.0001	<0.00010	<0.00010	<0.00010	<0.0050	<0.00010	<0.0001	<0.00020	<0.00020	<0.00020	<0.00020	<0.00020			
Thallium	mg/L	Not required under previous permit											<0.0001	<0.00010	<0.00010	<0.00010	<0.0050	<0.00010	<0.0001	<0.00020	<0.00020	<0.00020	<0.00020	<0.00020			
Tin	mg/L	Not required under previous permit											<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00020	<0.00020	<0.00020	<0.00020	<0.00020			
Titanium	mg/L	Not required under previous permit											0.05	0.0037	0.0041	0.0015	0.0037	0.0164	<0.001	0.00148	0.00805	0.0116	0.00511	0.00459			
Uranium	mg/L	Not required under previous permit											-	-	-	-	-	-	-	-	-	-	0.00351	0.0023			
Vanadium	mg/L	Not required under previous permit											0.009	0.0044	0.0074	0.0294	0.0365	0.0286	0.0162	0.0138	0.0178	0.018	0.0188	0.0269			
Zinc	mg/L	0.032	0.052	0.013	0.064	0.246	0.031	0.098	0.168	0.01	0.210	0.036	0.006	0.0108	0.003	0.0021	<0.0020	<0.0020	0.0071	<0.0020	0.0028	0.0033	<0.0020	0.004			
<b>Routine Water</b>																											
Ion Balance	%	109	100	108	105	107	102	98.2	107	104	102	98.7	100	104	105	91.5	95.3	103	111	94.5	107	94.4	99.5	104			
Bicarbonate	mg/L	360	529	455	408	571	1370	482	622	408	658	533	687	664	491	537	709	549	521	713	589	1100	932	850			
Chloride	mg/L	40.9	51.6	57.0	60.0	109.0	323.0	104	103	106	99	95	140	126	76.7	82.1	114	89.3	54.9	81.4	71.4	143	145	175			
Carbonate	mg/L	26	<5	60	45	69	89	20	19	19	<5	22	29	67.1	19.8	73	46.7	68.9	42.9	40.3	22.4	18.7	37.6	21.7			
Conductivity (EC)	uS/cm	1020	976	1200	1030	1460	3320	1410	1700	1530	1460	1500	1830	1810	1280	1610	1950	1480	1370	1640	1520	2080	2030	2120			
Calcium	mg/L	30.4	31.1	32	23.7	33.1	36.3	43	48.5	46.2	23.7	30.9	33.8	30	31.8	39.7	32.9	29.2	33.7	34.3	38.5	43.4	35.6	50.3			
Potassium	mg/L	40.4	43.2	42.2	32.6	35.1	43.1	57.1	52.5	48.1	35.7	52.6	42.9	40.6	57	52.1	45	40.3	42	44.9	54.5	83.8	67.2	119			
Magnesium	mg/L	11.8	12.2	13.5	10.5	12.3	23.2	15.1	18.7	17.2	9.7	15.3	14.2	15.3	13.2	16.9	14.6	11.3	15.6	13.5	20.4	26.1	18.2	35.9			
Sodium	mg/L	194	184	238	205	367	802	253	307	323	299	235	359	388	227	252	363	296	261	274	263	375	391	353			
Sulfate	mg/L	146	75.2	101	70.2	55	152	221	250	179	97.6	117	162	157	114	172	210	99.7	117	74.4	144	45.4	71.6	162			
Phosphorus	mg/L	Not required under previous permit											-	0.77	3.05	2.74	1.27	0.99									

**Table D.15: Chemical Analytical Results**

Sample ID:		Magneson D.6				
Site Number:		15				
Date Sampled:	Units	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019
Chem. O <sub>2</sub> Demand	mg/L	121	106	127	125	125
Ammonia-N	mg/L	0.088	0.056	0.27	<0.050	<0.050
Total Kjeldahl Nitrogen	mg/L	4.06	4.16	4.05	4.58	4.16
Total Organic Carbon	mg/L	-	-	-	-	-
Dissolved Organic Carbon	mg/L	43.1	33	127	43.0	33.1
Phenols	mg/L	-	-	-	0.0021	0.013
<b>BTEX, F1 (C<sub>6</sub>-C<sub>10</sub>) and F2 (&gt;C<sub>10</sub>-C<sub>16</sub>)</b>						
Benzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes (m & p)	mg/L	-	-	-	<0.0005	<0.00050
Xylene (o)	mg/L	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071
Styrene	mg/L	-	-	-	<0.0005	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	<0.10	<0.13	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>						
Aluminium	mg/L	0.0224	0.0167	<0.0050	0.0151	0.0051
Antimony	mg/L	0.00080	0.0007	0.00103	0.00113	0.00086
Arsenic	mg/L	-	-	-	0.019	0.0134
Barium	mg/L	0.0342	0.0266	0.0375	0.0302	0.0512
Beryllium	mg/L	<0.0005	<0.00050	<0.00050	<0.00020	<0.00020
Boron	mg/L	0.306	0.279	0.337	0.301	0.237
Cadmium	mg/L	<0.000025	<0.000025	<0.000025	0.000018	0.000012
Chromium	mg/L	<0.00050	<0.0005	<0.00050	<0.00020	<0.00020
Cobalt	mg/L	0.00061	0.00086	0.00133	0.00089	0.00075
Copper	mg/L	<0.0010	0.0016	<0.0010	0.00103	0.00174
Iron	mg/L	<0.050	<0.050	0.063	0.037	0.023
Lead	mg/L	<0.00025	<0.00025	<0.00025	<0.00010	<0.00010
Lithium	mg/L	-	-	-	0.13	0.0978
Manganese	mg/L	0.00404	0.00561	0.532	0.00962	0.00599
Mercury	mg/L	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050
Molybdenum	mg/L	0.00327	0.00254	0.0016	0.00211	0.00179
Nickel	mg/L	0.0072	0.0069	0.0086	0.0067	0.0082
Selenium	mg/L	0.00033	0.00037	<0.00025	0.00032	0.00029
Silver	mg/L	<0.000050	<0.000050	<0.000050	<0.000020	<0.000020
Thallium	mg/L	<0.000050	<0.000050	<0.000050	<0.00002	<0.000020
Tin	mg/L	<0.00050	<0.00050	<0.00050	<0.00020	<0.00020
Titanium	mg/L	0.0016	<0.0015	<0.0015	0.00146	0.00134
Uranium	mg/L	-	-	-	0.00442	0.00507
Vanadium	mg/L	0.00450	0.0052	0.0044	0.0042	0.0063
Zinc	mg/L	<0.0050	<0.0050	<0.0050	0.0020	<0.0020
<b>Routine Water</b>						
Ion Balance	%	104	106	94.3	98.7	101
Bicarbonate	mg/L	593	343	694	538	520
Chloride	mg/L	334	235	340	359	286
Carbonate	mg/L	30.9	13.1	20	14.5	16.6
Conductivity (EC)	uS/cm	4080	2790	4020	4070	3120
Calcium	mg/L	54.3	40.2	70.2	41.7	97.9
Potassium	mg/L	31.3	27.1	29.6	29.8	34.1
Magnesium	mg/L	55.5	42.5	56.4	58.5	56.6
Sodium	mg/L	785	528	729	794	558
Sulfate	mg/L	990	711	1030	1120	818
Phosphorus	mg/L	0.707	0.385	0.963	0.486	0.745
pH in H <sub>2</sub> O	pH	8.61	8.56	8.52	8.47	8.52
TDS (Calculated)	mg/L	2570	1770	2620	2680	2120
Nitrate	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10
Nitrite	mg/L	<0.050	<0.050	<0.050	<0.050	<0.050
Nitrate and Nitrite (as N)	mg/L	-	-	-	<0.11	<0.101
Hardness as CaCO <sub>3</sub>	mg/L	-	-	-	345	478
Alkalinity (total as CaCO <sub>3</sub> )	mg/L	-	-	-	465	454
Hydroxide	mg/L	-	-	-	<5	<5.0
Fluoride	mg/L	-	-	-	0.22	0.35
<b>Field Data</b>						
pH in H <sub>2</sub> O	pH	8.68	9.5	8.5	10.9	9.48
Conductivity (EC)	uS/cm	4120	2730	4300	4140	3.82

Table D.16: Chemical Analytical Results

Sample ID:		Beaver D.1																									
Site Number:		16																									
Date Sampled:	Units	18-Oct-1996	3-Oct-1997	8-Oct-1998	20-Oct-1999	11-Oct-2000	4-Oct-2001	9-Oct-2002	16-Oct-2003	14-Oct-2004	21-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	19-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019		
Chem. O <sub>2</sub> Demand	mg/L	60	70	90	90	80	100	80	50	70	59	65	78	85	140	66.4	89	302	73	105	60	74	56	66	93		
Ammonia-N	mg/L	0.1	<0.05	0.07	<0.05	<0.05	1.24	<0.05	<0.05	0.05	0.22	<0.05	2.11	0.46	5.66	<0.050	<0.050	<0.050	2.57	<0.05	0.188	<0.05	1.00	1.10	0.071		
Total Kjeldahl Nitrogen	mg/L	4.9	2.2	2.9	2.5	2	5.9	2.3	<0.2	2	1.8	2.1	8.5	2.8	9	2.21	2.62	3.98	4.30	3.69	1.61	2.67	2.78	4.27	2.46		
Total Organic Carbon	mg/L	25	28	30	25	26	30	32	26	24	22	22	27	-	-	-	-	-	-	-	-	-	-	-	-		
Dissolved Organic Carbon	mg/L	Not required under previous permit												27	63.2	24.9	29	29.9	29.5	25.6	22.7	22.5	56.0	25.6	28.1		
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	0.0023	0.0099	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																											
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F2 - (C10-C16)	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.13	<0.10	<0.10
<b>Dissolved Metals</b>																											
Aluminium	mg/L	Not required under previous permit												<0.01	0.074	0.022	<0.010	<0.010	0.059	<0.01	0.0119	0.0011	0.008	0.0064	0.0036		
Antimony	mg/L	<0.0004	0.0006	0.0011	<0.0004	0.0005	0.0007	<0.0004	0.0009	0.0018	0.001	0.0014	0.0009	0.0008	<0.0016	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00025	0.00024	0.00023	0.00024	0.00022		
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	0.00455	0.00586	
Barium	mg/L	0.15	0.049	0.029	0.084	0.074	0.123	0.15	0.051	0.040	0.047	0.061	0.092	0.039	0.115	0.037	0.0521	0.0799	0.0952	0.0558	0.0756	0.0581	0.0707	0.0833	0.0489		
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0020	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010
Boron	mg/L	Not required under previous permit												0.07	<0.050	0.071	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.00020	<0.000050	<0.000050	<0.0010	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050		
Chromium	mg/L	0.015	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.010	0.01	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050		
Cobalt	mg/L	<0.002	<0.002	0.019	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020		
Copper	mg/L	0.01	<0.001	0.006	<0.001	0.001	0.007	0.022	0.005	0.001	<0.001	0.002	0.001	0.001	<0.0024	0.0019	<0.0010	<0.0010	<0.0010	<0.0010	0.00043	0.00034	0.00101	0.00057	0.00071		
Iron	mg/L	6.880	0.376	0.201	0.581	0.127	1.220	0.339	1.17	0.09	0.316	0.311	0.74	0.008	0.089	0.013	0.016	0.04	0.212	0.078	0.038	0.011	0.033	0.026	0.049		
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.0002	<0.00040	<0.00010	<0.00010	<0.00050	0.00013	<0.0001	<0.000050	<0.000050	0.000075	<0.000050	<0.000050		
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	0.0329	0.0308	
Manganese	mg/L	Not required under previous permit												0.025	0.137	<0.0020	0.0025	<0.0020	0.248	0.0073	<0.00078	0.00062	0.182	0.387	0.00491		
Mercury	mg/L	<0.0002	<0.0002	<0.0002	0.0003	<0.0002	<0.0002	0.0004	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	0.000005	<0.000050	<0.000050	<0.000050		
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00199	0.000986	0.00105	0.00153	0.00067		
Nickel	mg/L	0.011	<0.002	0.015	0.005	0.003	<0.002	0.005	0.005	<0.005	<0.002	0.005	0.006	0.007	0.004	0.0049	0.0036	0.0049	0.0047	0.0043	0.00725	0.00521	0.00592	0.00697	0.00493		
Selenium	mg/L	Not required under previous permit												0.0015	0.0038	<0.00040	<0.00040	<0.00080	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040
Silver	mg/L	Not required under previous permit												<0.0001	<0.00040	<0.00010	<0.00010	<0.00050	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Thallium	mg/L	Not required under previous permit												<0.0001	<0.00020	<0.00010	<0.00010	<0.050	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050
Titanium	mg/L	Not required under previous permit												0.002	<0.0012	<0.0010	<0.0010	<0.0010	<0.0010	0.0037	<0.001	<0.00081	<0.00030	0.00044	0.00086	0.00069	
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.00225	0.00115
Vanadium	mg/L	Not required under previous permit												0.01	0.0052	0.0024	0.0031	0.0072	0.0038	0.0036	0.00484	0.00328	0.00439	0.00363	0.00324		
Zinc	mg/L	0.046	0.017	0.031	0.005	0.009	0.036	0.011	0.006	0.022	0.002	0.006	0.006	0.009	<0.0040	<0.0020	<0.0020	<0.0020	0.0051	0.0088	<0.0010	<0.0010	0.0098	<0.0010	<0.0010		
<b>Routine Water</b>																											
Ion Balance	%	97	103	103	94	103	91.7	102	102	96.7	103	103	97.4	95.5	92.5	93.9	93.5	95.8	101	109	98.6	100	104	103	109		
Bicarbonate	mg/L	338	315	271	315	310	423	520	193	361	335	270	386	408	348	327	357	345	429	306	307	396	566	451	464		
Chloride	mg/L	138.0	125.0	146.0	203.0	175.0	267.0	436	192	245	182	166	153	233	384	160	117	205	218	145	149	137	203	237	182		
Carbonate	mg/L	<5	7	27	15	16	<5	<5	15	<5	<5	<5	<5	9	6.1	11.1	12.8	9.3	11.6	25.2	<5.0	8.4	<5.0	7.9	6.7		
Conductivity (EC)	uS/cm	1200	1210	1020	1530	1380	1640	2860	1210	1520	1130	1120	1410	1620	1980	1280	1150	1420	1500	1130	1330	1230	1660	1780	1490		
Calcium	mg/L	43.9	43.1	36.1	48.7	47.2	55.8	70.9	63.6	53.2	48.9	46.8	55.9	62.9	72.9	42.1	46.3	43.7	55.7	50.2	53.0	49.4	58.5	67.2	53.7		
Potassium	mg/L	12.5	14.5	15.5	14.7	14.6	16.3	31.5	14.4	14.3	10	11.7	13.9	16.4	19.2	13.8	13.4	20.2	21.8	14.9	16.3	16.8	20.6	19.6	19.1		
Magnesium	mg/L	19.3	18.4	18.3	21.9	19.0	22.3	55.5	21.7	19.7	17.7	16.0															

Table D.18: Chemical Analytical Results

Sample ID:	Norgaard D.1																											
Site Number:	18																											
Date Sampled:	Units	17-Oct-1996	3-Oct-1997	8-Oct-1998	20-Oct-1999	11-Oct-2000	5-Oct-2001	9-Oct-2002	16-Oct-2003	14-Oct-2004	21-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	19-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	60	90	100	120	90	110	180	200	110	120	99	<5	109	131	82.8	119	109	106	155	81	80	78	35	158			
Ammonia-N	mg/L	<0.05	<0.05	0.09	<0.05	<0.05	<0.05	<0.05	<0.05	0.07	<0.05	<0.05	0.06	<0.05	3.85	<0.050	<0.050	<0.050	<0.050	0.062	1.31	0.553	<0.050	<0.050	<0.050			
Total Kjeldahl Nitrogen	mg/L	4	1.8	3.8	3.6	2.4	4.7	4.9	3.2	3	3.4	2.7	3.1	3.5	7.86	2.52	4.03	3.42	2.57	2.98	3.14	2.67	2.74	1.71	4.19			
Total Organic Carbon	mg/L	24	32	35	45	32	37	62	45	66	47	35	54	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit												38	54.4	31.3	34.5	37	34.5	29.5	29.9	27.7	78	21.6	39.2			
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0019	0.0081	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050			
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071		
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10		
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10		
F2 - (C10-C16)	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.13	<0.10	<0.10		
<b>Dissolved Metals</b>																												
Aluminum	mg/L	Not required under previous permit												<0.04	0.14	<0.010	<0.010	<0.010	0.022	<0.01	0.0056	0.0086	0.0025	0.0034	0.0035			
Antimony	mg/L	<0.0004	0.0006	0.0006	<0.0004	0.0005	0.0004	0.0007	0.0011	0.0015	0.001	0.0010	0.0021	<0.002	<0.0080	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	<0.00020	0.00012	0.00011	0.00027	0.00021			
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.00107	0.00247
Barium	mg/L	0.111	0.087	0.084	0.101	0.1	0.133	0.217	0.038	0.048	0.056	0.105	0.145	0.1	0.168	0.0779	0.086	0.0961	<0.0030	0.0947	0.096	0.0642	0.0801	0.0924	0.0716			
Beryllium	mg/L	Not required under previous permit												<0.004	<0.010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010		
Boron	mg/L	Not required under previous permit												<0.2	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	0.077	0.032	0.024	0.053	
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0004	<0.0010	<0.000050	<0.000050	<0.0010	<0.000050	<0.00005	<0.000010	<0.000050	<0.000050	0.000018	<0.000010			
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	0.011	<0.005	<0.005	<0.005	0.013	0.012	<0.02	<0.0080	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.00020	0.00015	0.00013	<0.0002	<0.00020			
Cobalt	mg/L	<0.002	<0.002	0.019	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.008	0.0049	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.00045	0.00033	0.00048	0.0101	0.00040			
Copper	mg/L	0.003	0.04	0.005	<0.001	0.001	0.004	0.017	0.005	0.002	<0.001	0.001	0.002	<0.004	<0.012	0.0037	<0.0010	<0.0010	<0.0010	<0.0010	<0.00040	0.00022	0.00031	0.00127	0.00049			
Iron	mg/L	<0.005	0.265	0.243	0.469	0.063	0.377	4.04	0.372	0.098	0.067	0.136	0.646	0.011	<0.010	0.025	0.034	0.024	0.022	0.073	0.033	0.129	0.081	0.064	0.111			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.0005	<0.0020	<0.00010	<0.00010	<0.0050	<0.00010	<0.0001	<0.00010	<0.000050	<0.000050	<0.00010	<0.00010			
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0698	0.0423	
Manganese	mg/L	Not required under previous permit												0.165	0.378	0.0021	0.01	<0.0020	0.411	0.0039	0.0758	0.00168	0.229	5.26	0.00533			
Mercury	mg/L	0.0002	<0.0002	<0.0002	0.0002	0.0002	<0.0002	0.0004	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050			
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.02	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00088	0.000341	0.000524	0.00304	0.00095			
Nickel	mg/L	0.003	<0.002	<0.002	0.004	0.003	<0.002	0.011	0.003	<0.002	0.011	0.003	<0.002	0.003	0.06	0.0034	0.0025	0.0039	0.0043	0.0035	0.0057	0.00333	0.00448	0.0113	0.0042			
Selenium	mg/L	Not required under previous permit												0.003	0.0093	<0.00040	<0.00040	<0.00080	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	0.000118	0.000092	0.00013	0.00018	
Silver	mg/L	Not required under previous permit												<0.0004	<0.0020	<0.00010	<0.00010	<0.0050	<0.00010	<0.00010	<0.00010	<0.00010	<0.000020	<0.000020	<0.000020	<0.000020		
Thallium	mg/L	Not required under previous permit												<0.0004	<0.0010	<0.00010	<0.00010	<0.050	<0.00010	<0.00010	<0.000020	<0.000010	<0.000010	0.000022	<0.000020	<0.000020		
Tin	mg/L	Not required under previous permit												<0.2	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.00020	<0.00010	<0.00020	<0.00020	
Titanium	mg/L	Not required under previous permit												<0.004	<0.0060	<0.0010	<0.0010	<0.0010	0.0019	<0.001	<0.00060	<0.00072	0.00033	<0.00060	<0.00060	<0.00060		
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.0197	0.000974
Vanadium	mg/L	Not required under previous permit												0.009	<0.0020	0.0014	0.0012	0.0038	0.0032	0.0011	0.0032	0.0016	0.00151	<0.0010	0.0013	0.0012		
Zinc	mg/L	0.021	0.051	0.025	0.002	0.001	0.041	0.026	0.006	0.037	0.002	0.01	0.034	<0.008	<0.020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.0085	<0.0020	0.0013	0.0012	0.0064	<0.0020		
<b>Routine Water</b>																												
Ion Balance	%	101	103	99	95	102	103	100	104	98.7	98.2	99.9	95.3	99.5	95.2	94.5	95.6	98	99.0	108	99.2	104	97.9	109	107			
Bicarbonate	mg/L	537	639	420	598	551	607	567	228	480	747	602	778	820	718	603	537	532	522	414	455	417	573	558	784			
Chloride	mg/L	268.0	375.0	339.0	465.0	343.0	544.0	881	579	586	520	443	514	595	756	296	181	283	242	155	228	156	265	688	285			
Carbonate	mg/L	<5	<5	<5	18	<5	<5	44	21	<5	10	<5	6	32	<5.0	<5.0	26.3	12.5	32.7	21.1	6.4	11.2	10.3	<5.0	<5.0			
Conductivity (EC)	uS/cm	2250	2510	2140	2770	2410	2890	4120	2890	3080	2790	2350	3030	3230	3820	1800	1560	1790	1600	1250	1740	1180	1800	3810	2120			
Calcium	mg/L	93.2	91.1	60.6	64.6	96.8	109	57.7	113	83.7	96.8	90.8	98.7	87.3	102	77.3	64.9	63.9	63.1	69.4	79.9	59.9	79.6	298	109			
Potassium	mg/L	21.3	26.1	23.9	23.9	24.9	31.5	36.9	38.1	30.3	31.5	25.7	32	32.6	40	21.5	22.1	28.8	22.5	19.4	22.9	19.2	20	26.1	26.1			
Magnesium	mg/L	49.7	57.5	39.5	48.2	49.0	62.4	66.5	91.7	57.9	58.9	48.4	59.5															



Table D.19: Chemical Analytical Results

Sample ID:		Winsnes D.1																										
Site Number:		19																										
Date Sampled:	Units	16-Oct-1996	7-Oct-1997	9-Oct-1998	19-Oct-1999	10-Oct-2000	4-Oct-2001	9-Oct-2002	16-Oct-2003	14-Oct-2004	21-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	19-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	60	70	70	90	100	110	100	80	80	54	65	68	65	101	85.8	68	420	79	94	92	69	83	92	75			
Ammonia-N	mg/L	<0.05	<0.05	0.09	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.105	0.09	<0.050	<0.050	0.084	0.059	0.069	<0.05	1.08	0.058	<0.050			
Total Kjeldahl Nitrogen	mg/L	3.1	2.5	2.6	2.5	3.4	6.2	4.1	3.6	2.1	1.7	2.4	2.7	3.8	4.48	4.36	2.79	3.66	3.62	3.48	3.76	3.52	4.11	4.01	2.52			
Total Organic Carbon	mg/L	25	28	28	27	31	36	40	37	30	23	24	24	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit												23	31.9	29.7	25	33.6	28.2	26.4	28.2	27	83	27.3	24.2			
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0026	0.0077	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071		
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	0.12	<0.13	<0.10	<0.10	
<b>Dissolved Metals</b>																												
Aluminium	mg/L	Not required under previous permit												<0.01	<0.010	0.025	<0.010	<0.010	<0.010	<0.01	0.0013	<0.010	0.0038	0.0085	0.0017			
Antimony	mg/L	<0.0004	0.0002	0.0009	<0.0004	0.0006	0.0008	0.0006	0.0014	0.0014	0.0015	0.0021	0.0011	0.0007	0.00045	0.0004	<0.00040	<0.00080	<0.00040	<0.0004	0.00029	0.00021	0.00023	0.00030	0.0002			
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.00574	0.00471	
Barium	mg/L	0.036	0.055	0.049	0.051	0.053	0.042	0.105	0.04	0.011	0.022	0.043	0.081	0.04	0.0418	0.0425	0.0238	0.0149	0.0257	0.0589	0.0508	0.0633	0.0359	0.0623	0.0412			
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	Not required under previous permit												<0.05	0.051	0.051	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	0.037	0.034	0.037	
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	<0.000050	<0.000050	<0.00010	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050	0.0000168	<0.000050			
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.008	0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00011	<0.00010			
Cobalt	mg/L	<0.002	0.002	0.021	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.00033	0.00022	0.00065	0.00055			
Copper	mg/L	0.002	<0.001	0.009	0.002	0.003	0.006	0.009	0.006	0.003	0.001	0.002	0.002	<0.001	<0.0010	0.0059	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	0.00021	0.00033	0.00043	0.00027			
Iron	mg/L	<0.005	0.291	0.200	0.460	0.342	0.081	0.991	0.369	0.203	0.101	0.211	0.76	0.005	0.022	<0.010	0.032	0.011	0.014	0.024	0.014	0.019	0.054	0.038	0.011			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	<0.000050	0.000055	0.000061			
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0279	0.0235	
Manganese	mg/L	Not required under previous permit												0.006	0.0341	0.0022	0.0025	0.0037	0.0029	0.0053	0.00179	0.00088	0.276	0.0371	0.00135			
Mercury	mg/L	0.0003	0.0008	<0.0002	<0.0002	<0.0002	<0.0002	0.0003	0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	0.000006	0.000058	<0.000050	<0.000050		
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.00036	0.000688	0.00054	0.00052	0.000602			
Nickel	mg/L	<0.002	<0.002	0.012	0.003	0.004	<0.002	0.006	0.004	<0.002	0.002	0.005	0.006	<0.002	0.0026	<0.0020	0.002	<0.0020	<0.0020	0.0025	0.00178	0.00214	0.0035	0.00316	0.00287			
Selenium	mg/L	Not required under previous permit												0.0007	0.00049	<0.00040	<0.00040	<0.00080	<0.00040	<0.00040	0.000194	0.000232	0.00021	0.000206	0.000204			
Silver	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	
Thallium	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	
Titanium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.00159	0.00116
Vanadium	mg/L	Not required under previous permit												0.004	0.0041	0.0018	<0.0010	0.001	<0.0010	0.0015	0.00172	0.00107	0.00167	0.00163	0.00094			
Zinc	mg/L	0.006	0.025	0.057	0.003	0.017	0.048	0.008	0.008	0.074	0.002	0.008	0.008	0.03	<0.0020	<0.0020	<0.0020	0.0024	<0.0020	0.0058	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010			
<b>Routine Water</b>																												
Ion Balance	%	98	110	108	103	109	90.3	101	106	105	107	106	97.7	98	100	106	97.1	92.7	103	104	93.2	100	96.3	107	104			
Bicarbonate	mg/L	483	445	475	485	464	457	635	361	276	285	315	366	319	366	362	370	348	450	420	408	446	563	469	416			
Chloride	mg/L	20.7	20.0	17.0	21.0	21.0	25.0	32	29	29	17	18	15	19	17.9	19.4	15	17.7	19.8	23.5	27.2	38.3	59.3	58.7	71.6			
Carbonate	mg/L	<5	<5	<5	17	25	60	44	49	75	13	7	12	46	52.4	32	11	46	11.3	30.9	18.2	9.3	<5.0	<5.0	10.8			
Conductivity (EC)	uS/cm	1270	1230	1100	1270	1320	1520	1850	1950	2400	1530	1280	1030	1080	1150	1180	914	1000	1020	1040	971	997	1190	1070	1060			
Calcium	mg/L	31.5	32.4	32.3	27.8	26.3	20.8	23.4	32.9	31.9	40.2	39.3	42.2	19.1	19.5	20.4	24.5	15.7	24.4	27.5	19.6	32.4	43.8	26.8	39.2			
Potassium	mg/L	8.8	10.6	10.3	11.1	10.8	11	13.4	13.5	11.9	10.9	11.6	11	11	13.2	13.9	12.8	12.7	14.2	13.6	12.7	13.7	16.4	15.8	15.7			
Magnesium	mg/L	16.6	17.5	17.8	17.7	18.9	19.5																					

Table D.20: Chemical Analytical Results

Sample ID:		Winsnes D.2																										
Site Number:		20																										
Date Sampled:	Units	16-Oct-1996	7-Oct-1997	9-Oct-1998	26-Nov-1999	10-Oct-2000	4-Oct-2001	9-Oct-2002	16-Oct-2003	14-Oct-2004	21-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	19-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019			
Chem. O <sub>2</sub> Demand	mg/L	40	50	50	60	70	70	70	50	60	45	56	65	62	80.7	49.6	56	61	65	49	54	81	77	61	79			
Ammonia-N	mg/L	<0.05	0.06	<0.05	0.14	<0.05	0.11	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.050	0.06	<0.050	<0.050	0.056	<0.05	0.139	0.618	0.67	<0.050	0.824			
Total Kjeldahl Nitrogen	mg/L	0.9	0.9	1.5	1.6	1.9	2.8	1.5	1.6	1.3	1.6	1.7	1.8	2	2.99	1.5	1.32	1.74	2.29	1.54	1.51	3.93	2.06	1.73	3.35			
Total Organic Carbon	mg/L	17	18	21	17	22	24	26	28	18	19	22	25	-	-	-	-	-	-	-	-	-	-	-	-			
Dissolved Organic Carbon	mg/L	Not required under previous permit												20	27.8	18.7	22	21.5	20.2	17.9	20.0	20.9	77	21.5	25.3			
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0018	0.0052	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																												
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 - (C10-C16)	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.13	<0.10	<0.10	<0.10	
<b>Dissolved Metals</b>																												
Aluminium	mg/L	Not required under previous permit												<0.01	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.01	<0.010	0.0018	0.004	0.0046	0.0052	
Antimony	mg/L	<0.0004	<0.0002	0.0005	<0.0004	<0.0004	0.0005	<0.0004	0.0009	0.0011	0.0006	0.0012	0.0015	<0.0004	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00013	<0.00010	0.00013	0.00016	0.00013			
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.00218	0.00283	
Barium	mg/L	0.086	0.179	0.112	0.17	0.118	0.087	0.06	0.128	0.096	0.095	0.132	0.136	0.116	0.189	0.134	0.134	0.107	0.115	0.103	0.119	0.104	0.0911	0.104	0.0997			
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	0.039	0.04	0.023	0.033	0.028	
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.000050	0.000661	<0.000050	<0.0010	<0.000050	<0.00005	<0.000050	<0.000050	<0.000050	0.0000237	0.0000063			
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	<0.00010	<0.00010	<0.00010	0.00013	0.00012			
Cobalt	mg/L	<0.002	0.002	0.023	<0.005	<0.005	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.002	0.00025	0.00012	0.0004	0.00053	0.00031			
Copper	mg/L	0.002	<0.001	0.007	0.001	0.003	0.002	0.003	0.002	<0.001	0.001	<0.001	<0.001	<0.001	<0.0010	0.00033	<0.0010	<0.0010	<0.0010	<0.001	0.00022	0.00027	0.00037	0.00027	0.00026			
Iron	mg/L	<0.005	0.771	1.490	0.065	0.765	0.748	0.308	0.818	0.983	1.29	0.927	1.96	0.057	0.095	0.416	0.152	0.013	0.444	0.047	<0.010	0.878	0.526	0.185	0.815			
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00010	<0.00010	<0.00010	<0.00050	<0.00010	<0.0001	<0.000050	0.000111	0.000067	0.000071				
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0237	0.0178	
Manganese	mg/L	Not required under previous permit												<0.001	0.0306	0.003	<0.0020	<0.0020	<0.0020	<0.002	0.00053	0.00173	0.104	0.0629	0.00851			
Mercury	mg/L	0.0002	0.0006	<0.0002	<0.0002	<0.0002	<0.0002	0.0003	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.0000050	<0.0000050	<0.0000050	<0.0000050	<0.0000050			
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	0.0015	0.000584	0.00068	0.00061	0.00039			
Nickel	mg/L	<0.002	0.002	0.013	0.007	0.007	<0.002	0.004	0.005	<0.002	0.002	0.005	0.005	0.005	0.0093	0.0045	0.0032	0.0031	0.0030	0.0031	0.00341	0.00267	0.00373	0.00305	0.00293			
Selenium	mg/L	Not required under previous permit												<0.0004	<0.00040	<0.00040	<0.00040	<0.00080	<0.00040	<0.00040	<0.00040	<0.0004	0.000186	0.000212	0.00019	0.00018	0.000188	
Silver	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.00050	<0.00010	<0.00010	<0.00010	<0.00010	<0.000010	<0.000010	<0.000010	<0.000010	<0.000010	
Thallium	mg/L	Not required under previous permit												<0.0001	<0.00010	<0.00010	<0.00010	<0.050	<0.00010	<0.00010	<0.00010	<0.00010	<0.000010	<0.000010	<0.000010	0.000024	<0.000010	
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.00010	<0.00010	<0.00010	<0.00010	
Titanium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.00030	<0.00030	0.00074	0.00053	0.00095	
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.000372	0.000199
Vanadium	mg/L	Not required under previous permit												<0.001	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.00050	<0.00050	0.00059	0.00071	0.00095	
Zinc	mg/L	0.005	0.022	0.135	0.021	0.028	0.038	0.007	0.003	0.044	0.007	0.004	0.01	0.003	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	0.0073	<0.0010	<0.0010	0.0027	<0.0010	<0.0010			
<b>Routine Water</b>																												
Ion Balance	%	99	106	104	101	99.5	101	103	103	98.5	105	109	98.7	97.5	96.3	97.6	105	93.9	107	103	102	109	91.1	108	106			
Bicarbonate	mg/L	262	273	273	307	272	286	173	293	310	277	299	315	323	340	303	319	295	266	245	255	227	294	269	277			
Chloride	mg/L	15.4	15.1	9.3	17.0	15.0	19.0	21	14	13	10	12	13	17	15.8	12.4	12.7	23.4	14.4	13.7	15.6	19.8	38.5	37.6	43.9			
Carbonate	mg/L	<5	<5	<5	<5	<5	<5	56	<5	<5	<5	<5	<5	<5	<5.0	<5.0	5.4	6.5	6.3	7.6	<5.0	<5.0	<5.0	<5.0				
Conductivity (EC)	uS/cm	514	557	511	591	479	523	514	482	518	501	529	542	552	567	538	567	515	484	465	490	431	634	569	574			
Calcium	mg/L	27.3	34.5	36.2	34.1	34.2	26.7	11.7	34.6	32.2	37.6	38.3	41.2	38.3	34.9	34	40.3	23.7	29.8	32	31.6	32.7	39.1	35.2	43.6			
Potassium	mg/L	11.5	11.5	11.2	13.3	12.2	13	15.2	14.5	14.4	12.9	14.2	13.8	14.4	16.6	15.6	17.1	15.7	15.4	14.3	16.7	13.6	15.8	17.8				

Table D.21: Chemical Analytical Results

Sample ID:		Winsnes D.3																											
Site Number:		21																											
Date Sampled:	Units	16-Oct-1996	7-Oct-1997	9-Oct-1998	19-Oct-1999	10-Oct-2000	4-Oct-2001	9-Oct-2002	16-Oct-2003	15-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019				
Chem. O <sub>2</sub> Demand	mg/L	60	80	160	110	110	260	E m p t y	90	110	54	85	64	106	251	97	96	128	116	108	108	81	97	112	93				
Ammonia-N	mg/L	0.06	<0.05	1.45	0.3	<0.05	2.78		<0.05	<0.05	<0.05	0.15	1.47	0.34	1.02	0.083	<0.050	0.225	<0.050	<0.05	0.639	<0.05	0.059	0.090	<0.050				
Total Kjeldahl Nitrogen	mg/L	5.5	3.2	10.5	5.2	4	15.8		2.9	3.4	1.7	3.1	3.8	4.1	13.8	4.71	3.08	4.2	4.03	3.81	5.34	2.92	3.91	4.39	2.75				
Total Organic Carbon	mg/L	26	32	44	28	39	71		49	38	20	29	29	-	-	-	-	-	-	-	-	-	-	-	-				
Dissolved Organic Carbon	mg/L	Not required under previous permit							Not required under previous permit							33	82.1	36.9	31	39	33.1	32.1	37.9	26.8	97	32.4	29.5		
Phenols	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	-	-	-	0.0018	0.0093
<b>BTEX, F1 (C6-C10) and F2(&gt;C10-C16)</b>																													
Benzene	mg/L	Not required under previous permit							Not required under previous permit							<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Toluene	mg/L	Not required under previous permit							Not required under previous permit							<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Ethylbenzene	mg/L	Not required under previous permit							Not required under previous permit							<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Xylenes (m & p)	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit							Not required under previous permit							<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071
Styrene	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C6-C10)	mg/L	Not required under previous permit							Not required under previous permit							<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F1 (C6-C10) - BTEX	mg/L	Not required under previous permit							Not required under previous permit							<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
F2 - (C10-C16)	mg/L	Not required under previous permit							Not required under previous permit							<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.13	<0.10	<0.10	<0.10
<b>Dissolved Metals</b>																													
Aluminum	mg/L	Not required under previous permit							Not required under previous permit							<0.01	0.034	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	0.0405	0.002	0.003	0.0177	0.0071	
Antimony	mg/L	0.0008	<0.0002	0.0014	<0.0004	0.001	0.001	0.0017	0.0013	0.0014	0.0013	0.001	0.001	0.0008	<0.0016	<0.0040	<0.0040	<0.0080	0.00044	0.00054	0.00093	0.00031	0.00044	0.00061	0.00024				
Arsenic	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	-	-	0.00898	0.00575	
Barium	mg/L	0.109	0.011	0.155	0.159	0.105	0.175	0.006	0.008	0.013	0.12	0.094	0.091	0.109	0.103	0.0553	0.111	0.101	0.0732	0.134	0.101	0.107	0.114	0.0766					
Beryllium	mg/L	Not required under previous permit							Not required under previous permit							<0.001	<0.0020	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	
Boron	mg/L	Not required under previous permit							Not required under previous permit							<0.05	<0.050	<0.050	0.067	0.077	0.073	0.079	0.077	0.094	<0.020	0.021	0.05		
Cadmium	mg/L	<0.001	0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.00020	<0.00050	<0.00050	<0.0001	<0.0001	<0.00020	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	0.000074	<0.000050	<0.00010	0.000199	<0.000050				
Chromium	mg/L	0.008	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050				
Cobalt	mg/L	0.003	0.003	0.022	<0.002	0.002	0.003	<0.002	<0.002	<0.002	<0.002	<0.002	0.001	<0.0024	0.0031	<0.0010	0.0016	<0.0010	0.0012	0.00236	0.00132	0.00141	0.00202	0.00071					
Copper	mg/L	0.006	<0.001	0.008	0.001	0.006	0.01	0.007	<0.005	<0.005	<0.005	<0.005	0.007	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050					
Iron	mg/L	1.320	1.090	2.500	1.110	0.628	3.690	0.146	0.163	0.051	0.083	0.508	0.015	0.062	0.011	0.02	0.025	0.022	0.047	0.022	0.011	0.03	0.037	0.038					
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0001	<0.00040	<0.00010	<0.00010	<0.00010	<0.00010	0.0001	<0.00050	<0.00050	<0.00010	0.00006	<0.00050					
Lithium	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	0.0595	0.0419			
Manganese	mg/L	Not required under previous permit							Not required under previous permit							0.003	0.0538	<0.0020	<0.0020	<0.0020	0.0593	0.0142	0.00143	0.00076	0.0129	0.00528	0.00437		
Mercury	mg/L	0.0003	<0.0004	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.000050	<0.000050	<0.000050	<0.000050					
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.007	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	0.0074	0.0041	0.0053	0.0117	0.00722	0.0057	0.0072	0.00398		
Nickel	mg/L	0.007	<0.002	0.027	0.008	0.014	0.008	0.007	<0.002	<0.002	0.004	0.004	0.006	0.0063	0.0058	0.0043	0.0074	0.0041	0.0053	0.0117	0.00722	0.0057	0.0072	0.00398					
Selenium	mg/L	Not required under previous permit							Not required under previous permit							0.0014	0.003	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.000359	0.000239	0.00027	0.000366	0.000201		
Silver	mg/L	Not required under previous permit							Not required under previous permit							<0.0001	<0.00040	0.00032	<0.00010	<0.00010	<0.00010	<0.00010	0.00001	<0.00010	<0.00010	<0.00010	<0.00010		
Thallium	mg/L	Not required under previous permit							Not required under previous permit							<0.0001	<0.00020	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Tin	mg/L	Not required under previous permit							Not required under previous permit							<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050		
Titanium	mg/L	Not required under previous permit							Not required under previous permit							0.003	<0.0012	<0.0010	<0.0010	0.0012	<0.0010	0.002	0.00198	<0.00030	0.00132	0.00333	0.00134		
Uranium	mg/L	Not required under previous permit							Not required under previous permit							-	-	-	-	-	-	-	-	-	-	0.00437	0.0021		
Vanadium	mg/L	Not required under previous permit							Not required under previous permit							0.006	0.007	0.002	0.0025	0.0098	0.0019	0.0052	0.00154	0.0016	0.0048	0.00433	0.0018		
Zinc	mg/L	0.016	0.022	0.049	0.004	0.063	0.047	0.009	0.06	0.006	0.003	0.017	0.016	0.006	<0.0020	<0.0020	<0.0020	<0.0020	0.0053	<0.0010	0.0014	<0.0020	<0.0010	<0.0010					
<b>Routine Water</b>																													
Ion Balance	%	109	109	109	97	107	92.2	107	103	104	103	101	96.5	106	107	101	97.4	106	107	105	98.9	105	98.9	105	106				
Bicarbonate	mg/L	219	285	336	357	428	623	72	693	381	450	455	352	386	353	446	419	375	292	375	396	504	429	435					
Chloride	mg/L	81.9	112.0	156.0	158.0	152.0	248.0	318	294	76	101	133	213	266	270	156	222	209	224	216	238	357	304	244					
Carbonate	mg/L	55	15	<5	7	34	<5	114	14	15	28	<5	69	70.5	30	21.1	48.3	38.8	59.6	9.3	<5.0	10.9	<5.0	<5.0					
Conductivity (EC)	uS/cm	793	886	992	1210	1310	1640	2950	2620	832	1140	1180	1380	1620	1880	1350	1530	1410	1400	1500	1420	2020	1710	1580					
Calcium	mg/L	19.8	32.4	27.9	34	29.1	26.6	57.6	105	46.6	45.4	50.4	39.9	36.7	54.4	54.1	39.3	38.2	29.7	29.8	52.4	52.3	46.7	69.8					
Potassium	mg/L	20.6	22.4	22.5	24.5	25.8	26.4	67.3	73	26.1	32.2	25.6	23.3	33.1	38.6	28.8	30.4	28.1	26.1	28.5	27.8	30.3	28.5	22.6					
Magnesium	mg/L	18.9	19.3	22.8	28.2	24.6	27.1	158	133.0	34.6	43.9	35.4	32.9																

Table D.22: Chemical Analytical Results

Sample ID:		Winsnes D.4																											
Site Number:		22																											
Date Sampled:	Units	16-Oct-1996	7-Oct-1997	9-Oct-1998	19-Oct-1999	10-Oct-2000	4-Oct-2001	9-Oct-2002	16-Oct-2003	15-Oct-2004	20-Oct-2005	13-Oct-2006	3-Oct-2007	17-Oct-2008	28-Oct-2009	18-Oct-2010	12-Oct-2011	16-Oct-2012	8-Oct-2013	15-Oct-2014	14-Oct-2015	5-Oct-2016	20-Oct-2017	16-Oct-2018	29-Oct-2019				
Chem. O <sub>2</sub> Demand	mg/L	70	70	100	90	130	150	180	140	150	83	97	86	95	138	88.6	115	116	78	102	96	70	112	101	535				
Ammonia-N	mg/L	0.06	<0.05	1.58	<0.05	<0.05	0.52	<0.05	<0.05	0.75	<0.05	<0.05	0.06	3.11	0.917	0.399	<0.050	0.052	<0.050	<0.05	0.070	<0.050	0.120	0.055	0.075				
Total Kjeldahl Nitrogen	mg/L	4.5	3	5.5	3.4	3.7	8.2	5.4	5.9	9.3	2.9	2.9	2.6	6.1	8.08	3.47	<0.050	4.36	2.65	3.27	2.48	2.33	3.4	3.57	17.0				
Total Organic Carbon	mg/L	29	25	34	28	46	61	68	59	55	32	33	33	-	-	-	-	-	-	-	-	-	-	-	-				
Dissolved Organic Carbon	mg/L	Not required under previous permit												32	47	34.8	32	38.9	32.3	30.4	33.2	25.3	112	34.2	31.2				
Phenols	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.0012	0.0067	
<b>BTEX, F1 (C6-C10) and F2 (&gt;C10-C16)</b>																													
Benzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Toluene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Ethylbenzene	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.0005	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050		
Xylenes (m & p)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050	
Xylene (o)	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
Xylenes	mg/L	Not required under previous permit												<0.0005	<0.00050	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	<0.00071	
Styrene	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.00050
F1 (C <sub>6</sub> -C <sub>10</sub> )	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	
F1 (C <sub>6</sub> -C <sub>10</sub> ) - BTEX	mg/L	Not required under previous permit												<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.1	<0.10	<0.1	<0.10	<0.10	<0.10	<0.10	<0.10	
F2 - (C <sub>10</sub> -C <sub>16</sub> )	mg/L	Not required under previous permit												<0.05	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.13	<0.10	<0.10	<0.10	
<b>Dissolved Metals</b>																													
Aluminium	mg/L	Not required under previous permit												0.02	0.062	<0.010	<0.010	<0.010	<0.010	<0.01	<0.010	0.0017	0.0114	0.0455	0.0165				
Antimony	mg/L	<0.0004	<0.0004	0.0009	<0.0004	0.0006	0.0009	<0.0004	0.0015	0.0015	0.0016	0.0016	0.0022	<0.0004	<0.0016	<0.00040	<0.00040	<0.00080	<0.00040	<0.0004	0.00033	0.00017	0.00026	0.00029	0.00019				
Arsenic	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	-	0.00555	0.0057	
Barium	mg/L	0.058	0.044	0.063	0.083	0.058	0.052	<0.003	0.089	0.061	0.01	0.022	0.014	0.084	0.0693	0.0728	0.0302	0.0782	0.129	0.0722	0.115	0.0559	0.0462	0.0659	0.0437				
Beryllium	mg/L	Not required under previous permit												<0.001	<0.0020	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010		
Boron	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.05	0.041	0.036	0.031	0.033				
Cadmium	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.00020	<0.000050	<0.000050	<0.0010	<0.000050	<0.00005	<0.000050	<0.000050	<0.000050	0.0000172	<0.000050				
Chromium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	<0.00010	<0.00010	<0.00010	0.00012	0.00014				
Cobalt	mg/L	<0.002	0.005	0.019	<0.002	<0.002	<0.002	<0.002	0.003	<0.002	<0.002	<0.002	<0.002	<0.002	<0.0020	<0.0020	<0.0020	<0.0020	<0.0020	<0.002	0.00056	0.00027	0.00085	0.00099	0.00101				
Copper	mg/L	0.002	<0.001	0.007	0.002	0.007	0.009	<0.001	0.006	0.003	<0.001	<0.001	<0.001	<0.001	<0.0024	0.0038	<0.0010	<0.0010	<0.0010	<0.001	0.00043	0.00052	0.0008	0.00118	0.00101				
Iron	mg/L	0.612	0.807	1.140	1.810	0.373	0.639	0.065	3.48	0.815	0.3	0.602	0.581	0.041	0.053	0.033	0.018	0.06	<0.010	0.027	0.011	0.021	0.088	0.130	0.898				
Lead	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.0001	<0.00040	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.000050	<0.000050	0.000068	0.00012	0.000139				
Lithium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.0158	0.013		
Manganese	mg/L	Not required under previous permit												0.404	0.0068	0.0143	0.0326	0.0046	<0.0020	0.003	0.0099	0.00054	0.0158	0.0104	0.410				
Mercury	mg/L	0.0003	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	0.0003	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.000050	<0.000050	<0.000050	<0.000050	<0.000050				
Molybdenum	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.005	0.00373	0.00197	0.00135	0.00183	0.000865				
Nickel	mg/L	0.002	0.003	0.018	0.006	0.015	<0.002	<0.002	0.011	0.006	0.002	0.005	0.003	0.006	0.0051	0.0051	0.0029	0.004	0.0058	0.0049	0.00578	0.00391	0.00359	0.00364	0.00233				
Selenium	mg/L	Not required under previous permit												0.0011	0.0021	<0.00040	<0.00040	<0.00080	<0.00040	<0.00040	<0.00040	0.000293	0.000227	0.000222	0.000252	0.000201			
Silver	mg/L	Not required under previous permit												<0.0001	<0.00040	<0.00010	<0.00010	<0.00010	<0.00010	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010			
Thallium	mg/L	Not required under previous permit												<0.0001	<0.00020	<0.00010	<0.00010	<0.050	<0.00010	<0.0001	<0.00010	<0.00010	<0.00010	<0.00010	0.000017	<0.00010			
Tin	mg/L	Not required under previous permit												<0.05	<0.050	<0.050	<0.050	<0.050	<0.050	<0.05	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010	<0.00010			
Titanium	mg/L	Not required under previous permit												0.001	<0.0012	<0.0010	<0.0010	<0.0010	<0.0010	<0.001	<0.00030	<0.00030	<0.00067	0.000854	0.00139				
Uranium	mg/L	Not required under previous permit												-	-	-	-	-	-	-	-	-	-	-	-	0.00247	0.000959		
Vanadium	mg/L	Not required under previous permit												0.003	0.0049	0.0011	<0.0010	0.0026	<0.0010	<0.001	<0.00050	<0.00050	0.00144	0.00229	0.0018				
Zinc	mg/L	0.11	0.016	0.05	0.015	0.246	0.045	0.007	0.014	0.243	0.003	0.005	0.012	0.004	<0.0040	<0.0020	<0.0020	<0.0020	<0.0020	0.0086	<0.0010	0.001	0.0015	<0.0010	0.0012				
<b>Routine Water</b>																													
Ion Balance	%	109	107	103	105	109	92	102	104	102	101	103	99.6	95.6	105	104	96.5	98.1	110	107	100	107	101	110	107				
Bicarbonate	mg/L	253	287	284	223	591	526	536	387	509	347	336	322	384	288	313	341	311	300	261	248	216	350	290	264				
Chloride	mg/L	135.0	105.0	183.0	181.0	134.0	189.0	235	200	207	98	101	83	146	156	242	173	241	240	246	204	170	238	222	246				
Carbonate	mg/L	17	41	<5	16	<5	64	124	90	47	<5	13	<5	<5	38.2	11.9	<5.0	14.4	8.8	8.3	<5.0	<5.0	<5.0	<5.0					
Conductivity (EC)	uS/cm	884	934	1000	1050	1490	1660	1990	1520	1550	773	905	787	1050	1070	1350	1130	1310	1280	1270	1190	889	1330	1190	1230				
Calcium	mg/L	28.1	34	34	29.9	32.4	22.2	25.7	34.2	26.4	21.9	22.5	25.5	28.9	25.8	31.5	29.8	27.2	34.1	27.9	29.4	27.9	40.2	37.5	45.1				
Potassium	mg/L	24.4	19.7	25.6	22.8	26	24.6	27.7	29.9	27.7	18.8	24.1	21.2	23.1	25.7	29.7	25.8	28.1	30.6	28.1	25.9	22.9	32.3	32.8	26				
Magnesium	mg/L	16.8																											

## APPENDIX E

### SELECTED SITE PHOTOGRAPHS



**Photo 1:** Dugout 13, a typical dugout in the monitoring program. Taken October 16, 2023.



**Photo 2:** Dugout 19, a typical dugout in the monitoring program. Taken October 19, 2022.